SIMULATED DATA. Street geometry is real; every pipe, pavement, break and cost figure below is simulated. Results are model outputs under stated assumptions, not predictions or a recommendation for real streets.

Dig Once: Capital Plan Recommendation

SIMULATED DATA · 2026–2035

1570 projects funded Simulated	**$163,779,447** total funded Simulated	**1453** street openings Simulated	**117** shared digs Simulated
$6,890,019 dig savings from shared digs Simulated	**$140,140,282** net cost after financing Simulated	**$16,532,473** loan interest over loan lives Simulated	**47** funded, needs engineering review Simulated

Isolated baseline (separate departments, fixed budget split, same seed): 526 projects in 526 street openings for $60,154,701. This plan: 1570 projects in 1453 openings for $163,779,447. The two fund different amounts of work, so compare dig savings ($6,890,019 from shared digs here, none in isolation) and cost per opening, not raw counts.

FUNDING BY YEAR AND SOURCE SIMULATED SOURCE MIX: SOURCED

Source shares follow the BWSC 2024-2026 CIP water program (Table 11). Debt service is the repayment due that year on loans and bonds issued earlier.

YEAR	INTEREST-FREE LOAN	STATE REVOLVING LOAN	RATE REVENUE	BONDS	TOTAL	DEBT SERVICE
2026	$6,372,048	$5,829,912	$9,120,061	$322,670	**$21,644,691**	$0
2027	$6,369,411	$5,830,349	$2,064,720	$0	**$14,264,480**	$959,558
2028	$6,366,395	$5,806,470	$2,692,862	$135,267	**$15,000,994**	$1,895,132
2029	$6,372,737	$5,824,305	$3,656,386	$0	**$15,853,428**	$2,839,135
2030	$6,373,688	$5,824,679	$3,440,007	$0	**$15,638,374**	$3,774,732
2031	$6,362,609	$5,794,536	$3,971,472	$0	**$16,128,617**	$4,710,443
2032	$6,328,214	$5,827,690	$3,994,742	$0	**$16,150,645**	$5,643,503
2033	$6,346,132	$5,816,606	$3,743,160	$0	**$15,905,898**	$6,574,821
2034	$6,343,262	$5,830,191	$4,744,836	$0	**$16,918,289**	$7,507,364
2035	$6,370,423	$5,782,307	$4,121,300	$0	**$16,274,030**	$8,440,315

PROGRAM PACE: MILES PER YEAR SIMULATED

Network: 839.2 miles of street (real geometry); the pipes and pavement on them are simulated.

YEAR	MAIN REPLACED	MAIN RELINED	REPAVED	PRESERVED	REPLACED, % OF NETWORK	REPAVED, % OF NETWORK
2026	1.47	0.10	12.55	0.23	0.18%	1.50%
2027	0.35	0.05	7.38	0.07	0.04%	0.88%
2028	0.21	0.00	7.58	0.11	0.02%	0.90%
2029	0.11	0.02	7.97	0.00	0.01%	0.95%
2030	0.06	0.01	7.47	0.00	0.01%	0.89%
2031	0.06	0.04	7.13	0.00	0.01%	0.85%
2032	0.09	0.03	6.70	0.00	0.01%	0.80%
2033	0.02	0.00	6.12	0.00	0.00%	0.73%
2034	0.07	0.00	5.49	0.00	0.01%	0.65%
2035	0.01	0.00	5.81	0.00	0.00%	0.69%

EMERGENCY RESERVE BALANCE BY YEAR SIMULATED

YEAR	OPENING	SET ASIDE	EMERGENCY REPAIRS	SHORTFALL	CLOSING
2026	$0	$10,070,197	$117,108,172	$107,037,975	$0
2027	$0	$10,070,197	$115,383,798	$105,313,600	$0
2028	$0	$10,070,197	$123,973,868	$113,903,670	$0
2029	$0	$10,070,197	$123,827,732	$113,757,534	$0
2030	$0	$10,070,197	$120,916,748	$110,846,551	$0
2031	$0	$10,070,197	$132,494,879	$122,424,681	$0
2032	$0	$10,070,197	$142,184,394	$132,114,196	$0
2033	$0	$10,070,197	$146,893,090	$136,822,893	$0

2034	$0	$10,070,197	$159,883,234	$149,813,037	$0
2035	$0	$10,070,197	$154,995,261	$144,925,063	$0

RECOMMENDED PROJECTS (RANKED) SIMULATED

#	YEAR	STREET	WORK	PRIORITY	FUNDING	RETURN	WHY
1	2026	**Lagrange St** S15836	Repave	1 Urgent	$142,856 State revolving loan	14.36	Failed arterial road (condition 0), paved 2002, 15,427 vehicles/day
2	2026	**W Newton St** S9866	Repave	1 Urgent	$131,228 State revolving loan	14.09	Failed arterial road (condition 0), paved 1998, 15,904 vehicles/day
3	2026	**Beacon St** S15832.1	Repave	1 Urgent	$142,124 State revolving loan	14.01	Failed arterial road (condition 0), paved 2002, 15,084 vehicles/day
4	2026	**Hancock St** S12807	Repave	1 Urgent	$127,892 State revolving loan	13.83	Failed arterial road (condition 0), paved 1998, 15,869 vehicles/day
5	2026	**Columbus Ave** S10254	Repave	1 Urgent	$135,536 State revolving loan	13.80	Failed arterial road (condition 0), paved 2000, 15,270 vehicles/day
6	2026	**Hyde Park Ave** S13082.4	Repave	1 Urgent	$129,464 State revolving loan	13.71	Failed arterial road (condition 0), paved 2002, 15,600 vehicles/day
7	2026	**Hyde Park Ave** S12858	Repave	1 Urgent	$124,496 State revolving loan	13.70	Failed arterial road (condition 0), paved 1999, 15,999 vehicles/day
8	2026	**Washington St** S10285	Repave	1 Urgent	$140,552 State revolving loan	13.67	Failed arterial road (condition 0), paved 2000, 14,807 vehicles/day
9	2026	**Harvard St** S3595	Repave	1 Urgent	$127,508 State revolving loan	13.52	Failed arterial road (condition 0), paved 1998, 15,532 vehicles/day
10	2026	**Bennington St** S11659	Repave	1 Urgent	$126,932 State revolving loan	13.39	Failed arterial road (condition 0), paved 2000, 15,431 vehicles/day
11	2026	**Grove St** S13506	Repave	1 Urgent	$123,440 State revolving loan	13.25	Failed arterial road (condition 1), paved 2003, 15,606 vehicles/day
12	2026	**Bennington St** S9857	Repave	1 Urgent	$128,060 State revolving loan	13.21	Failed arterial road (condition 0), paved 1999, 15,127 vehicles/day
13	2026	**Washington St** S8133	Repave	1 Urgent	$126,056 State revolving loan	12.96	Failed arterial road (condition 0), paved 1999, 14,991 vehicles/day
14	2026	**Old Colony Ave** S9030	Repave	1 Urgent	$117,908 State revolving loan	12.74	Failed arterial road (condition 0), paved 1999, 15,444 vehicles/day
15	2026	**Austin St** S24719	Repave	1 Urgent	$117,716 State revolving loan	12.72	Failed arterial road (condition 0), paved 2000, 15,445 vehicles/day
16	2026	**Commonwealth Ave** S12072	Repave	1 Urgent	$113,120 State revolving loan	12.59	Failed arterial road (condition 0), paved 1998, 15,770 vehicles/day
17	2026	**New Rutherford Ave** S19449	Repave	1 Urgent	$113,876 State revolving loan	12.54	Failed arterial road (condition 1), paved 2003, 15,662 vehicles/day
18	2026	**Blue Hill Ave** S12901	Repave	1 Urgent	$123,272 State revolving loan	12.46	Failed arterial road (condition 0), paved 2000, 14,624 vehicles/day
19	2026	**Atlantic Ave** S23929	Repave	1 Urgent	$115,652 State revolving loan	12.44	Failed arterial road (condition 0), paved 1999, 15,305 vehicles/day

20	2026	**Cambridge St** S15111	Repave	1 Urgent	$113,516 State revolving loan	12.18	Failed arterial road (condition 0), paved 2000, 15,194 vehicles/day
21	2026	**Devonshire St** S2365	Repave	1 Urgent	$106,484 State revolving loan	12.02	Failed arterial road (condition 0), paved 1998, 15,832 vehicles/day
22	2026	**Commonwealth Ave** S9281	Repave	1 Urgent	$107,564 State revolving loan	11.97	Failed arterial road (condition 0), paved 2000, 15,630 vehicles/day
23	2026	**Heath St** S3953	Repave	1 Urgent	$107,732 State revolving loan	11.80	Failed arterial road (condition 0), paved 1998, 15,379 vehicles/day
24	2026	**Commonwealth Ave** S9942	Repave	1 Urgent	$108,668 State revolving loan	11.77	Failed arterial road (condition 0), paved 1998, 15,221 vehicles/day
25	2026	**Alford St** S24703.2	Repave	1 Urgent	$101,132 State revolving loan	11.49	Failed arterial road (condition 0), paved 1999, 15,876 vehicles/day
26	2026	**Newbury St** S5660	Repave	1 Urgent	$123,740 State revolving loan	11.31	Failed arterial road (condition 0), paved 1999, 13,216 vehicles/day
27	2026	**Columbia Rd** S11966	Repave	1 Urgent	$99,284 State revolving loan	11.17	Failed arterial road (condition 0), paved 2000, 15,716 vehicles/day
28	2026	**Albany St** S17333	Repave	1 Urgent	$98,852 State revolving loan	11.16	Failed arterial road (condition 0), paved 2000, 15,777 vehicles/day
29	2026	**American Legion Hwy** S18664.1	Repave	1 Urgent	$100,076 State revolving loan	11.15	Failed arterial road (condition 1), paved 2003, 15,617 vehicles/day
30	2026	**American Legion Hwy** S18116	Repave	1 Urgent	$102,704 State revolving loan	11.03	Failed arterial road (condition 0), paved 2002, 15,004 vehicles/day
31	2026	**Commonwealth Ave** S9888	Repave	1 Urgent	$100,052 State revolving loan	10.97	Failed arterial road (condition 0), paved 1998, 15,319 vehicles/day
32	2026	**Columbus Ave** S1883	Repave	1 Urgent	$95,900 State revolving loan	10.94	Failed arterial road (condition 0), paved 2000, 15,973 vehicles/day
33	2026	**S Huntington Ave** S17350	Repave	1 Urgent	$98,828 State revolving loan	10.77	Failed arterial road (condition 0), paved 1998, 15,221 vehicles/day
34	2026	**Lagrange St** S19073	Repave	1 Urgent	$94,556 State revolving loan	10.76	Failed arterial road (condition 0), paved 2003, 15,969 vehicles/day
35	2026	**Dorchester St** S10925	Repave	1 Urgent	$96,104 State revolving loan	10.74	Failed arterial road (condition 0), paved 2001, 15,636 vehicles/day
36	2026	**Seaport Blvd** S20566	Repave	1 Urgent	$93,524 State revolving loan	10.63	Failed arterial road (condition 0), paved 1999, 15,960 vehicles/day
37	2026	**Talbot Ave** S11705	Repave	1 Urgent	$96,068 State revolving loan	10.63	Failed arterial road (condition 0), paved 2002, 15,478 vehicles/day
38	2026	**American Legion Hwy** S12651	Repave	1 Urgent	$97,568 State revolving loan	10.52	Failed arterial road (condition 0), paved 2001, 15,062 vehicles/day
39	2026	**New Rutherford Ave** S16122	Repave	1 Urgent	$92,192 State revolving loan	10.39	Failed arterial road (condition 0), paved 2001, 15,867 vehicles/day
40	2026	**Longwood Ave** S13040	Repave	1 Urgent	$93,260 State revolving loan	10.31	Failed arterial road (condition 0), paved 1999, 15,519 vehicles/day

41	2026	**High St** S4021	Repave	1 Urgent	$94,304 State revolving loan	10.27	Failed arterial road (condition 0), paved 2002, 15,264 vehicles/day
42	2026	**Belgrade Ave** S594	Repave	1 Urgent	$92,708 State revolving loan	10.21	Failed arterial road (condition 0), paved 2002, 15,484 vehicles/day
43	2026	**Columbus Ave** S19515	Repave	1 Urgent	$92,048 State revolving loan	10.06	Failed arterial road (condition 0), paved 1999, 15,373 vehicles/day
44	2026	**River St** S12245	Repave	1 Urgent	$93,512 State revolving loan	9.99	Failed arterial road (condition 0), paved 1999, 14,990 vehicles/day
45	2026	**West St** S8366	Repave	1 Urgent	$91,664 State revolving loan	9.91	Failed arterial road (condition 0), paved 2000, 15,221 vehicles/day
46	2026	**Washington St** S20503	Repave	1 Urgent	$92,924 State revolving loan	9.90	Failed arterial road (condition 0), paved 2001, 14,958 vehicles/day
47	2026	**Alford St** S26541	Repave	1 Urgent	$88,232 State revolving loan	9.90	Failed arterial road (condition 0), paved 2000, 15,961 vehicles/day
48	2026	**Dorchester Ave** S17846	Repave	1 Urgent	$90,152 State revolving loan	9.89	Failed arterial road (condition 0), paved 1999, 15,511 vehicles/day
49	2026	**Quincy St** S25632	Repave	1 Urgent	$88,928 State revolving loan	9.89	Failed arterial road (condition 0), paved 2001, 15,781 vehicles/day
50	2026	**Washington St** S8123	Repave	1 Urgent	$88,832 State revolving loan	9.82	Failed arterial road (condition 0), paved 1998, 15,690 vehicles/day
51	2026	**Warren St** S17595	Repave	1 Urgent	$91,904 State revolving loan	9.78	Failed arterial road (condition 0), paved 2001, 14,973 vehicles/day
52	2026	**Washington St** S13547	Repave	1 Urgent	$88,556 Interest-free loan	9.72	Failed arterial road (condition 0), paved 2002, 15,595 vehicles/day
53	2026	**Franklin St** S3157	Repave	1 Urgent	$88,868 Interest-free loan	9.66	Failed arterial road (condition 0), paved 2002, 15,420 vehicles/day
54	2026	**Lincoln St** S16005	Repave	1 Urgent	$86,336 Interest-free loan	9.52	Failed arterial road (condition 0), paved 1999, 15,809 vehicles/day
55	2026	**Dorchester Ave** S2441	Repave	1 Urgent	$88,424 Interest-free loan	9.36	Failed arterial road (condition 0), paved 2002, 15,033 vehicles/day
56	2026	**Columbus Ave** S12666	Repave	1 Urgent	$84,128 Interest-free loan	9.18	Failed arterial road (condition 0), paved 1999, 15,809 vehicles/day
57	2026	**John F. Fitzgerald Surface Rd** S19425	Repave	1 Urgent	$107,936 State revolving loan	9.10	Failed arterial road (condition 0), paved 1998, 11,791 vehicles/day
58	2026	**Massachusetts Ave** S13961	Repave	1 Urgent	$83,084 Interest-free loan	9.08	Failed arterial road (condition 0), paved 1999, 15,937 vehicles/day
59	2026	**Meridian St** S5247	Repave	1 Urgent	$83,552 Interest-free loan	9.07	Failed arterial road (condition 1), paved 2003, 15,802 vehicles/day
60	2026	**Columbia Rd** S10757	Repave	1 Urgent	$83,456 Interest-free loan	8.89	Failed arterial road (condition 0), paved 1998, 15,495 vehicles/day
61	2026	**Monsignor Reynolds Way** S25361	Repave	1 Urgent	$119,108 State revolving loan	8.79	Failed arterial road (condition 0), paved 1998, 10,520 vehicles/day

62	2026	**Meridian St** S5248	Repave	1 Urgent	$83,576 Interest-free loan	8.74	Failed arterial road (condition 0), paved 2002, 15,184 vehicles/day
63	2026	**Centre St** S19511	Repave	1 Urgent	$83,468 Interest-free loan	8.64	Failed arterial road (condition 0), paved 1998, 15,034 vehicles/day
64	2026	**E Berkeley St** S13195	Repave	1 Urgent	$81,512 Interest-free loan	8.57	Failed arterial road (condition 0), paved 2001, 15,490 vehicles/day
65	2026	**Tremont St** S7660	Repave	1 Urgent	$80,684 Interest-free loan	8.51	Failed arterial road (condition 1), paved 2003, 15,681 vehicles/day
66	2026	**Reservation Rd** S15101	Repave	1 Urgent	$81,344 Interest-free loan	8.41	Failed arterial road (condition 0), paved 2001, 15,246 vehicles/day
67	2026	**Centre St** S14425	Repave	1 Urgent	$80,696 Interest-free loan	8.37	Failed arterial road (condition 0), paved 2001, 15,360 vehicles/day
68	2026	**Main St** S24684	Repave	1 Urgent	$79,232 Interest-free loan	8.32	Failed arterial road (condition 0), paved 2000, 15,751 vehicles/day
69	2026	**Tremont St** S17224	Repave	1 Urgent	$80,420 Interest-free loan	8.24	Failed arterial road (condition 0), paved 2000, 15,204 vehicles/day
70	2026	**Huntington Ave** S21701	Repave	1 Urgent	$79,748 Interest-free loan	8.22	Failed arterial road (condition 0), paved 1999, 15,381 vehicles/day
71	2026	**Quincy St** S17701	Repave	1 Urgent	$78,788 Interest-free loan	8.13	Failed arterial road (condition 0), paved 2002, 15,551 vehicles/day
72	2026	**Tremont St** S25398	Repave	1 Urgent	$79,892 Interest-free loan	8.12	Failed arterial road (condition 0), paved 1998, 15,154 vehicles/day
73	2026	**Columbus Ave** S25405	Repave	1 Urgent	$90,092 Interest-free loan	8.11	Failed arterial road (condition 5), paved 2002, 12,831 vehicles/day
74	2026	**Harrison Ave** S27057	Repave	1 Urgent	$80,036 Interest-free loan	8.09	Failed arterial road (condition 0), paved 1999, 15,043 vehicles/day
75	2026	**Commonwealth Ave** S9914	Repave	1 Urgent	$101,228 Interest-free loan	8.06	Failed arterial road (condition 18), paved 2004, 12,116 vehicles/day
76	2026	**Meridian St** S5243	Repave	1 Urgent	$79,808 Interest-free loan	8.05	Failed arterial road (condition 0), paved 2002, 15,048 vehicles/day
77	2026	**Tremont St** S9443	Repave	1 Urgent	$77,852 Interest-free loan	7.99	Failed arterial road (condition 0), paved 2000, 15,603 vehicles/day
78	2026	**Blue Hill Ave** S9437	Repave	1 Urgent	$77,744 Interest-free loan	7.98	Failed arterial road (condition 0), paved 2001, 15,629 vehicles/day
79	2026	**Arlington St** S352	Repave	1 Urgent	$77,336 Interest-free loan	7.86	Failed arterial road (condition 0), paved 1998, 15,542 vehicles/day
80	2026	**Medford St** S5184	Repave	1 Urgent	$76,940 Interest-free loan	7.74	Failed arterial road (condition 0), paved 1998, 15,443 vehicles/day
81	2026	**Dorchester St** S11542	Repave	1 Urgent	$76,844 Interest-free loan	7.69	Failed arterial road (condition 0), paved 2001, 15,369 vehicles/day
82	2026	**Washington St** S17491	Repave	1 Urgent	$75,680 Interest-free loan	7.69	Failed arterial road (condition 0), paved 1999, 15,829 vehicles/day

83	2026	**Huntington Ave** S20218	Repave	1 Urgent	$75,464 Interest-free loan	7.63	Failed arterial road (condition 0), paved 2001, 15,789 vehicles/day
84	2026	**Dudley St** S11950	Repave	1 Urgent	$75,764 Interest-free loan	7.62	Failed arterial road (condition 0), paved 2002, 15,656 vehicles/day
85	2026	**Dorchester St** S2390	Repave	1 Urgent	$76,964 Interest-free loan	7.55	Failed arterial road (condition 0), paved 2000, 15,048 vehicles/day
86	2026	**Nashua St** S21375	Repave	1 Urgent	$105,500 Interest-free loan	7.54	Failed arterial road (condition 13), paved 2002, 10,492 vehicles/day
87	2026	**Summer St** S15971.1	Repave	1 Urgent	$105,008 Interest-free loan	7.44	Failed arterial road (condition 13), paved 2002, 10,417 vehicles/day
88	2026	**Blue Hill Ave** S14986	Repave	1 Urgent	$74,588 Interest-free loan	7.31	Failed arterial road (condition 0), paved 2000, 15,484 vehicles/day
89	2026	**Congress St** S15640	Repave	1 Urgent	$74,060 Interest-free loan	7.25	Failed arterial road (condition 0), paved 1998, 15,600 vehicles/day
90	2026	**Washington St** S8089	Repave	1 Urgent	$73,928 Interest-free loan	7.23	Failed arterial road (condition 0), paved 1999, 15,614 vehicles/day
91	2026	**City Sq** S9362	Repave	1 Urgent	$74,432 Interest-free loan	7.18	Failed arterial road (condition 0), paved 2000, 15,265 vehicles/day
92	2026	**Massachusetts Ave** S23659	Repave	1 Urgent	$73,544 Interest-free loan	7.02	Failed arterial road (condition 0), paved 1999, 15,310 vehicles/day
93	2026	**W Fourth St** S9103	Repave	1 Urgent	$72,584 Interest-free loan	6.91	Failed arterial road (condition 1), paved 2003, 15,573 vehicles/day
94	2026	**N Harvard St** S8851	Repave	1 Urgent	$73,340 Interest-free loan	6.84	Failed arterial road (condition 0), paved 2001, 15,003 vehicles/day
95	2026	**Freeport St** S15103	Repave	1 Urgent	$71,132 Interest-free loan	6.74	Failed arterial road (condition 0), paved 1998, 15,853 vehicles/day
96	2026	**Washington St** S8103	Repave	1 Urgent	$72,572 Interest-free loan	6.72	Failed arterial road (condition 0), paved 2001, 15,094 vehicles/day
97	2026	**Washington St** S8115	Repave	1 Urgent	$71,180 Interest-free loan	6.71	Failed arterial road (condition 0), paved 2001, 15,765 vehicles/day
98	2026	**Centre St** S9093	Repave	1 Urgent	$70,784 Interest-free loan	6.71	Failed arterial road (condition 0), paved 2002, 15,964 vehicles/day
99	2026	**Parker Hill Ave** S6108	Repave	1 Urgent	$126,032 Interest-free loan	6.70	Failed collector road (condition 3), paved 1998, 7,754 vehicles/day
100	2026	**Adams St** S35	Repave	1 Urgent	$71,264 Interest-free loan	6.66	Failed arterial road (condition 0), paved 1999, 15,603 vehicles/day
101	2026	**Market St** S5072	Repave	1 Urgent	$71,696 Interest-free loan	6.66	Failed arterial road (condition 0), paved 1999, 15,378 vehicles/day
102	2026	**Massachusetts Ave** S21754	Repave	1 Urgent	$71,156 Interest-free loan	6.62	Failed arterial road (condition 1), paved 2003, 15,610 vehicles/day
103	2026	**Washington St** S7992	Repave	1 Urgent	$71,144 Interest-free loan	6.62	Failed arterial road (condition 0), paved 1999, 15,548 vehicles/day

104	2026	**Lagrange St** S19207	Repave	1 Urgent	$70,652 Interest-free loan	6.56	Failed arterial road (condition 1), paved 2003, 15,725 vehicles/day
105	2026	**Washington St** S22053	Repave	1 Urgent	$70,040 Interest-free loan	6.53	Failed arterial road (condition 0), paved 2000, 15,948 vehicles/day
106	2026	**Beacon St** S24880	Repave	1 Urgent	$71,360 Interest-free loan	6.44	Failed arterial road (condition 0), paved 1998, 15,012 vehicles/day
107	2026	**Stuart St** S9630	Repave	1 Urgent	$70,904 Interest-free loan	6.41	Failed arterial road (condition 0), paved 1999, 15,185 vehicles/day
108	2026	**Massachusetts Ave** S15492.2	Repave	1 Urgent	$126,404 Interest-free loan	6.38	Failed arterial road (condition 37), paved 2007, 10,544 vehicles/day
109	2026	**Clarendon St** S1755	Repave	1 Urgent	$69,344 Interest-free loan	6.32	Failed arterial road (condition 0), paved 1998, 15,843 vehicles/day
110	2026	**Bennington St** S12210	Repave	1 Urgent	$70,508 Interest-free loan	6.26	Failed arterial road (condition 0), paved 1998, 15,035 vehicles/day
111	2026	**Tremont St** S13144	Repave	1 Urgent	$70,088 Interest-free loan	6.24	Failed arterial road (condition 0), paved 1998, 15,199 vehicles/day
112	2026	**Cummins Hwy** S18265	Repave	1 Urgent	$70,028 Interest-free loan	6.19	Failed arterial road (condition 0), paved 1998, 15,098 vehicles/day
113	2026	**Columbia Rd** S24210	Repave	1 Urgent	$68,516 Interest-free loan	6.11	Failed arterial road (condition 0), paved 2001, 15,798 vehicles/day
114	2026	**Charles St** S26756	Repave	1 Urgent	$69,452 Interest-free loan	6.03	Failed arterial road (condition 0), paved 2002, 15,028 vehicles/day
115	2026	**Dudley St** S2540	Repave shared dig B-2026-S2540	1 Urgent	$55,996 Rate revenue	5.94	Failed arterial road (condition 0), paved 2001, 15,056 vehicles/day
116	2026	**Washington St** S17057	Repave	1 Urgent	$67,436 Interest-free loan	5.90	Failed arterial road (condition 0), paved 1999, 15,950 vehicles/day
117	2026	**Waltham St** S7952	Repave	1 Urgent	$68,420 Interest-free loan	5.87	Failed arterial road (condition 0), paved 2002, 15,236 vehicles/day
118	2026	**South St** S25933	Repave	1 Urgent	$67,124 Interest-free loan	5.81	Failed arterial road (condition 0), paved 2002, 15,927 vehicles/day
119	2026	**Bennington St** S22028	Repave	1 Urgent	$68,204 Interest-free loan	5.74	Failed arterial road (condition 0), paved 2002, 15,007 vehicles/day
120	2026	**Blue Hill Ave** S18145	Repave	1 Urgent	$66,644 Interest-free loan	5.68	Failed arterial road (condition 0), paved 2000, 15,887 vehicles/day
121	2026	**N Beacon St** S25221	Repave	1 Urgent	$66,476 Interest-free loan	5.64	Failed arterial road (condition 0), paved 2002, 15,899 vehicles/day
122	2026	**Hyde Park Ave** S14935	Repave	1 Urgent	$88,508 Interest-free loan	5.48	Poor arterial road (condition 40), paved 2009, 13,212 vehicles/day
123	2026	**Harrison Ave** S9783	Repave	1 Urgent	$66,152 Interest-free loan	5.43	Failed arterial road (condition 0), paved 1999, 15,548 vehicles/day
124	2026	**Centre St** S20760	Repave	1 Urgent	$66,428 Interest-free loan	5.41	Failed arterial road (condition 0), paved 1999, 15,276 vehicles/day

125	2026	**Shawmut Ave** S8795	Repave	1 Urgent	$65,048 Interest-free loan	5.15	Failed arterial road (condition 0), paved 1998, 15,549 vehicles/day
126	2026	**Congress St** S16444	Repave	1 Urgent	$65,240 Interest-free loan	5.07	Failed arterial road (condition 0), paved 1999, 15,150 vehicles/day
127	2026	**Centre St** S1510	Repave	1 Urgent	$64,712 Interest-free loan	5.00	Failed arterial road (condition 0), paved 2001, 15,351 vehicles/day
128	2026	**Washington St** S8159	Repave	1 Urgent	$63,884 Interest-free loan	4.89	Failed arterial road (condition 0), paved 1999, 15,733 vehicles/day
129	2026	**Commonwealth Ave** S21062	Repave	1 Urgent	$63,548 Interest-free loan	4.86	Failed arterial road (condition 0), paved 2000, 15,934 vehicles/day
130	2026	**Columbia Rd** S14457	Repave shared dig B-2026-S14457	1 Urgent	$52,768 Rate revenue	4.83	Failed arterial road (condition 0), paved 2003, 15,934 vehicles/day
131	2026	**New Rutherford Ave** S23719.2	Repave	1 Urgent	$107,528 Interest-free loan	4.82	Poor arterial road (condition 42), paved 2008, 10,198 vehicles/day
132	2026	**Tremont St** S11987	Repave shared dig B-2026-S11987	1 Urgent	$57,364 Rate revenue	4.72	Failed arterial road (condition 0), paved 1998, 14,520 vehicles/day
133	2026	**Richmond St** S16126	Repave shared dig B-2026-S16126	1 Urgent	$49,804 Rate revenue	4.70	Failed arterial road (condition 0), paved 1998, 15,843 vehicles/day
134	2026	**Harvard St** S3875	Repave shared dig B-2026-S3875	1 Urgent	$51,664 Rate revenue	4.62	Failed arterial road (condition 0), paved 2001, 15,238 vehicles/day
135	2026	**River St** S6660	Repave shared dig B-2026-S6660	1 Urgent	$51,340 Rate revenue	4.61	Failed arterial road (condition 0), paved 1999, 15,407 vehicles/day
136	2026	**Washington St** S21788	Repave	1 Urgent	$62,168 State revolving loan	4.44	Failed arterial road (condition 0), paved 1999, 15,839 vehicles/day
137	2026	**Belvidere St** S15896	Repave shared dig B-2026-S15896	1 Urgent	$62,080 Rate revenue	4.23	Failed arterial road (condition 14), paved 2004, 13,296 vehicles/day
138	2026	**Hyde Park Ave** S4234	Repave shared dig B-2026-S4234	1 Urgent	$47,308 Rate revenue	4.12	Failed arterial road (condition 10), paved 2004, 14,626 vehicles/day
139	2026	**Columbia Rd** S9414	Repave shared dig B-2026-S9414	1 Urgent	$56,668 Rate revenue	3.80	Failed arterial road (condition 4), paved 2001, 11,541 vehicles/day
140	2026	**Washington St** S8152	Repave	1 Urgent	$60,452 Interest-free loan	3.79	Failed arterial road (condition 0), paved 1999, 15,311 vehicles/day
141	2026	**Adams St** S17869	Repave	1 Urgent	$60,356 Interest-free loan	3.76	Failed arterial road (condition 0), paved 2002, 15,319 vehicles/day
142	2026	**Washington St** S17526	Repave shared dig B-2026-S17526	1 Urgent	$38,284 Rate revenue	3.73	Failed arterial road (condition 0), paved 1999, 15,501 vehicles/day
143	2026	**New Rutherford Ave** S24736	Repave	1 Urgent	$60,344 Interest-free loan	3.71	Failed arterial road (condition 0), paved 2001, 15,093 vehicles/day
144	2026	**Hyde Park Ave** S4241	Repave	1 Urgent	$59,900 Rate revenue	3.69	Failed arterial road (condition 1), paved 2003, 15,623 vehicles/day
145	2026	**Centre St** S1481	Repave	1 Urgent	$59,468 Rate revenue	3.60	Failed arterial road (condition 1), paved 2003, 15,835 vehicles/day
146	2026	**Adams St** S27576	Repave	1 Urgent	$59,588 Rate revenue	3.57	Failed arterial road (condition 0), paved 1999, 15,497 vehicles/day
147	2026	**Tremont St** S21316	Repave shared dig B-2026-S21316	1 Urgent	$43,156 Rate revenue	3.56	Failed arterial road (condition 0), paved 2000, 13,036 vehicles/day
148	2026	**Charles St S** S12892	Repave shared dig B-2026-S12892	1 Urgent	$58,372 Rate revenue	3.50	Failed arterial road (condition 20), paved 2004, 11,568 vehicles/day
149	2026	**Cummins Hwy** S27243	Repave	1 Urgent	$59,588 Rate revenue	3.49	Failed arterial road (condition 0), paved 2000, 15,145 vehicles/day

150	2026	**Arlington St** S16549	Repave shared dig B-2026-S16549	1 Urgent	$47,152 Rate revenue	3.44	Failed arterial road (condition 32), paved 2008, 14,691 vehicles/day
151	2026	**Arlington St** S342	Repave	1 Urgent	$139,760 Interest-free loan	3.42	Failed collector road (condition 19), paved 1998, 4,132 vehicles/day
152	2026	**Dorchester Ave** S23586	Repave	1 Urgent	$59,408 Rate revenue	3.40	Failed arterial road (condition 0), paved 1999, 14,973 vehicles/day
153	2026	**Franklin St** S3248	Repave shared dig B-2026-S3248	1 Urgent	$37,528 Rate revenue	3.33	Failed arterial road (condition 0), paved 1999, 15,185 vehicles/day
154	2026	**Warren St** S25579	Repave	1 Urgent	$59,168 Rate revenue	3.33	Failed arterial road (condition 0), paved 1998, 15,007 vehicles/day
155	2026	**Hanover St** S3759	Repave	1 Urgent	$58,724 Rate revenue	3.32	Failed arterial road (condition 1), paved 2003, 15,672 vehicles/day
156	2026	**Berkeley St** S11155	Repave shared dig B-2026-S11155	1 Urgent	$47,116 Rate revenue	3.29	Failed arterial road (condition 2), paved 2000, 10,701 vehicles/day
157	2026	**Shawmut Ave** S25253	Repave shared dig B-2026-S25253	1 Urgent	$38,032 Rate revenue	3.29	Failed arterial road (condition 0), paved 2002, 15,008 vehicles/day
158	2026	**Main St** S11822	Repave shared dig B-2026-S11822	1 Urgent	$35,440 Rate revenue	3.10	Failed arterial road (condition 0), paved 1999, 15,749 vehicles/day
159	2026	**E Cottage St** S11751	Repave	1 Urgent	$127,028 Interest-free loan	3.02	Failed collector road (condition 32), paved 2002, 4,771 vehicles/day
160	2026	**Hampden St** S17483	Repave shared dig B-2026-S17483	1 Urgent	$41,080 Rate revenue	3.02	Failed arterial road (condition 10), paved 2002, 11,320 vehicles/day
161	2026	**Dorchester St** S2477	Repave shared dig B-2026-S2477	1 Urgent	$35,836 Rate revenue	3.01	Failed arterial road (condition 0), paved 2001, 15,170 vehicles/day
162	2026	**Clarendon St** S24627	Repave shared dig B-2026-S24627	1 Urgent	$62,212 Rate revenue	2.94	Failed arterial road (condition 32), paved 2006, 10,627 vehicles/day
163	2026	**D St** S11721	Repave shared dig B-2026-S11721	1 Urgent	$58,720 Rate revenue	2.88	Failed arterial road (condition 29), paved 2005, 10,114 vehicles/day
164	2026	**South St** S7210	Repave	1 Urgent	$57,092 Rate revenue	2.83	Failed arterial road (condition 0), paved 1998, 15,923 vehicles/day
165	2026	**Cummins Hwy** S18271	Repave	1 Urgent	$57,260 Rate revenue	2.73	Failed arterial road (condition 0), paved 2002, 15,004 vehicles/day
166	2026	**Tremont St** S16955	Repave	1 Urgent	$57,056 Rate revenue	2.67	Failed arterial road (condition 0), paved 2002, 15,089 vehicles/day
167	2026	**Dorchester Ave** S2429	Repave	1 Urgent	$56,960 Rate revenue	2.67	Failed arterial road (condition 0), paved 2002, 15,261 vehicles/day
168	2026	**Beacon St** S23558	Repave shared dig B-2026-S23558	1 Urgent	$51,964 Rate revenue	2.64	Failed arterial road (condition 37), paved 2007, 10,637 vehicles/day
169	2026	**Trenton St** S7704	Repave shared dig B-2026-S7704	1 Urgent	$62,128 Rate revenue	2.58	Failed collector road (condition 23), paved 2002, 7,620 vehicles/day
170	2026	**Centre St** S1447	Repave shared dig B-2026-S1447	1 Urgent	$49,876 Rate revenue	2.47	Failed collector road (condition 9), paved 1999, 7,617 vehicles/day
171	2026	**Berkeley St** S12103	Repave shared dig B-2026-S12103	1 Urgent	$43,660 Rate revenue	2.29	Poor arterial road (condition 40), paved 2008, 11,201 vehicles/day
172	2026	**Harvard Ave** S3861	Repave	1 Urgent	$55,496 Rate revenue	2.25	Failed arterial road (condition 0), paved 1998, 15,878 vehicles/day
173	2026	**Stuart St** S27590	Repave shared dig B-2026-S27590	1 Urgent	$31,576 Rate revenue	2.21	Failed arterial road (condition 0), paved 1998, 15,261 vehicles/day
174	2026	**Summer St** S16404	Repave shared dig B-2026-S16404	1 Urgent	$31,600 Rate revenue	2.18	Failed arterial road (condition 0), paved 1999, 15,021 vehicles/day
175	2026	**Bunker Hill St** S1124	Repave shared dig B-2026-S1124	1 Urgent	$31,072 Rate revenue	2.16	Failed arterial road (condition 0), paved 1999, 15,727 vehicles/day
176	2026	**Centre St** S19218	Repave shared dig B-2026-S19218	1 Urgent	$31,048 Rate revenue	2.12	Failed arterial road (condition 0), paved 1998, 15,288 vehicles/day
177	2026	**G St** S3293	Repave shared dig B-2026-S3293	1 Urgent	$59,500 Rate revenue	2.06	Failed collector road (condition 13), paved 1998, 5,521 vehicles/day

178	2026	**Warren St** S27318	Repave shared dig B-2026-S27318	1 Urgent	$30,028 Rate revenue	1.90	Failed arterial road (condition 0), paved 2000, 15,660 vehicles/day
179	2026	**Bennington St** S20445	Repave shared dig B-2026-S20445	1 Urgent	$30,088 Rate revenue	1.87	Failed arterial road (condition 0), paved 1999, 15,165 vehicles/day
180	2026	**Amory St** S248	Repave shared dig B-2026-S248	1 Urgent	$48,436 Rate revenue	1.71	Poor collector road (condition 41), paved 2006, 7,165 vehicles/day
181	2026	**Dudley St** S2525	Repave shared dig B-2026-S2525	1 Urgent	$27,352 Rate revenue	1.48	Failed arterial road (condition 0), paved 2001, 15,509 vehicles/day
182	2026	**Cambridge St** S27570	Repave shared dig B-2026-S27570	1 Urgent	$28,060 Rate revenue	1.38	Failed arterial road (condition 0), paved 1999, 15,224 vehicles/day
183	2026	**Boston St** S901	Repave shared dig B-2026-S901 engineering review	1 Urgent	$27,064 Rate revenue	1.05	Failed arterial road (condition 0), paved 2000, 15,900 vehicles/day
184	2026	**Thompson St** S7586	Repave	1 Urgent	$108,356 Rate revenue	0.68	Failed local road (condition 31), paved 1998, 1,221 vehicles/day
185	2026	**New Heath St** S14348	Repave	1 Urgent	$91,364 Rate revenue	0.66	Failed local road (condition 30), paved 1998, 1,398 vehicles/day
186	2026	**Lorna Rd** S4823	Repave	1 Urgent	$136,940 Rate revenue	0.53	Failed local road (condition 39), paved 2000, 985 vehicles/day
187	2026	**Wordsworth St** S8689	Repave	1 Urgent	$80,180 Rate revenue	0.51	Failed local road (condition 34), paved 1999, 1,403 vehicles/day
188	2026	**Barclay Rd** S560	Repave	1 Urgent	$93,812 Rate revenue	0.47	Failed local road (condition 35), paved 1999, 1,075 vehicles/day
189	2026	**Travis St** S14324	Repave	1 Urgent	$75,392 Rate revenue	0.36	Failed local road (condition 32), paved 1998, 1,047 vehicles/day
190	2026	**New Cypher St** S8916	Repave	1 Urgent	$81,932 Rate revenue	0.33	Failed local road (condition 36), paved 1999, 928 vehicles/day
191	2026	**Juniper St** S9760	Repave	1 Urgent	$73,616 Rate revenue	0.33	Failed local road (condition 32), paved 1998, 1,019 vehicles/day
192	2026	**Dakota St** S12741.2	Repave	1 Urgent	$105,368 Rate revenue	0.29	Failed local road (condition 40), paved 2000, 686 vehicles/day
193	2026	**Hillsboro Rd** S13142	Repave	1 Urgent	$99,452 Rate revenue	0.27	Failed local road (condition 34), paved 1998, 577 vehicles/day
194	2026	**Crawford St** S1918.1	Repave	1 Urgent	$117,344 Rate revenue	0.27	Failed local road (condition 37), paved 1999, 543 vehicles/day
195	2026	**Capen St** S1349	Repave	1 Urgent	$87,032 Rate revenue	0.26	Failed local road (condition 37), paved 1999, 684 vehicles/day
196	2026	**South St** S14747	Repave	1 Urgent	$76,316 Rate revenue	0.16	Failed local road (condition 37), paved 1999, 549 vehicles/day
197	2026	**Courtney Rd** S2048.2	Preserve pavement	1 Urgent	$62,417 Bonds	0.13	Poor local road (condition 43), paved 2001, 688 vehicles/day
198	2026	**Bartlett St** S8726	Preserve pavement	1 Urgent	$57,035 Bonds	0.05	Poor local road (condition 44), paved 2001, 441 vehicles/day
199	2026	**Gardena St** S3326	Preserve pavement	1 Urgent	$58,343 Bonds	0.04	Poor local road (condition 41), paved 2000, 301 vehicles/day
200	2026	**Cushing Ave** S2151	Preserve pavement	1 Urgent	$55,943 Bonds	0.04	Poor local road (condition 44), paved 2001, 403 vehicles/day
201	2026	**Park St** S6053	Preserve pavement	1 Urgent	$53,348 Bonds	0.03	Poor local road (condition 44), paved 2001, 539 vehicles/day
202	2026	**Summer St** S20206	Repave	2 Soon	$147,320 Rate revenue	7.42	Poor arterial road (condition 45), paved 2010, 13,205 vehicles/day
203	2026	**Commonwealth Ave** S13434	Repave	2 Soon	$117,524 Rate revenue	6.69	Poor arterial road (condition 45), paved 2010, 13,474 vehicles/day
204	2026	**W Newton St** S10451	Repave	2 Soon	$97,772 Rate revenue	5.72	Poor arterial road (condition 45), paved 2010, 13,509 vehicles/day
205	2026	**Waldemar Ave** S15675	Repave	2 Soon	$127,928 Rate revenue	3.25	Poor collector road (condition 48), paved 2008, 7,521 vehicles/day
206	2026	**Malcolm X Blvd** S25608	Repave shared dig B-2026-S25608	2 Soon	$59,152 Rate revenue	2.82	Poor arterial road (condition 45), paved 2010, 13,294 vehicles/day

207	2026	**Bennington St** S10628	Repave shared dig B-2026-S10628	2 Soon	$57,544 Rate revenue	2.47	Poor arterial road (condition 50), paved 2011, 13,003 vehicles/day
208	2026	**Chelsea St** S1613	Repave shared dig B-2026-S1613	2 Soon	$55,720 Rate revenue	2.09	Poor arterial road (condition 53), paved 2011, 11,724 vehicles/day
209	2026	**E St** S2717	Repave shared dig B-2026-S2717	2 Soon	$41,224 Rate revenue	1.48	Poor collector road (condition 48), paved 2008, 7,786 vehicles/day
210	2026	**Commonwealth Ave** S24640	Repave	3 Plan	$108,968 Rate revenue	4.51	Poor arterial road (condition 61), paved 2014, 15,441 vehicles/day
211	2026	**Geneva Ave** S10039	Repave	3 Plan	$127,388 Rate revenue	3.46	Poor arterial road (condition 70), paved 2016, 15,339 vehicles/day
212	2026	**E First St** S11658	Repave	3 Plan	$101,276 Rate revenue	3.38	Poor arterial road (condition 63), paved 2014, 13,803 vehicles/day
213	2026	**Border St** S10529	Repave	3 Plan	$100,544 Rate revenue	2.47	Poor arterial road (condition 65), paved 2014, 11,765 vehicles/day
214	2026	**Boylston St** S10622	Repave	3 Plan	$96,572 Rate revenue	2.13	Poor arterial road (condition 64), paved 2013, 10,142 vehicles/day
215	2026	**Huntington Ave** S22149.2	Repave	3 Plan	$105,044 Rate revenue	1.95	Poor arterial road (condition 67), paved 2014, 10,121 vehicles/day
216	2026	**Saint Alphonsus St** S9368	Repave shared dig B-2026-S9368	3 Plan	$54,220 Rate revenue	1.91	Poor arterial road (condition 62), paved 2014, 14,035 vehicles/day
217	2026	**Massachusetts Ave** S5099	Repave shared dig B-2026-S5099	3 Plan	$47,980 Rate revenue	1.73	Poor arterial road (condition 63), paved 2014, 13,773 vehicles/day
218	2026	**Washington St** S8085	Repave shared dig B-2026-S8085	3 Plan	$56,248 Rate revenue	1.72	Poor arterial road (condition 59), paved 2012, 10,221 vehicles/day
219	2026	**Kneeland St** S24444	Repave shared dig B-2026-S24444	3 Plan	$53,728 Rate revenue	1.69	Poor arterial road (condition 61), paved 2013, 12,110 vehicles/day
220	2026	**Flora Way** S18466.3	Repave	3 Plan	$116,240 Rate revenue	1.62	Poor collector road (condition 64), paved 2012, 7,174 vehicles/day
221	2026	**Dorchester St** S24227	Repave shared dig B-2026-S24227	3 Plan	$43,660 Rate revenue	1.36	Fair arterial road (condition 71), paved 2016, 13,913 vehicles/day
222	2026	**Dudley St** S2540	Reline water main shared dig B-2026-S2540	4 Monitor	$63,745 Rate revenue	5.94	High risk (index 52): cast iron main from 1936, 1 prior breaks, PoF 80, serves a critical facility
223	2026	**Columbia Rd** S14457	Replace water main shared dig B-2026-S14457	4 Monitor	$94,420 Rate revenue	4.83	Moderate risk (index 49): cast iron main from 1902, 1 prior breaks, PoF 78, serves a critical facility
224	2026	**Tremont St** S11987	Replace water main shared dig B-2026-S11987	4 Monitor	$105,910 Rate revenue	4.72	High risk (index 61): cast iron main from 1907, 3 prior breaks, PoF 88, serves a critical facility
225	2026	**Richmond St** S16126	Replace water main shared dig B-2026-S16126	4 Monitor	$87,010 Rate revenue	4.70	High risk (index 52): cast iron main from 1903, 2 prior breaks, PoF 82, serves a critical facility
226	2026	**Harvard St** S3875	Replace water main shared dig B-2026-S3875	4 Monitor	$91,660 Rate revenue	4.62	Moderate risk (index 50): cast iron main from 1890, 2 prior breaks, PoF 82, serves a critical facility
227	2026	**River St** S6660	Replace water main shared dig B-2026-S6660	4 Monitor	$90,850 Rate revenue	4.61	High risk (index 56): cast iron main from 1966, 2 prior breaks, PoF 80, serves a critical facility
228	2026	**Belvidere St** S15896	Replace water main shared dig B-2026-S15896	4 Monitor	$117,700 Rate revenue	4.23	High risk (index 60): cast iron main from 1912, 2 prior breaks, PoF 95, serves a critical facility
229	2026	**Hyde Park Ave** S4234	Replace water main shared dig B-2026-S4234	4 Monitor	$80,770 Rate revenue	4.12	High risk (index 54): cast iron main from 1889, 1 prior breaks, PoF 84, serves a critical facility
230	2026	**Columbia Rd** S9414	Replace water main shared dig B-2026-S9414	4 Monitor	$104,170 Rate revenue	3.80	High risk (index 60): cast iron main from 1914, 1 prior breaks, PoF 87, serves a critical facility
231	2026	**Washington St** S17526	Replace water main shared dig B-2026-S17526	4 Monitor	$58,210 Rate revenue	3.73	High risk (index 58): cast iron main from 1917, 1 prior breaks, PoF 91, serves a critical facility
232	2026	**Tremont St** S21316	Replace water main shared dig B-2026-S21316	4 Monitor	$70,390 Rate revenue	3.56	High risk (index 53): cast iron main from 1946, 1 prior breaks, PoF 88, serves a critical facility
233	2026	**Charles St S** S12892	Replace water main shared dig B-2026-S12892	4 Monitor	$108,430 Rate revenue	3.50	High risk (index 58): cast iron main from 1912, 1 prior breaks, PoF 81, serves a critical facility
234	2026	**Arlington St** S16549	Replace water main shared dig B-2026-S16549	4 Monitor	$80,380 Rate revenue	3.44	High risk (index 55): cast iron main from 1884, 1 prior breaks, PoF 87, serves a critical facility
235	2026	**Franklin St** S3248	Replace water main shared dig B-2026-S3248	4 Monitor	$56,320 Rate revenue	3.33	Moderate risk (index 35): cast iron main from 1881, 0 prior breaks, PoF 56, serves a critical facility

236	2026	**Berkeley St** S11155	Replace water main shared dig B-2026-S11155	4 Monitor	$80,290 Rate revenue	3.29	High risk (index 53): cast iron main from 1893, 1 prior breaks, PoF 78, serves a critical facility
237	2026	**Shawmut Ave** S25253	Replace water main shared dig B-2026-S25253	4 Monitor	$57,580 Rate revenue	3.29	Low risk (index 24): cast iron main from 1888, 2 prior breaks, PoF 84
238	2026	**Main St** S11822	Replace water main shared dig B-2026-S11822	4 Monitor	$51,100 Rate revenue	3.10	Moderate risk (index 25): cast iron main from 1904, 1 prior breaks, PoF 78
239	2026	**Hampden St** S17483	Replace water main shared dig B-2026-S17483	4 Monitor	$65,200 Rate revenue	3.02	High risk (index 53): cast iron main from 1874, 3 prior breaks, PoF 91, serves a critical facility
240	2026	**Dorchester St** S2477	Replace water main shared dig B-2026-S2477	4 Monitor	$52,090 Rate revenue	3.01	Moderate risk (index 25): cast iron main from 1923, 1 prior breaks, PoF 87
241	2026	**Clarendon St** S24627	Replace water main shared dig B-2026-S24627	4 Monitor	$118,030 Rate revenue	2.94	High risk (index 54): cast iron main from 1861, 3 prior breaks, PoF 84, serves a critical facility
242	2026	**D St** S11721	Replace water main shared dig B-2026-S11721	4 Monitor	$109,300 Rate revenue	2.88	High risk (index 58): cast iron main from 1920, 2 prior breaks, PoF 91, serves a critical facility
243	2026	**Malcolm X Blvd** S25608	Replace water main shared dig B-2026-S25608	4 Monitor	$110,380 Rate revenue	2.82	High risk (index 53): cast iron main from 1903, 3 prior breaks, PoF 88, serves a critical facility
244	2026	**Beacon St** S23558	Replace water main shared dig B-2026-S23558	4 Monitor	$92,410 Rate revenue	2.64	High risk (index 62): cast iron main from 1887, 2 prior breaks, PoF 88, serves a critical facility
245	2026	**Trenton St** S7704	Replace water main shared dig B-2026-S7704	4 Monitor	$117,820 Rate revenue	2.58	Critical risk (index 76): cast iron main from 1893, 2 prior breaks, PoF 95, serves a critical facility
246	2026	**Centre St** S1447	Replace water main shared dig B-2026-S1447	4 Monitor	$87,190 Rate revenue	2.47	High risk (index 53): cast iron main from 1930, 1 prior breaks, PoF 88, serves a critical facility
247	2026	**Bennington St** S10628	Replace water main shared dig B-2026-S10628	4 Monitor	$106,360 Rate revenue	2.47	High risk (index 60): cast iron main from 1915, 1 prior breaks, PoF 84, serves a critical facility
248	2026	**Berkeley St** S12103	Replace water main shared dig B-2026-S12103	4 Monitor	$71,650 Rate revenue	2.29	High risk (index 53): cast iron main from 1926, 1 prior breaks, PoF 91, serves a critical facility
249	2026	**Stuart St** S27590	Replace water main shared dig B-2026-S27590	4 Monitor	$41,440 Rate revenue	2.21	Low risk (index 20): cast iron main from 1860, 0 prior breaks, PoF 64
250	2026	**Summer St** S16404	Replace water main shared dig B-2026-S16404	4 Monitor	$41,500 Rate revenue	2.18	Low risk (index 17): cast iron main from 1931, 0 prior breaks, PoF 53
251	2026	**Bunker Hill St** S1124	Replace water main shared dig B-2026-S1124	4 Monitor	$40,180 Rate revenue	2.16	Low risk (index 20): cast iron main from 1889, 0 prior breaks, PoF 64
252	2026	**Centre St** S19218	Replace water main shared dig B-2026-S19218	4 Monitor	$40,120 Rate revenue	2.12	Low risk (index 18): cast iron main from 1915, 0 prior breaks, PoF 54
253	2026	**Westland Ave** S15710	Repave	4 Monitor	$106,616 Rate revenue	2.12	Fair arterial road (condition 75), paved 2017, 14,206 vehicles/day
254	2026	**Chelsea St** S1613	Replace water main shared dig B-2026-S1613	4 Monitor	$101,800 Rate revenue	2.09	High risk (index 56): cast iron main from 1941, 1 prior breaks, PoF 77, serves a critical facility
255	2026	**G St** S3293	Replace water main shared dig B-2026-S3293	4 Monitor	$111,250 Rate revenue	2.06	High risk (index 55): cast iron main from 1879, 3 prior breaks, PoF 88, serves a critical facility
256	2026	**Saint Alphonsus St** S9368	Replace water main shared dig B-2026-S9368	4 Monitor	$98,050 Rate revenue	1.91	High risk (index 53): cast iron main from 1873, 3 prior breaks, PoF 82, serves a critical facility
257	2026	**Warren St** S27318	Replace water main shared dig B-2026-S27318	4 Monitor	$37,570 Rate revenue	1.90	Low risk (index 21): cast iron main from 1885, 0 prior breaks, PoF 67
258	2026	**Bennington St** S20445	Replace water main shared dig B-2026-S20445	4 Monitor	$37,720 Rate revenue	1.87	Low risk (index 20): cast iron main from 1900, 0 prior breaks, PoF 64
259	2026	**Massachusetts Ave** S5099	Replace water main shared dig B-2026-S5099	4 Monitor	$82,450 Rate revenue	1.73	High risk (index 53): cast iron main from 1909, 1 prior breaks, PoF 87, serves a critical facility
260	2026	**Washington St** S8085	Reline water main shared dig B-2026-S8085	4 Monitor	$64,060 Rate revenue	1.72	High risk (index 53): cast iron main from 1937, 1 prior breaks, PoF 84, serves a critical facility
261	2026	**Amory St** S248	Replace water main shared dig B-2026-S248	4 Monitor	$83,590 Rate revenue	1.71	High risk (index 53): cast iron main from 1894, 2 prior breaks, PoF 88, serves a critical facility
262	2026	**Kneeland St** S24444	Replace water main shared dig B-2026-S24444	4 Monitor	$96,820 Rate revenue	1.69	High risk (index 53): cast iron main from 1907, 1 prior breaks, PoF 91, serves a critical facility
263	2026	**Dudley St** S2525	Replace water main shared dig B-2026-S2525	4 Monitor	$30,880 Rate revenue	1.48	Moderate risk (index 35): cast iron main from 1869, 0 prior breaks, PoF 56, serves a critical facility
264	2026	**E St** S2717	Replace water main shared dig B-2026-S2717	4 Monitor	$65,560 Rate revenue	1.48	High risk (index 54): cast iron main from 1928, 1 prior breaks, PoF 88, serves a critical facility

265	2026	**Bremen St** S1048	Repave	4 Monitor	$126,308 Rate revenue	1.41	Fair arterial road (condition 85), paved 2020, 15,722 vehicles/day
266	2026	**Cambridge St** S27570	Replace water main shared dig B-2026-S27570	4 Monitor	$32,650 Rate revenue	1.38	Low risk (index 20): cast iron main from 1897, 0 prior breaks, PoF 60
267	2026	**Dorchester St** S24227	Replace water main shared dig B-2026-S24227	4 Monitor	$71,650 Rate revenue	1.36	High risk (index 56): cast iron main from 1909, 1 prior breaks, PoF 91, serves a critical facility
268	2026	**Boston St** S901	Replace water main shared dig B-2026-S901 engineering review	4 Monitor	$30,160 Rate revenue	1.05	Low risk (index 19): cast iron main from 1935, 0 prior breaks, PoF 64
269	2026	**Huntington Ave** S4279	Replace water main shared dig B-2026-S4279 engineering review	4 Monitor	$92,590 Rate revenue	1.03	High risk (index 56): cast iron main from 1879, 2 prior breaks, PoF 91, serves a critical facility
270	2026	**Huntington Ave** S4279	Repave shared dig B-2026-S4279 engineering review	4 Monitor	$52,036 Rate revenue	1.03	Fair arterial road (condition 82), paved 2019, 14,020 vehicles/day
271	2026	**Perkins St** S6196	Replace water main shared dig B-2026-S6196 engineering review	4 Monitor	$51,460 Rate revenue	1.02	High risk (index 57): cast iron main from 1899, 1 prior breaks, PoF 91, serves a critical facility
272	2026	**Perkins St** S6196	Repave shared dig B-2026-S6196 engineering review	4 Monitor	$35,584 Bonds	1.02	Fair arterial road (condition 82), paved 2019, 13,992 vehicles/day
273	2027	**Commonwealth Ave** S12256	Repave	1 Urgent	$138,976 State revolving loan	13.01	Failed arterial road (condition 1), paved 2004, 15,842 vehicles/day
274	2027	**S Huntington Ave** S17354.2	Repave	1 Urgent	$144,022 State revolving loan	12.81	Failed arterial road (condition 0), paved 2003, 15,222 vehicles/day
275	2027	**Martin Luther King Jr Blvd** S5008	Repave	1 Urgent	$153,010 State revolving loan	12.72	Failed arterial road (condition 0), paved 1998, 14,607 vehicles/day
276	2027	**Columbus Ave** S20240	Repave	1 Urgent	$139,567 State revolving loan	12.66	Failed arterial road (condition 2), paved 2004, 15,411 vehicles/day
277	2027	**River St** S11939	Repave	1 Urgent	$145,974 State revolving loan	12.50	Failed arterial road (condition 0), paved 2000, 14,735 vehicles/day
278	2027	**American Legion Hwy** S14560.1	Repave	1 Urgent	$142,494 State revolving loan	12.45	Failed arterial road (condition 0), paved 1999, 14,889 vehicles/day
279	2027	**Huntington Ave** S21497	Repave	1 Urgent	$148,144 State revolving loan	12.44	Failed arterial road (condition 0), paved 2001, 14,540 vehicles/day
280	2027	**River St** S6622	Repave	1 Urgent	$139,798 State revolving loan	12.44	Failed arterial road (condition 0), paved 2003, 15,052 vehicles/day
281	2027	**Cambridge St** S12407	Repave	1 Urgent	$138,578 State revolving loan	12.11	Failed arterial road (condition 0), paved 2002, 14,728 vehicles/day
282	2027	**Commonwealth Ave** S11076	Repave	1 Urgent	$133,172 State revolving loan	11.79	Failed arterial road (condition 0), paved 2003, 14,712 vehicles/day
283	2027	**Bennington St** S12159	Repave	1 Urgent	$119,729 State revolving loan	11.78	Failed arterial road (condition 0), paved 2004, 15,931 vehicles/day
284	2027	**Lagrange St** S12834	Repave	1 Urgent	$125,751 State revolving loan	11.39	Failed arterial road (condition 0), paved 1999, 14,806 vehicles/day
285	2027	**High St** S12854	Repave	1 Urgent	$125,481 State revolving loan	11.26	Failed arterial road (condition 0), paved 2001, 14,649 vehicles/day
286	2027	**Commonwealth Ave** S13218	Repave	1 Urgent	$124,467 State revolving loan	11.16	Failed arterial road (condition 0), paved 2003, 14,607 vehicles/day
287	2027	**Boylston St** S25008	Repave	1 Urgent	$124,980 State revolving loan	10.97	Failed arterial road (condition 0), paved 2000, 14,320 vehicles/day

288	2027	**D St** S22767	Repave	1 Urgent	$116,840 State revolving loan	10.84	Failed arterial road (condition 0), paved 1998, 14,928 vehicles/day
289	2027	**Northampton St** S5750	Repave	1 Urgent	$106,105 State revolving loan	10.58	Failed arterial road (condition 0), paved 2004, 15,960 vehicles/day
290	2027	**Huntington Ave** S23671	Repave	1 Urgent	$107,056 State revolving loan	10.57	Failed arterial road (condition 1), paved 2004, 15,821 vehicles/day
291	2027	**Neponset Ave** S5614	Repave	1 Urgent	$110,920 State revolving loan	10.50	Failed arterial road (condition 2), paved 2004, 15,239 vehicles/day
292	2027	**Summer St** S15971.2	Repave	1 Urgent	$112,359 State revolving loan	10.17	Failed arterial road (condition 0), paved 2003, 14,494 vehicles/day
293	2027	**Quincy St** S17699	Repave	1 Urgent	$109,996 State revolving loan	10.15	Failed arterial road (condition 0), paved 1998, 14,752 vehicles/day
294	2027	**Washington St** S12830.1	Repave	1 Urgent	$106,773 State revolving loan	9.95	Failed arterial road (condition 0), paved 1999, 14,894 vehicles/day
295	2027	**Blue Hill Ave** S18139.1	Repave	1 Urgent	$108,609 State revolving loan	9.84	Failed arterial road (condition 0), paved 1998, 14,473 vehicles/day
296	2027	**Huntington Ave** S19410	Repave	1 Urgent	$101,868 State revolving loan	9.78	Failed arterial road (condition 0), paved 2003, 15,391 vehicles/day
297	2027	**Condor St** S1952.2	Repave	1 Urgent	$106,709 State revolving loan	9.72	Failed arterial road (condition 0), paved 1999, 14,550 vehicles/day
298	2027	**Commonwealth Ave** S16861	Repave	1 Urgent	$102,908 State revolving loan	9.58	Failed arterial road (condition 0), paved 2000, 14,906 vehicles/day
299	2027	**Otis St** S16513	Repave	1 Urgent	$106,760 State revolving loan	9.58	Failed arterial road (condition 0), paved 2003, 14,332 vehicles/day
300	2027	**Rutherford Ave** S24710	Repave	1 Urgent	$104,013 State revolving loan	9.51	Failed arterial road (condition 0), paved 2002, 14,626 vehicles/day
301	2027	**Battery St** S458	Repave	1 Urgent	$100,443 State revolving loan	9.17	Failed arterial road (condition 0), paved 2001, 14,656 vehicles/day
302	2027	**Columbia Rd** S1873	Repave	1 Urgent	$100,148 State revolving loan	9.16	Failed arterial road (condition 0), paved 1998, 14,683 vehicles/day
303	2027	**Blue Hill Ave** S15807	Repave	1 Urgent	$99,763 State revolving loan	9.04	Failed arterial road (condition 0), paved 2001, 14,560 vehicles/day
304	2027	**Beacon St** S637	Repave	1 Urgent	$92,842 State revolving loan	9.00	Failed arterial road (condition 0), paved 2004, 15,895 vehicles/day
305	2027	**Avenue Louis Pasteur** S16907	Repave	1 Urgent	$98,466 State revolving loan	8.94	Failed arterial road (condition 0), paved 1998, 14,610 vehicles/day
306	2027	**D St** S21072	Repave	1 Urgent	$96,167 State revolving loan	8.84	Failed arterial road (condition 0), paved 2002, 14,872 vehicles/day
307	2027	**Hyde Park Ave** S22004	Repave	1 Urgent	$96,578 State revolving loan	8.73	Failed arterial road (condition 0), paved 2001, 14,616 vehicles/day
308	2027	**Grove St** S16318	Repave	1 Urgent	$94,883 State revolving loan	8.65	Failed arterial road (condition 0), paved 2000, 14,816 vehicles/day

309	2027	**Columbus Ave** S10879	Repave	1 Urgent	$95,577 State revolving loan	8.64	Failed arterial road (condition 0), paved 2003, 14,651 vehicles/day
310	2027	**Washington St** S8157	Repave	1 Urgent	$93,972 State revolving loan	8.47	Failed arterial road (condition 0), paved 2002, 14,678 vehicles/day
311	2027	**Hyde Park Ave** S21179	Repave	1 Urgent	$91,571 State revolving loan	8.45	Failed arterial road (condition 2), paved 2004, 15,267 vehicles/day
312	2027	**Columbia Rd** S14830	Repave	1 Urgent	$93,188 State revolving loan	8.37	Failed arterial road (condition 0), paved 2000, 14,667 vehicles/day
313	2027	**Dorchester Ave** S2472	Repave	1 Urgent	$91,494 State revolving loan	8.25	Failed arterial road (condition 0), paved 2003, 14,830 vehicles/day
314	2027	**Tremont St** S14333	Repave	1 Urgent	$91,892 State revolving loan	8.12	Failed arterial road (condition 0), paved 2003, 14,515 vehicles/day
315	2027	**American Legion Hwy** S18123	Repave	1 Urgent	$91,609 State revolving loan	8.08	Failed arterial road (condition 0), paved 1999, 14,499 vehicles/day
316	2027	**Cambridge St** S1310	Repave	1 Urgent	$87,410 State revolving loan	8.02	Failed arterial road (condition 0), paved 2003, 15,451 vehicles/day
317	2027	**Commonwealth Ave** S16931	Repave	1 Urgent	$89,734 State revolving loan	7.98	Failed arterial road (condition 0), paved 2000, 14,751 vehicles/day
318	2027	**Hyde Park Ave** S20169	Repave	1 Urgent	$89,131 State revolving loan	7.97	Failed arterial road (condition 0), paved 2001, 14,887 vehicles/day
319	2027	**Centre St** S12995	Repave	1 Urgent	$87,141 State revolving loan	7.93	Failed arterial road (condition 2), paved 2004, 15,425 vehicles/day
320	2027	**River St** S6655	Repave	1 Urgent	$85,099 State revolving loan	7.93	Failed arterial road (condition 0), paved 2004, 15,971 vehicles/day
321	2027	**Chelsea St** S14001	Repave	1 Urgent	$88,027 State revolving loan	7.82	Failed arterial road (condition 0), paved 1998, 14,886 vehicles/day
322	2027	**Market St** S12235	Repave	1 Urgent	$89,786 State revolving loan	7.72	Failed arterial road (condition 0), paved 1998, 14,265 vehicles/day
323	2027	**Cummins Hwy** S18258	Repave	1 Urgent	$86,884 State revolving loan	7.67	Failed arterial road (condition 0), paved 1999, 14,906 vehicles/day
324	2027	**Massachusetts Ave** S11609	Repave	1 Urgent	$85,613 State revolving loan	7.64	Failed arterial road (condition 0), paved 2003, 15,212 vehicles/day
325	2027	**Tremont St** S25382	Repave	1 Urgent	$83,648 Interest-free loan	7.57	Failed arterial road (condition 1), paved 2004, 15,730 vehicles/day
326	2027	**Chelsea St** S1601	Repave	1 Urgent	$84,945 Interest-free loan	7.56	Failed arterial road (condition 2), paved 2004, 15,332 vehicles/day
327	2027	**Lagrange St** S12715	Repave	1 Urgent	$86,293 State revolving loan	7.54	Failed arterial road (condition 0), paved 1999, 14,809 vehicles/day
328	2027	**Commercial St** S15803	Repave	1 Urgent	$85,985 Interest-free loan	7.50	Failed arterial road (condition 0), paved 2000, 14,816 vehicles/day
329	2027	**Washington St** S21041	Repave	1 Urgent	$84,290 Interest-free loan	7.31	Failed arterial road (condition 0), paved 1998, 14,949 vehicles/day

330	2027	**Washington St** S8149	Repave	1 Urgent	$82,172 Interest-free loan	7.30	Failed arterial road (condition 1), paved 2004, 15,679 vehicles/day
331	2027	**Adams St** S9494	Repave	1 Urgent	$82,441 Interest-free loan	7.27	Failed arterial road (condition 2), paved 2004, 15,527 vehicles/day
332	2027	**Victory Rd** S7835	Repave	1 Urgent	$84,380 Interest-free loan	7.07	Failed arterial road (condition 0), paved 2000, 14,429 vehicles/day
333	2027	**Neponset Ave** S5619	Repave	1 Urgent	$84,149 Interest-free loan	7.07	Failed arterial road (condition 0), paved 1999, 14,497 vehicles/day
334	2027	**River St** S6639	Repave	1 Urgent	$82,660 Interest-free loan	7.03	Failed arterial road (condition 0), paved 2000, 14,876 vehicles/day
335	2027	**Morton St** S27586	Repave	1 Urgent	$83,237 Interest-free loan	7.02	Failed arterial road (condition 0), paved 2003, 14,674 vehicles/day
336	2027	**Dalton St** S16160	Repave	1 Urgent	$81,581 State revolving loan	6.97	Failed arterial road (condition 3), paved 2004, 15,225 vehicles/day
337	2027	**Commonwealth Ave** S22667	Repave	1 Urgent	$82,416 Interest-free loan	6.92	Failed arterial road (condition 0), paved 2002, 14,733 vehicles/day
338	2027	**Washington St** S9813	Repave	1 Urgent	$80,567 Interest-free loan	6.91	Failed arterial road (condition 0), paved 2003, 15,360 vehicles/day
339	2027	**Commonwealth Ave** S19498	Repave	1 Urgent	$82,274 Interest-free loan	6.89	Failed arterial road (condition 0), paved 2000, 14,699 vehicles/day
340	2027	**S Huntington Ave** S18415	Repave	1 Urgent	$82,711 Interest-free loan	6.81	Failed arterial road (condition 0), paved 2002, 14,399 vehicles/day
341	2027	**Harrison Ave** S14289	Repave	1 Urgent	$81,517 Interest-free loan	6.79	Failed arterial road (condition 0), paved 1999, 14,747 vehicles/day
342	2027	**Beacon St** S23074	Repave	1 Urgent	$82,364 Interest-free loan	6.72	Failed arterial road (condition 0), paved 2003, 14,304 vehicles/day
343	2027	**Maverick St** S5132	Repave	1 Urgent	$80,605 Interest-free loan	6.68	Failed arterial road (condition 0), paved 1998, 14,834 vehicles/day
344	2027	**Congress St** S24251	Repave	1 Urgent	$80,169 Interest-free loan	6.59	Failed arterial road (condition 0), paved 2002, 14,804 vehicles/day
345	2027	**Cummins Hwy** S2128	Repave	1 Urgent	$81,440 Interest-free loan	6.58	Failed arterial road (condition 0), paved 2000, 14,322 vehicles/day
346	2027	**American Legion Hwy** S10781	Repave	1 Urgent	$79,296 Interest-free loan	6.51	Failed arterial road (condition 0), paved 2001, 14,947 vehicles/day
347	2027	**Milk St** S5214	Repave	1 Urgent	$79,219 Interest-free loan	6.48	Failed arterial road (condition 0), paved 2002, 14,916 vehicles/day
348	2027	**Washington St** S8054	Repave	1 Urgent	$79,373 Interest-free loan	6.48	Failed arterial road (condition 0), paved 1999, 14,839 vehicles/day
349	2027	**Tremont St** S16879	Repave	1 Urgent	$78,949 Interest-free loan	6.43	Failed arterial road (condition 0), paved 2001, 14,908 vehicles/day
350	2027	**River St** S6657	Repave	1 Urgent	$79,873 Interest-free loan	6.42	Failed arterial road (condition 0), paved 2003, 14,523 vehicles/day

351	2027	**Bunker Hill St** S1215	Repave	1 Urgent	$79,578 Interest-free loan	6.40	Failed arterial road (condition 0), paved 2003, 14,570 vehicles/day
352	2027	**Harrison Ave** S11372	Repave	1 Urgent	$76,265 Interest-free loan	6.38	Failed arterial road (condition 0), paved 2004, 15,996 vehicles/day
353	2027	**Broad St** S16032	Repave	1 Urgent	$79,270 Interest-free loan	6.33	Failed arterial road (condition 0), paved 1998, 14,528 vehicles/day
354	2027	**Cambridge St** S22887	Repave	1 Urgent	$78,910 Interest-free loan	6.32	Failed arterial road (condition 0), paved 2002, 14,647 vehicles/day
355	2027	**Massachusetts Ave** S23120	Repave	1 Urgent	$77,434 Interest-free loan	6.30	Failed arterial road (condition 2), paved 2004, 15,308 vehicles/day
356	2027	**River St** S6661	Repave	1 Urgent	$78,089 Interest-free loan	6.30	Failed arterial road (condition 0), paved 1998, 14,938 vehicles/day
357	2027	**Washington St** S8111	Repave	1 Urgent	$79,514 Interest-free loan	6.26	Failed arterial road (condition 0), paved 1998, 14,283 vehicles/day
358	2027	**Washington St** S8066	Repave	1 Urgent	$76,933 Interest-free loan	6.21	Failed arterial road (condition 0), paved 2003, 15,240 vehicles/day
359	2027	**Blue Hill Ave** S17472	Repave	1 Urgent	$78,718 Interest-free loan	6.17	Failed arterial road (condition 0), paved 2001, 14,373 vehicles/day
360	2027	**N Harvard St** S8852	Repave	1 Urgent	$77,395 Interest-free loan	6.14	Failed arterial road (condition 0), paved 2002, 14,856 vehicles/day
361	2027	**Dartmouth St** S2238	Repave	1 Urgent	$77,896 Interest-free loan	6.09	Failed arterial road (condition 0), paved 1999, 14,512 vehicles/day
362	2027	**Dorchester Ave** S2416	Repave	1 Urgent	$76,214 Interest-free loan	6.08	Failed arterial road (condition 2), paved 2004, 15,315 vehicles/day
363	2027	**Monsignor John J. O'Donnell Sq** S17948	Repave	1 Urgent	$73,710 Interest-free loan	5.84	Failed arterial road (condition 0), paved 2004, 15,938 vehicles/day
364	2027	**Dudley St** S2529	Repave	1 Urgent	$76,317 Interest-free loan	5.76	Failed arterial road (condition 0), paved 2001, 14,378 vehicles/day
365	2027	**Berkeley St** S11077	Repave	1 Urgent	$74,596 Interest-free loan	5.72	Failed arterial road (condition 3), paved 2004, 15,197 vehicles/day
366	2027	**Dorchester Ave** S2438	Repave	1 Urgent	$75,585 Interest-free loan	5.65	Failed arterial road (condition 0), paved 1999, 14,433 vehicles/day
367	2027	**Columbia Rd** S15633	Repave	1 Urgent	$74,070 Interest-free loan	5.55	Failed arterial road (condition 0), paved 2001, 14,922 vehicles/day
368	2027	**Preble St** S23227	Repave	1 Urgent	$74,134 Interest-free loan	5.51	Failed arterial road (condition 0), paved 2002, 14,776 vehicles/day
369	2027	**Hyde Park Ave** S4235	Repave	1 Urgent	$73,004 Interest-free loan	5.49	Failed arterial road (condition 2), paved 2004, 15,415 vehicles/day
370	2027	**Washington St** S7986	Repave	1 Urgent	$74,506 Interest-free loan	5.46	Failed arterial road (condition 0), paved 1998, 14,469 vehicles/day
371	2027	**Neptune Rd** S16368	Repave	1 Urgent	$73,903 Interest-free loan	5.38	Failed arterial road (condition 0), paved 1998, 14,546 vehicles/day

372	2027	**Talbot Ave** S10542	Repave	1 Urgent	$74,442 Interest-free loan	5.38	Failed arterial road (condition 0), paved 2000, 14,269 vehicles/day
373	2027	**Lagrange St** S4548	Repave	1 Urgent	$73,094 Interest-free loan	5.36	Failed arterial road (condition 0), paved 2001, 14,935 vehicles/day
374	2027	**Old Colony Ave** S5866	Repave	1 Urgent	$73,890 Interest-free loan	5.29	Failed arterial road (condition 0), paved 2002, 14,315 vehicles/day
375	2027	**Dorchester St** S2483	Repave	1 Urgent	$73,222 Interest-free loan	5.22	Failed arterial road (condition 0), paved 2000, 14,480 vehicles/day
376	2027	**Albany St** S23871	Repave	1 Urgent	$71,681 Interest-free loan	5.19	Failed arterial road (condition 2), paved 2004, 15,369 vehicles/day
377	2027	**Medford St** S24683	Repave	1 Urgent	$72,670 Interest-free loan	5.18	Failed arterial road (condition 0), paved 2002, 14,648 vehicles/day
378	2027	**Bunker Hill St** S1211	Repave	1 Urgent	$71,206 Interest-free loan	5.10	Failed arterial road (condition 0), paved 2003, 15,331 vehicles/day
379	2027	**Harrison Ave** S13806	Repave	1 Urgent	$71,271 Interest-free loan	4.91	Failed arterial road (condition 0), paved 1999, 14,712 vehicles/day
380	2027	**Sullivan Sq** S15636	Repave	1 Urgent	$70,205 Interest-free loan	4.86	Failed arterial road (condition 0), paved 2003, 15,275 vehicles/day
381	2027	**Dorchester Ave** S2463	Repave	1 Urgent	$70,500 Interest-free loan	4.81	Failed arterial road (condition 0), paved 2000, 14,897 vehicles/day
382	2027	**Tremont St** S21503	Repave	1 Urgent	$71,129 Interest-free loan	4.75	Failed arterial road (condition 0), paved 1999, 14,292 vehicles/day
383	2027	**D St** S2175	Repave	1 Urgent	$71,104 Interest-free loan	4.73	Failed arterial road (condition 0), paved 1999, 14,272 vehicles/day
384	2027	**Centre St** S21834	Repave	1 Urgent	$70,731 Interest-free loan	4.69	Failed arterial road (condition 0), paved 2000, 14,356 vehicles/day
385	2027	**Avenue Louis Pasteur** S24987	Repave	1 Urgent	$69,820 Interest-free loan	4.57	Failed arterial road (condition 0), paved 1999, 14,609 vehicles/day
386	2027	**Massachusetts Ave** S5024	Repave	1 Urgent	$69,897 Interest-free loan	4.57	Failed arterial road (condition 0), paved 2003, 14,551 vehicles/day
387	2027	**Columbus Ave** S11957	Repave	1 Urgent	$69,049 Interest-free loan	4.50	Failed arterial road (condition 0), paved 2000, 14,924 vehicles/day
388	2027	**Dorchester Ave** S2444	Repave	1 Urgent	$69,499 Interest-free loan	4.43	Failed arterial road (condition 0), paved 2000, 14,370 vehicles/day
389	2027	**Warren St** S7894	Repave	1 Urgent	$68,869 Interest-free loan	4.40	Failed arterial road (condition 0), paved 2001, 14,723 vehicles/day
390	2027	**Bunker Hill St** S1205	Repave	1 Urgent	$68,536 Interest-free loan	4.25	Failed arterial road (condition 0), paved 2002, 14,458 vehicles/day
391	2027	**Boston St** S900	Repave	1 Urgent	$68,767 Interest-free loan	4.24	Failed arterial road (condition 0), paved 2003, 14,253 vehicles/day
392	2027	**Cambridge St** S22924	Repave shared dig B-2027-S22924	1 Urgent	$57,630 Rate revenue	4.14	Failed arterial road (condition 0), paved 2001, 11,150 vehicles/day

393	2027	**Commonwealth Ave** S20221	Repave	1 Urgent	$67,881 Interest-free loan	4.09	Failed arterial road (condition 0), paved 2002, 14,401 vehicles/day
394	2027	**Commonwealth Ave** S14251	Repave	1 Urgent	$67,598 Interest-free loan	4.06	Failed arterial road (condition 0), paved 2001, 14,537 vehicles/day
395	2027	**Magazine St** S4879	Repave shared dig B-2027-S4879	1 Urgent	$50,761 Rate revenue	3.93	Failed arterial road (condition 0), paved 2001, 14,325 vehicles/day
396	2027	**Quincy St** S13012	Repave	1 Urgent	$66,828 Interest-free loan	3.92	Failed arterial road (condition 0), paved 1999, 14,675 vehicles/day
397	2027	**Southampton St** S15925	Repave	1 Urgent	$66,186 Interest-free loan	3.80	Failed arterial road (condition 0), paved 1999, 14,804 vehicles/day
398	2027	**Walk Hill St** S25828	Repave	1 Urgent	$65,582 Interest-free loan	3.79	Failed arterial road (condition 0), paved 2003, 15,380 vehicles/day
399	2027	**Perkins St** S25963	Repave	1 Urgent	$66,584 Interest-free loan	3.76	Failed arterial road (condition 0), paved 2001, 14,276 vehicles/day
400	2027	**E First St** S2644	Repave shared dig B-2027-S2644	1 Urgent	$44,739 Interest-free loan	3.63	Failed arterial road (condition 0), paved 2001, 14,811 vehicles/day
401	2027	**Bowdoin St** S929	Repave shared dig B-2027-S929	1 Urgent	$39,962 Rate revenue	3.15	Failed arterial road (condition 1), paved 2004, 15,700 vehicles/day
402	2027	**D St** S26943	Repave	1 Urgent	$63,207 Interest-free loan	3.06	Failed arterial road (condition 0), paved 2001, 14,856 vehicles/day
403	2027	**Old Colony Ave** S9043	Repave	1 Urgent	$63,053 Interest-free loan	3.05	Failed arterial road (condition 3), paved 2004, 15,147 vehicles/day
404	2027	**Hanover St** S3748	Repave	1 Urgent	$62,822 Interest-free loan	3.00	Failed arterial road (condition 3), paved 2004, 15,177 vehicles/day
405	2027	**Warren St** S17643	Repave shared dig B-2027-S17643	1 Urgent	$40,181 Rate revenue	2.99	Failed arterial road (condition 0), paved 2003, 14,797 vehicles/day
406	2027	**Washington St** S25347	Repave shared dig B-2027-S25347	1 Urgent	$40,810 Rate revenue	2.97	Failed arterial road (condition 0), paved 1999, 14,307 vehicles/day
407	2027	**Shawmut Ave** S8806	Repave shared dig B-2027-S8806	1 Urgent	$39,718 Rate revenue	2.95	Failed arterial road (condition 0), paved 1998, 14,635 vehicles/day
408	2027	**Dorchester St** S24224	Repave shared dig B-2027-S24224	1 Urgent	$46,613 Rate revenue	2.91	Failed arterial road (condition 0), paved 1999, 10,744 vehicles/day
409	2027	**State St** S9648	Repave	1 Urgent	$61,474 Interest-free loan	2.70	Failed arterial road (condition 1), paved 2004, 15,596 vehicles/day
410	2027	**Commonwealth Ave** S24960	Repave	1 Urgent	$61,743 Interest-free loan	2.64	Failed arterial road (condition 0), paved 2002, 14,738 vehicles/day
411	2027	**Maverick St** S15496	Repave	1 Urgent	$61,589 Interest-free loan	2.55	Failed arterial road (condition 0), paved 1999, 14,495 vehicles/day
412	2027	**Medford St** S5179	Repave shared dig B-2027-S5179	1 Urgent	$36,573 Rate revenue	2.48	Failed arterial road (condition 0), paved 1998, 14,298 vehicles/day
413	2027	**Spring St** S7314	Repave	1 Urgent	$60,999 Interest-free loan	2.35	Failed arterial road (condition 0), paved 2000, 14,254 vehicles/day
414	2027	**Exeter St** S24061	Repave shared dig B-2027-S24061	1 Urgent	$34,891 Rate revenue	2.17	Failed arterial road (condition 0), paved 1999, 14,407 vehicles/day
415	2027	**Centre St** S1485	Repave	1 Urgent	$60,036 Interest-free loan	2.09	Failed arterial road (condition 0), paved 2002, 14,323 vehicles/day

416	2027	**Cummins Hwy** S27250	Repave	1 Urgent	$59,535 Interest-free loan	1.94	Failed arterial road (condition 0), paved 1998, 14,305 vehicles/day
417	2027	**Dorchester Ave** S2427	Repave shared dig B-2027-S2427	1 Urgent	$33,722 Rate revenue	1.94	Failed arterial road (condition 0), paved 2002, 14,320 vehicles/day
418	2027	**Seaver St** S27300	Repave shared dig B-2027-S27300	1 Urgent	$32,810 Rate revenue	1.81	Failed arterial road (condition 0), paved 2003, 14,341 vehicles/day
419	2027	**Bowdoin St** S11499	Repave shared dig B-2027-S11499	1 Urgent	$32,451 Rate revenue	1.78	Failed arterial road (condition 0), paved 1998, 14,699 vehicles/day
420	2027	**Staniford St** S27118	Repave shared dig B-2027-S27118	1 Urgent	$31,565 Rate revenue	1.71	Failed arterial road (condition 0), paved 2004, 15,903 vehicles/day
421	2027	**Malden St** S4934	Repave	1 Urgent	$57,609 Interest-free loan	1.51	Failed arterial road (condition 1), paved 2004, 15,805 vehicles/day
422	2027	**Staniford St** S27117	Repave shared dig B-2027-S27117	1 Urgent	$30,474 Rate revenue	1.48	Failed arterial road (condition 2), paved 2004, 15,486 vehicles/day
423	2027	**Havre St** S3925	Repave shared dig B-2027-S3925	1 Urgent	$34,159 Rate revenue	1.36	Failed collector road (condition 8), paved 1998, 5,573 vehicles/day
424	2027	**Dale St** S2195	Repave shared dig B-2027-S2195	1 Urgent	$55,499 Rate revenue	1.35	Failed collector road (condition 27), paved 2001, 4,178 vehicles/day
425	2027	**River St** S6632	Repave shared dig B-2027-S6632 engineering review	1 Urgent	$29,921 Rate revenue	1.12	Failed arterial road (condition 0), paved 2000, 14,725 vehicles/day
426	2027	**Beacon St** S25302	Repave	1 Urgent	$55,888 Interest-free loan	0.85	Failed arterial road (condition 0), paved 2003, 14,896 vehicles/day
427	2027	**Cambridge St** S26853	Repave	1 Urgent	$55,760 Interest-free loan	0.79	Failed arterial road (condition 0), paved 2001, 14,463 vehicles/day
428	2027	**Linley Ter** S4754	Preserve pavement	1 Urgent	$60,010 Interest-free loan	0.11	Poor local road (condition 44), paved 2003, 1,218 vehicles/day
429	2027	**Margaret St** S4993	Preserve pavement	1 Urgent	$59,211 Interest-free loan	0.10	Poor local road (condition 42), paved 2002, 1,104 vehicles/day
430	2027	**Malcolm X Blvd** S26819	Repave shared dig B-2027-S26819	3 Plan	$41,555 Rate revenue	1.68	Poor arterial road (condition 61), paved 2015, 15,042 vehicles/day
431	2027	**Cambridge St** S22924	Reline water main shared dig B-2027-S22924	4 Monitor	$65,350 Rate revenue	4.14	High risk (index 51): cast iron main from 1942, 1 prior breaks, PoF 77, serves a critical facility
432	2027	**Magazine St** S4879	Replace water main shared dig B-2027-S4879	4 Monitor	$86,777 Interest-free loan	3.93	High risk (index 51): cast iron main from 1898, 2 prior breaks, PoF 84, serves a critical facility
433	2027	**E First St** S2644	Replace water main shared dig B-2027-S2644	4 Monitor	$71,722 Rate revenue	3.63	Moderate risk (index 49): cast iron main from 1888, 1 prior breaks, PoF 84, serves a critical facility
434	2027	**Bowdoin St** S929	Replace water main shared dig B-2027-S929	4 Monitor	$59,781 Rate revenue	3.15	Moderate risk (index 31): cast iron main from 1912, 1 prior breaks, PoF 91
435	2027	**Warren St** S17643	Replace water main shared dig B-2027-S17643	4 Monitor	$60,327 Rate revenue	2.99	Low risk (index 23): cast iron main from 1918, 2 prior breaks, PoF 88
436	2027	**Washington St** S25347	Replace water main shared dig B-2027-S25347	4 Monitor	$61,900 Rate revenue	2.97	Low risk (index 22): cast iron main from 1901, 1 prior breaks, PoF 78
437	2027	**Shawmut Ave** S8806	Replace water main shared dig B-2027-S8806	4 Monitor	$59,171 Rate revenue	2.95	Moderate risk (index 28): cast iron main from 1893, 1 prior breaks, PoF 87
438	2027	**Dorchester St** S24224	Replace water main shared dig B-2027-S24224	4 Monitor	$76,409 Rate revenue	2.91	High risk (index 52): cast iron main from 1858, 1 prior breaks, PoF 84, serves a critical facility
439	2027	**Medford St** S5179	Replace water main shared dig B-2027-S5179	4 Monitor	$51,306 Rate revenue	2.48	Low risk (index 24): cast iron main from 1875, 1 prior breaks, PoF 87
440	2027	**Exeter St** S24061	Replace water main shared dig B-2027-S24061	4 Monitor	$47,101 Rate revenue	2.17	Low risk (index 18): cast iron main from 1880, 0 prior breaks, PoF 56
441	2027	**Dorchester Ave** S2427	Replace water main shared dig B-2027-S2427	4 Monitor	$44,180 Rate revenue	1.94	Low risk (index 15): cast iron main from 1949, 0 prior breaks, PoF 47

442	2027	**Seaver St** S27300	Replace water main shared dig B-2027-S27300	4 Monitor	$41,901 Rate revenue	1.81	Low risk (index 19): cast iron main from 1942, 0 prior breaks, PoF 57
443	2027	**Bowdoin St** S11499	Replace water main shared dig B-2027-S11499	4 Monitor	$41,002 Rate revenue	1.78	Low risk (index 21): cast iron main from 1905, 0 prior breaks, PoF 67
444	2027	**Staniford St** S27118	Replace water main shared dig B-2027-S27118	4 Monitor	$38,788 Rate revenue	1.71	Low risk (index 22): cast iron main from 1909, 0 prior breaks, PoF 64
445	2027	**Malcolm X Blvd** S26819	Replace water main shared dig B-2027-S26819	4 Monitor	$63,761 Rate revenue	1.68	High risk (index 52): cast iron main from 1885, 1 prior breaks, PoF 78, serves a critical facility
446	2027	**Staniford St** S27117	Replace water main shared dig B-2027-S27117	4 Monitor	$36,059 Rate revenue	1.48	Low risk (index 23): cast iron main from 1903, 1 prior breaks, PoF 80
447	2027	**Blue Hill Ave** S18173	Repave	4 Monitor	$100,084 Rate revenue	1.47	Fair arterial road (condition 76), paved 2018, 13,078 vehicles/day
448	2027	**Havre St** S3925	Replace water main shared dig B-2027-S3925	4 Monitor	$45,272 Rate revenue	1.36	High risk (index 51): cast iron main from 1899, 1 prior breaks, PoF 91, serves a critical facility
449	2027	**Dale St** S2195	Replace water main shared dig B-2027-S2195	4 Monitor	$98,622 Rate revenue	1.35	High risk (index 51): cast iron main from 1922, 1 prior breaks, PoF 91, serves a critical facility
450	2027	**River St** S6632	Replace water main shared dig B-2027-S6632 engineering review	4 Monitor	$34,679 Rate revenue	1.12	Low risk (index 10): ductile iron main from 1957, 0 prior breaks, PoF 37
451	2027	**Massachusetts Ave** S21026	Repave engineering review	4 Monitor	$122,361 Rate revenue	1.04	Fair arterial road (condition 83), paved 2020, 12,563 vehicles/day
452	2027	**N Harvard St** S14651	Replace water main shared dig B-2027-S14651 engineering review	4 Monitor	$85,429 Rate revenue	1.01	High risk (index 57): cast iron main from 1887, 2 prior breaks, PoF 91, serves a critical facility
453	2027	**N Harvard St** S14651	Repave shared dig B-2027-S14651 engineering review	4 Monitor	$50,222 Rate revenue	1.01	Fair arterial road (condition 82), paved 2020, 14,392 vehicles/day
454	2028	**Harvard St** S18292.1	Repave	1 Urgent	$150,133 State revolving loan	12.04	Failed arterial road (condition 1), paved 2005, 15,615 vehicles/day
455	2028	**Belgrade Ave** S18702	Repave	1 Urgent	$144,225 State revolving loan	11.99	Failed arterial road (condition 0), paved 2005, 15,922 vehicles/day
456	2028	**Commonwealth Ave** S10705	Repave	1 Urgent	$140,241 State revolving loan	11.55	Failed arterial road (condition 1), paved 2005, 15,658 vehicles/day
457	2028	**American Legion Hwy** S18113	Repave	1 Urgent	$162,196 State revolving loan	11.50	Failed arterial road (condition 0), paved 2000, 14,194 vehicles/day
458	2028	**Chelsea St** S19321	Repave	1 Urgent	$149,405 State revolving loan	11.19	Failed arterial road (condition 0), paved 2004, 14,492 vehicles/day
459	2028	**Saint James Ave** S7267	Repave	1 Urgent	$150,820 State revolving loan	11.07	Failed arterial road (condition 0), paved 2003, 14,241 vehicles/day
460	2028	**Newbury St** S5658	Repave	1 Urgent	$149,968 State revolving loan	10.83	Failed arterial road (condition 0), paved 1999, 13,980 vehicles/day
461	2028	**Talbot Ave** S15006	Repave	1 Urgent	$127,203 State revolving loan	10.63	Failed arterial road (condition 2), paved 2005, 15,519 vehicles/day
462	2028	**Bennington St** S9554	Repave	1 Urgent	$124,208 State revolving loan	10.51	Failed arterial road (condition 1), paved 2005, 15,640 vehicles/day
463	2028	**Saratoga St** S9475	Repave	1 Urgent	$139,238 State revolving loan	10.46	Failed arterial road (condition 0), paved 1999, 14,187 vehicles/day
464	2028	**Cambridge St** S22090	Repave	1 Urgent	$124,153 State revolving loan	10.25	Failed arterial road (condition 2), paved 2005, 15,284 vehicles/day
465	2028	**New Rutherford Ave** S23991	Repave	1 Urgent	$134,608 State revolving loan	10.24	Failed arterial road (condition 0), paved 1999, 14,229 vehicles/day

466	2028	**W Broadway** S8297	Repave	1 Urgent	$133,069 State revolving loan	10.17	Failed arterial road (condition 0), paved 1999, 14,251 vehicles/day
467	2028	**Pleasant St** S9104	Repave	1 Urgent	$137,974 State revolving loan	10.03	Failed arterial road (condition 0), paved 2000, 13,685 vehicles/day
468	2028	**Columbia Rd** S1855	Repave	1 Urgent	$137,356 State revolving loan	10.00	Failed arterial road (condition 0), paved 1999, 13,683 vehicles/day
469	2028	**Rutherford Ave** S14204.2	Repave	1 Urgent	$116,143 State revolving loan	9.97	Failed arterial road (condition 6), paved 2006, 15,971 vehicles/day
470	2028	**American Legion Hwy** S11980	Repave	1 Urgent	$135,268 State revolving loan	9.90	Failed arterial road (condition 0), paved 1998, 13,700 vehicles/day
471	2028	**Washington St** S14841	Repave	1 Urgent	$134,704 State revolving loan	9.84	Failed arterial road (condition 0), paved 1998, 13,648 vehicles/day
472	2028	**Avenue Louis Pasteur** S16908.1	Repave	1 Urgent	$113,739 State revolving loan	9.68	Failed arterial road (condition 7), paved 2006, 15,855 vehicles/day
473	2028	**Columbus Ave** S14003	Repave	1 Urgent	$127,643 State revolving loan	9.63	Failed arterial road (condition 0), paved 2002, 13,939 vehicles/day
474	2028	**Huntington Ave** S16586	Repave	1 Urgent	$128,385 State revolving loan	9.63	Failed arterial road (condition 0), paved 2002, 13,872 vehicles/day
475	2028	**Walk Hill St** S11172.2	Repave	1 Urgent	$128,027 State revolving loan	9.60	Failed arterial road (condition 0), paved 2000, 13,865 vehicles/day
476	2028	**Harvard Ave** S17124	Repave	1 Urgent	$115,113 State revolving loan	9.51	Failed arterial road (condition 3), paved 2005, 15,214 vehicles/day
477	2028	**Ruggles St** S13633	Repave	1 Urgent	$123,590 State revolving loan	9.34	Failed arterial road (condition 0), paved 2002, 13,885 vehicles/day
478	2028	**Malden St** S4935.2	Repave	1 Urgent	$117,558 State revolving loan	9.27	Failed arterial road (condition 0), paved 2004, 14,432 vehicles/day
479	2028	**Massachusetts Ave** S20326	Repave	1 Urgent	$116,404 State revolving loan	9.23	Failed arterial road (condition 0), paved 2004, 14,505 vehicles/day
480	2028	**Walk Hill St** S18396	Repave	1 Urgent	$123,631 State revolving loan	9.19	Failed arterial road (condition 0), paved 2002, 13,652 vehicles/day
481	2028	**Hyde Park Ave** S27283	Repave	1 Urgent	$118,767 State revolving loan	8.86	Failed arterial road (condition 0), paved 2001, 13,644 vehicles/day
482	2028	**Commonwealth Ave** S16570	Repave	1 Urgent	$117,077 State revolving loan	8.76	Failed arterial road (condition 0), paved 1999, 13,671 vehicles/day
483	2028	**Columbia Rd** S22494	Repave	1 Urgent	$108,711 State revolving loan	8.74	Failed arterial road (condition 4), paved 2005, 14,888 vehicles/day
484	2028	**Dartmouth St** S17208	Repave	1 Urgent	$113,464 State revolving loan	8.73	Failed arterial road (condition 0), paved 1998, 14,066 vehicles/day
485	2028	**Southampton St** S21957	Repave	1 Urgent	$109,535 State revolving loan	8.72	Failed arterial road (condition 0), paved 2004, 14,593 vehicles/day
486	2028	**Longwood Ave** S12696	Repave	1 Urgent	$110,139 State revolving loan	8.52	Failed arterial road (condition 0), paved 2000, 14,159 vehicles/day

487	2028	**Morton St** S15796	Repave	1 Urgent	$106,416 State revolving loan	8.50	Failed arterial road (condition 4), paved 2005, 14,825 vehicles/day
488	2028	**Washington St** S14779	Repave	1 Urgent	$104,768 State revolving loan	8.48	Failed arterial road (condition 0), paved 2004, 14,949 vehicles/day
489	2028	**Columbus Ave** S20809	Repave	1 Urgent	$100,247 State revolving loan	8.44	Failed arterial road (condition 6), paved 2006, 15,977 vehicles/day
490	2028	**N Harvard St** S11166	Repave	1 Urgent	$106,870 State revolving loan	8.42	Failed arterial road (condition 0), paved 2004, 14,482 vehicles/day
491	2028	**Massachusetts Ave** S15290	Repave	1 Urgent	$99,258 State revolving loan	8.41	Failed arterial road (condition 0), paved 2005, 15,901 vehicles/day
492	2028	**Washington St** S8080	Repave	1 Urgent	$108,079 State revolving loan	8.04	Failed arterial road (condition 0), paved 1999, 13,633 vehicles/day
493	2028	**Dudley St** S2520	Repave	1 Urgent	$100,247 State revolving loan	7.98	Failed arterial road (condition 3), paved 2005, 14,988 vehicles/day
494	2028	**Warren St** S17742	Repave	1 Urgent	$105,468 State revolving loan	7.88	Failed arterial road (condition 0), paved 1999, 13,750 vehicles/day
495	2028	**Southampton St** S15924	Repave	1 Urgent	$105,908 State revolving loan	7.86	Failed arterial road (condition 0), paved 1998, 13,648 vehicles/day
496	2028	**Hyde Park Ave** S20520	Repave	1 Urgent	$97,857 State revolving loan	7.84	Failed arterial road (condition 3), paved 2005, 15,196 vehicles/day
497	2028	**N Harvard St** S14649	Repave	1 Urgent	$102,707 State revolving loan	7.72	Failed arterial road (condition 0), paved 1999, 13,926 vehicles/day
498	2028	**Atlantic Ave** S19688	Repave	1 Urgent	$103,256 State revolving loan	7.69	Failed arterial road (condition 0), paved 2001, 13,775 vehicles/day
499	2028	**Dudley St** S17668	Repave	1 Urgent	$102,226 State revolving loan	7.67	Failed arterial road (condition 0), paved 2003, 13,913 vehicles/day
500	2028	**River St** S6613	Repave	1 Urgent	$100,879 State revolving loan	7.66	Failed arterial road (condition 0), paved 2002, 14,134 vehicles/day
501	2028	**Bowdoin St** S17893	Repave	1 Urgent	$94,573 Interest-free loan	7.61	Failed arterial road (condition 2), paved 2005, 15,482 vehicles/day
502	2028	**Adams St** S77	Repave	1 Urgent	$98,530 Interest-free loan	7.50	Failed arterial road (condition 0), paved 2004, 14,291 vehicles/day
503	2028	**Austin St** S24720	Repave	1 Urgent	$98,475 Interest-free loan	7.49	Failed arterial road (condition 0), paved 2004, 14,283 vehicles/day
504	2028	**Huntington Ave** S21992	Repave	1 Urgent	$99,588 State revolving loan	7.48	Failed arterial road (condition 0), paved 2000, 14,047 vehicles/day
505	2028	**Cambridge St** S16719	Repave	1 Urgent	$99,231 Interest-free loan	7.44	Failed arterial road (condition 0), paved 1999, 14,035 vehicles/day
506	2028	**Blue Hill Ave** S18060	Repave	1 Urgent	$99,451 Interest-free loan	7.41	Failed arterial road (condition 0), paved 2001, 13,938 vehicles/day
507	2028	**Columbus Ave** S20528	Repave	1 Urgent	$92,595 Interest-free loan	7.34	Failed arterial road (condition 2), paved 2005, 15,435 vehicles/day

508	2028	**L St** S4521	Repave	1 Urgent	$98,929 Interest-free loan	7.26	Failed arterial road (condition 0), paved 2001, 13,751 vehicles/day
509	2028	**Summer St** S21674	Repave	1 Urgent	$98,901 Interest-free loan	7.25	Failed arterial road (condition 0), paved 2003, 13,728 vehicles/day
510	2028	**Centre St** S1507	Repave	1 Urgent	$98,132 Interest-free loan	7.22	Failed arterial road (condition 0), paved 2002, 13,823 vehicles/day
511	2028	**Washington St** S26314	Repave	1 Urgent	$90,617 Interest-free loan	7.01	Failed arterial road (condition 2), paved 2005, 15,299 vehicles/day
512	2028	**Bowdoin St** S946	Repave	1 Urgent	$96,016 Interest-free loan	6.97	Failed arterial road (condition 0), paved 1998, 13,778 vehicles/day
513	2028	**Shawmut Ave** S8780	Repave	1 Urgent	$96,332 Interest-free loan	6.94	Failed arterial road (condition 0), paved 2003, 13,645 vehicles/day
514	2028	**Harvard Ave** S3859	Repave	1 Urgent	$87,580 Interest-free loan	6.92	Failed arterial road (condition 0), paved 2005, 15,997 vehicles/day
515	2028	**Chestnut Hill Ave** S17341	Repave	1 Urgent	$91,358 Interest-free loan	6.83	Failed arterial road (condition 0), paved 2004, 14,606 vehicles/day
516	2028	**River St** S6648	Repave	1 Urgent	$94,518 Interest-free loan	6.78	Failed arterial road (condition 0), paved 2003, 13,723 vehicles/day
517	2028	**Washington St** S13068	Repave	1 Urgent	$92,856 Interest-free loan	6.77	Failed arterial road (condition 0), paved 1998, 14,087 vehicles/day
518	2028	**Lagrange St** S4551	Repave	1 Urgent	$91,729 Interest-free loan	6.62	Failed arterial road (condition 0), paved 2000, 14,056 vehicles/day
519	2028	**Dorchester Ave** S15369	Repave	1 Urgent	$91,180 Interest-free loan	6.53	Failed arterial road (condition 0), paved 1998, 14,013 vehicles/day
520	2028	**Neponset Ave** S5618	Repave	1 Urgent	$88,185 Interest-free loan	6.49	Failed arterial road (condition 4), paved 2005, 14,916 vehicles/day
521	2028	**Boston St** S17638	Repave	1 Urgent	$91,922 Interest-free loan	6.45	Failed arterial road (condition 0), paved 1998, 13,642 vehicles/day
522	2028	**Shawmut Ave** S8799	Repave	1 Urgent	$87,539 Interest-free loan	6.40	Failed arterial road (condition 0), paved 2004, 14,782 vehicles/day
523	2028	**Norfolk St** S18376	Repave	1 Urgent	$88,501 Interest-free loan	6.37	Failed arterial road (condition 0), paved 2004, 14,396 vehicles/day
524	2028	**Hyde Park Ave** S4245	Repave	1 Urgent	$87,690 Interest-free loan	6.32	Failed arterial road (condition 0), paved 2004, 14,551 vehicles/day
525	2028	**Massachusetts Ave** S14341	Repave	1 Urgent	$86,303 Interest-free loan	6.27	Failed arterial road (condition 3), paved 2005, 14,993 vehicles/day
526	2028	**Tremont St** S19769	Repave	1 Urgent	$90,328 Interest-free loan	6.26	Failed arterial road (condition 0), paved 2000, 13,634 vehicles/day
527	2028	**Cambridge St** S17022	Repave	1 Urgent	$88,020 Interest-free loan	6.20	Failed arterial road (condition 0), paved 2001, 14,153 vehicles/day
528	2028	**Causeway St** S20980	Repave	1 Urgent	$83,170 Interest-free loan	6.19	Failed arterial road (condition 0), paved 2005, 15,905 vehicles/day

529	2028	**Blue Hill Ave** S867	Repave	1 Urgent	$87,869 Interest-free loan	6.19	Failed arterial road (condition 0), paved 2000, 14,177 vehicles/day
530	2028	**Commonwealth Ave** S14678	Repave	1 Urgent	$87,223 Interest-free loan	6.01	Failed arterial road (condition 0), paved 2001, 13,967 vehicles/day
531	2028	**Commercial St** S15531	Repave	1 Urgent	$85,973 Interest-free loan	5.95	Failed arterial road (condition 0), paved 2000, 14,217 vehicles/day
532	2028	**Maverick St** S13816	Repave	1 Urgent	$85,492 Interest-free loan	5.87	Failed arterial road (condition 0), paved 2000, 14,175 vehicles/day
533	2028	**Congress St** S1957	Repave	1 Urgent	$83,953 Interest-free loan	5.75	Failed arterial road (condition 0), paved 2004, 14,431 vehicles/day
534	2028	**Dorchester Ave** S17871	Repave	1 Urgent	$82,799 Interest-free loan	5.64	Failed arterial road (condition 0), paved 2004, 14,590 vehicles/day
535	2028	**W Dedham St** S11968	Repave	1 Urgent	$81,109 Interest-free loan	5.61	Failed arterial road (condition 2), paved 2005, 15,334 vehicles/day
536	2028	**Richmond St** S9896	Repave	1 Urgent	$84,297 Interest-free loan	5.57	Failed arterial road (condition 0), paved 2001, 13,842 vehicles/day
537	2028	**N Beacon St** S20197	Repave	1 Urgent	$83,555 Interest-free loan	5.45	Failed arterial road (condition 0), paved 2000, 13,809 vehicles/day
538	2028	**Arlington St** S9995	Repave	1 Urgent	$79,021 Interest-free loan	5.43	Failed arterial road (condition 1), paved 2005, 15,791 vehicles/day
539	2028	**Freeport St** S3263	Repave	1 Urgent	$82,414 Interest-free loan	5.38	Failed arterial road (condition 0), paved 2002, 14,069 vehicles/day
540	2028	**Austin St** S12769	Repave	1 Urgent	$82,868 Interest-free loan	5.37	Failed arterial road (condition 0), paved 2003, 13,849 vehicles/day
541	2028	**Neponset Ave** S5615	Repave	1 Urgent	$82,923 Interest-free loan	5.33	Failed arterial road (condition 0), paved 2001, 13,735 vehicles/day
542	2028	**Medford St** S5188	Repave	1 Urgent	$79,048 Interest-free loan	5.23	Failed arterial road (condition 2), paved 2005, 15,253 vehicles/day
543	2028	**Avery St** S476	Repave	1 Urgent	$81,370 Interest-free loan	5.22	Failed arterial road (condition 0), paved 2002, 14,068 vehicles/day
544	2028	**Milk St** S5311	Repave	1 Urgent	$79,062 Interest-free loan	5.06	Failed arterial road (condition 0), paved 2004, 14,659 vehicles/day
545	2028	**Porter St** S24767	Repave	1 Urgent	$76,644 Interest-free loan	4.97	Failed arterial road (condition 1), paved 2005, 15,726 vehicles/day
546	2028	**Tremont St** S11067	Repave	1 Urgent	$80,203 Interest-free loan	4.89	Failed arterial road (condition 0), paved 1999, 13,645 vehicles/day
547	2028	**Dorchester Ave** S25666	Repave	1 Urgent	$77,991 Interest-free loan	4.74	Failed arterial road (condition 0), paved 1999, 14,234 vehicles/day
548	2028	**W Milton St** S10591	Repave	1 Urgent	$78,307 Interest-free loan	4.70	Failed arterial road (condition 1), paved 2004, 13,975 vehicles/day
549	2028	**Massachusetts Ave** S9820	Repave	1 Urgent	$78,732 Interest-free loan	4.68	Failed arterial road (condition 0), paved 1998, 13,694 vehicles/day

550	2028	**Boston St** S10670	Repave	1 Urgent	$75,119 Interest-free loan	4.65	Failed arterial road (condition 1), paved 2005, 15,659 vehicles/day
551	2028	**Boylston St** S13383	Repave	1 Urgent	$76,136 Interest-free loan	4.63	Failed arterial road (condition 0), paved 2004, 14,918 vehicles/day
552	2028	**Devonshire St** S2366	Repave	1 Urgent	$76,191 Interest-free loan	4.60	Failed arterial road (condition 4), paved 2005, 14,921 vehicles/day
553	2028	**Seaver St** S26998	Repave	1 Urgent	$76,795 Interest-free loan	4.58	Failed arterial road (condition 0), paved 2004, 14,375 vehicles/day
554	2028	**D St** S2167	Repave	1 Urgent	$77,262 Interest-free loan	4.47	Failed arterial road (condition 0), paved 2001, 13,767 vehicles/day
555	2028	**Hancock St** S22838	Repave	1 Urgent	$76,589 Interest-free loan	4.44	Failed arterial road (condition 0), paved 2000, 14,036 vehicles/day
556	2028	**Dorchester St** S2479	Repave	1 Urgent	$76,012 Interest-free loan	4.39	Failed arterial road (condition 0), paved 2002, 14,196 vehicles/day
557	2028	**Western Ave** S23249	Repave	1 Urgent	$76,823 Interest-free loan	4.37	Failed arterial road (condition 0), paved 2001, 13,685 vehicles/day
558	2028	**E Brookline St** S2409	Repave	1 Urgent	$74,212 Interest-free loan	4.31	Failed arterial road (condition 0), paved 2004, 15,071 vehicles/day
559	2028	**Southampton St** S14385	Repave	1 Urgent	$76,040 Interest-free loan	4.26	Failed arterial road (condition 0), paved 1999, 13,757 vehicles/day
560	2028	**Brookline Ave** S12678	Repave	1 Urgent	$75,325 Interest-free loan	4.26	Failed arterial road (condition 0), paved 2004, 14,169 vehicles/day
561	2028	**Dearborn St** S2084	Repave	1 Urgent	$74,295 Interest-free loan	4.24	Failed arterial road (condition 0), paved 2004, 14,762 vehicles/day
562	2028	**Beacon St** S15554	Repave	1 Urgent	$74,254 Interest-free loan	4.22	Failed arterial road (condition 4), paved 2005, 14,844 vehicles/day
563	2028	**Blue Hill Ave** S864	Repave	1 Urgent	$75,229 Interest-free loan	4.21	Failed arterial road (condition 0), paved 2003, 14,047 vehicles/day
564	2028	**Commercial St** S1922	Repave	1 Urgent	$75,861 Interest-free loan	4.20	Failed arterial road (condition 0), paved 2000, 13,672 vehicles/day
565	2028	**Heath St** S23793	Repave	1 Urgent	$74,858 Interest-free loan	4.20	Failed arterial road (condition 0), paved 1998, 14,247 vehicles/day
566	2028	**Longwood Ave** S24988	Repave	1 Urgent	$74,844 Interest-free loan	4.20	Failed arterial road (condition 0), paved 2004, 14,254 vehicles/day
567	2028	**River St** S6653	Repave	1 Urgent	$74,707 Interest-free loan	4.19	Failed arterial road (condition 0), paved 2004, 14,316 vehicles/day
568	2028	**Shawmut Ave** S8796	Repave	1 Urgent	$75,133 Interest-free loan	4.16	Failed arterial road (condition 0), paved 2002, 13,964 vehicles/day
569	2028	**Hyde Park Ave** S19751	Repave	1 Urgent	$75,229 Interest-free loan	4.13	Failed arterial road (condition 0), paved 1998, 13,776 vehicles/day
570	2028	**W Second St** S11814	Repave	1 Urgent	$74,762 Interest-free loan	4.03	Failed arterial road (condition 0), paved 2003, 13,737 vehicles/day

571	2028	**Dorchester Ave** S2468	Repave	1 Urgent	$73,690 Interest-free loan	3.98	Failed arterial road (condition 0), paved 2004, 14,253 vehicles/day
572	2028	**Massachusetts Ave** S14886	Repave	1 Urgent	$71,781 Interest-free loan	3.86	Failed arterial road (condition 2), paved 2005, 15,309 vehicles/day
573	2028	**Adams St** S84	Repave	1 Urgent	$72,014 Interest-free loan	3.84	Failed arterial road (condition 0), paved 2004, 14,962 vehicles/day
574	2028	**Washington St** S8013	Repave	1 Urgent	$72,880 Interest-free loan	3.82	Failed arterial road (condition 0), paved 2002, 14,222 vehicles/day
575	2028	**Huntington Ave** S24634	Repave	1 Urgent	$73,635 Interest-free loan	3.82	Failed arterial road (condition 0), paved 2001, 13,692 vehicles/day
576	2028	**Washington St** S8028	Repave	1 Urgent	$70,750 Interest-free loan	3.79	Failed arterial road (condition 0), paved 2005, 15,917 vehicles/day
577	2028	**Huntington Ave** S16595	Repave	1 Urgent	$72,880 Interest-free loan	3.67	Failed arterial road (condition 0), paved 1998, 13,661 vehicles/day
578	2028	**City Sq** S1745	Repave	1 Urgent	$71,341 Rate revenue	3.45	Failed arterial road (condition 0), paved 1998, 13,939 vehicles/day
579	2028	**South St** S7207	Repave	1 Urgent	$70,943 Rate revenue	3.37	Failed arterial road (condition 0), paved 2000, 13,922 vehicles/day
580	2028	**Columbus Ave** S12711	Repave	1 Urgent	$69,143 Rate revenue	3.24	Failed arterial road (condition 3), paved 2005, 15,159 vehicles/day
581	2028	**River St** S6630	Repave	1 Urgent	$70,159 Rate revenue	3.24	Failed arterial road (condition 0), paved 1999, 14,034 vehicles/day
582	2028	**Medford St** S5189	Repave shared dig B-2028-S5189	1 Urgent	$49,574 Interest-free loan	3.19	Failed arterial road (condition 0), paved 1999, 12,856 vehicles/day
583	2028	**Sumner St** S7437	Repave	1 Urgent	$69,816 Rate revenue	3.17	Failed arterial road (condition 0), paved 1999, 14,057 vehicles/day
584	2028	**Cambridge St** S1308	Repave	1 Urgent	$69,376 Rate revenue	3.10	Failed arterial road (condition 0), paved 1999, 14,132 vehicles/day
585	2028	**Main St** S4916	Repave	1 Urgent	$69,596 Rate revenue	3.08	Failed arterial road (condition 0), paved 2001, 13,855 vehicles/day
586	2028	**Centre St** S1488	Repave	1 Urgent	$69,335 Rate revenue	3.08	Failed arterial road (condition 0), paved 2004, 14,101 vehicles/day
587	2028	**W Second St** S11812	Repave	1 Urgent	$69,541 Rate revenue	3.05	Failed arterial road (condition 0), paved 1999, 13,770 vehicles/day
588	2028	**Washington St** S8082	Repave	1 Urgent	$68,566 Rate revenue	2.87	Failed arterial road (condition 0), paved 2000, 13,873 vehicles/day
589	2028	**Purchase St** S16024	Repave shared dig B-2028-S16024	1 Urgent	$43,158 Rate revenue	2.83	Failed arterial road (condition 4), paved 2005, 14,878 vehicles/day
590	2028	**Columbus Ave** S22732	Repave	1 Urgent	$67,494 Rate revenue	2.79	Failed arterial road (condition 0), paved 2004, 14,703 vehicles/day
591	2028	**Cummins Hwy** S18229	Repave shared dig B-2028-S18229	1 Urgent	$46,744 Rate revenue	2.78	Failed arterial road (condition 0), paved 2001, 11,864 vehicles/day
592	2028	**Centre St** S1469	Repave	1 Urgent	$68,099 Rate revenue	2.76	Failed arterial road (condition 0), paved 2003, 13,808 vehicles/day
593	2028	**Washington St** S27160	Repave	1 Urgent	$68,099 Rate revenue	2.72	Failed arterial road (condition 0), paved 2001, 13,635 vehicles/day
594	2028	**Washington St** S26017	Repave	1 Urgent	$66,148 Rate revenue	2.60	Failed arterial road (condition 2), paved 2005, 15,514 vehicles/day
595	2028	**Chelsea St** S1608	Repave shared dig B-2028-S1608	1 Urgent	$40,850 Rate revenue	2.42	Failed arterial road (condition 0), paved 2002, 13,709 vehicles/day
596	2028	**Beacon St** S13735	Repave	1 Urgent	$65,296 Rate revenue	2.31	Failed arterial road (condition 0), paved 2004, 14,960 vehicles/day

597	2028	**N Harvard St** S11523	Repave shared dig B-2028-S11523	1 Urgent	$38,006 Rate revenue	2.30	Failed arterial road (condition 0), paved 2004, 15,065 vehicles/day
598	2028	**Market St** S5080	Repave shared dig B-2028-S5080	1 Urgent	$37,003 Rate revenue	2.27	Failed arterial road (condition 6), paved 2006, 15,986 vehicles/day
599	2028	**Bowdoin St** S934	Repave shared dig B-2028-S934	1 Urgent	$36,110 Rate revenue	1.94	Failed arterial road (condition 0), paved 2004, 14,135 vehicles/day
600	2028	**Hancock St** S20135	Repave	1 Urgent	$64,375 Rate revenue	1.92	Failed arterial road (condition 0), paved 2002, 13,810 vehicles/day
601	2028	**Centre St** S1474	Repave	1 Urgent	$63,551 Rate revenue	1.78	Failed arterial road (condition 0), paved 2004, 14,292 vehicles/day
602	2028	**W Newton St** S15557	Repave shared dig B-2028-S15557	1 Urgent	$34,187 Rate revenue	1.63	Failed arterial road (condition 6), paved 2006, 15,869 vehicles/day
603	2028	**South St** S13640	Repave shared dig B-2028-S13640	1 Urgent	$34,022 Rate revenue	1.44	Failed arterial road (condition 0), paved 1998, 14,048 vehicles/day
604	2028	**Porter St** S27088	Repave	1 Urgent	$62,232 Rate revenue	1.42	Failed arterial road (condition 0), paved 2000, 14,197 vehicles/day
605	2028	**Perkins St** S10221	Repave engineering review	1 Urgent	$60,268 Rate revenue	0.88	Failed arterial road (condition 0), paved 2002, 14,006 vehicles/day
606	2028	**South St** S20637	Repave	1 Urgent	$59,471 Rate revenue	0.67	Failed arterial road (condition 0), paved 2004, 14,282 vehicles/day
607	2028	**Richfield Park** S10048	Preserve pavement	1 Urgent	$64,097 Bonds	0.09	Poor local road (condition 42), paved 2003, 993 vehicles/day
608	2028	**Spring Valley Rd** S7316	Preserve pavement	1 Urgent	$71,169 Bonds	0.05	Poor local road (condition 41), paved 2002, 309 vehicles/day
609	2028	**D St** S19837	Repave shared dig B-2028-S19837	2 Soon	$49,574 Rate revenue	2.55	Poor arterial road (condition 45), paved 2013, 15,971 vehicles/day
610	2028	**Medford St** S5189	Replace water main shared dig B-2028-S5189	4 Monitor	$81,002 Rate revenue	3.19	High risk (index 62): cast iron main from 1928, 1 prior breaks, PoF 91, serves a critical facility
611	2028	**Purchase St** S16024	Replace water main shared dig B-2028-S16024	4 Monitor	$64,962 Rate revenue	2.83	Low risk (index 23): cast iron main from 1914, 2 prior breaks, PoF 82
612	2028	**Cummins Hwy** S18229	Replace water main shared dig B-2028-S18229	4 Monitor	$73,926 Rate revenue	2.78	High risk (index 52): cast iron main from 1948, 1 prior breaks, PoF 84, serves a critical facility
613	2028	**D St** S19837	Replace water main shared dig B-2028-S19837	4 Monitor	$81,002 Rate revenue	2.55	High risk (index 61): cast iron main from 1868, 1 prior breaks, PoF 91, serves a critical facility
614	2028	**Chelsea St** S1608	Replace water main shared dig B-2028-S1608	4 Monitor	$59,191 Rate revenue	2.42	Low risk (index 22): cast iron main from 1927, 1 prior breaks, PoF 80
615	2028	**N Harvard St** S11523	Replace water main shared dig B-2028-S11523	4 Monitor	$52,082 Rate revenue	2.30	Low risk (index 25): cast iron main from 1916, 1 prior breaks, PoF 78
616	2028	**Market St** S5080	Replace water main shared dig B-2028-S5080	4 Monitor	$49,574 Rate revenue	2.27	Moderate risk (index 31): cast iron main from 1935, 1 prior breaks, PoF 88
617	2028	**Bowdoin St** S934	Replace water main shared dig B-2028-S934	4 Monitor	$47,342 Rate revenue	1.94	Low risk (index 23): cast iron main from 1912, 1 prior breaks, PoF 78
618	2028	**W Newton St** S15557	Replace water main shared dig B-2028-S15557	4 Monitor	$42,533 Rate revenue	1.63	Low risk (index 19): cast iron main from 1897, 0 prior breaks, PoF 60
619	2028	**South St** S13640	Replace water main shared dig B-2028-S13640	4 Monitor	$42,121 Rate revenue	1.44	Low risk (index 17): cast iron main from 1933, 0 prior breaks, PoF 64
620	2028	**Seaport Blvd** S21617	Repave engineering review	4 Monitor	$106,526 Rate revenue	1.08	Fair arterial road (condition 82), paved 2021, 14,658 vehicles/day
621	2028	**E First St** S2647	Repave engineering review	4 Monitor	$134,375 Rate revenue	1.03	Fair arterial road (condition 83), paved 2021, 12,840 vehicles/day
622	2028	**River St** S6626	Replace water main shared dig B-2028-S6626 engineering review	4 Monitor	$98,965 Rate revenue	1.00	High risk (index 55): cast iron main from 1931, 1 prior breaks, PoF 77, serves a critical facility
623	2028	**River St** S6626	Repave shared dig B-2028-S6626 engineering review	4 Monitor	$56,760 Rate revenue	1.00	Fair arterial road (condition 79), paved 2020, 13,198 vehicles/day
624	2029	**Huntington Ave** S4277	Repave	1 Urgent	$171,976 State revolving loan	11.70	Failed arterial road (condition 7), paved 2007, 15,823 vehicles/day

625	2029	**Saratoga St** S6938	Repave	1 Urgent	$156,629 State revolving loan	11.01	Failed arterial road (condition 7), paved 2007, 15,754 vehicles/day
626	2029	**Atlantic Ave** S16020	Repave	1 Urgent	$150,176 State revolving loan	10.55	Failed arterial road (condition 2), paved 2006, 15,326 vehicles/day
627	2029	**Columbia Rd** S1867	Repave	1 Urgent	$164,420 State revolving loan	10.52	Failed arterial road (condition 0), paved 2005, 14,333 vehicles/day
628	2029	**American Legion Hwy** S18344	Repave	1 Urgent	$173,902 State revolving loan	10.25	Failed arterial road (condition 0), paved 1998, 13,506 vehicles/day
629	2029	**Huntington Ave** S21786.1	Repave	1 Urgent	$157,364 State revolving loan	10.24	Failed arterial road (condition 0), paved 2005, 14,330 vehicles/day
630	2029	**Bennington St** S742	Repave	1 Urgent	$171,653 State revolving loan	10.18	Failed arterial road (condition 0), paved 1998, 13,506 vehicles/day
631	2029	**Prince St** S25982.1	Repave	1 Urgent	$171,286 State revolving loan	10.15	Failed arterial road (condition 0), paved 2004, 13,485 vehicles/day
632	2029	**Tremont St** S16954	Repave	1 Urgent	$143,590 State revolving loan	10.08	Failed arterial road (condition 3), paved 2006, 15,137 vehicles/day
633	2029	**Commonwealth Ave** S9270.1	Repave	1 Urgent	$162,201 State revolving loan	9.87	Failed arterial road (condition 0), paved 2000, 13,537 vehicles/day
634	2029	**W First St** S8299	Repave	1 Urgent	$142,943 State revolving loan	9.67	Failed arterial road (condition 4), paved 2006, 14,625 vehicles/day
635	2029	**Sumner St** S15036	Repave	1 Urgent	$145,045 State revolving loan	9.60	Failed arterial road (condition 0), paved 2005, 14,194 vehicles/day
636	2029	**Blue Hill Ave** S15409	Repave	1 Urgent	$152,631 State revolving loan	9.52	Failed arterial road (condition 0), paved 2004, 13,572 vehicles/day
637	2029	**Newbury St** S5659	Repave	1 Urgent	$152,381 State revolving loan	9.47	Failed arterial road (condition 0), paved 2001, 13,516 vehicles/day
638	2029	**Summer St** S16285	Repave	1 Urgent	$136,636 State revolving loan	9.44	Failed arterial road (condition 4), paved 2006, 14,765 vehicles/day
639	2029	**Commonwealth Ave** S19272	Repave	1 Urgent	$128,492 State revolving loan	9.39	Failed arterial road (condition 7), paved 2007, 15,663 vehicles/day
640	2029	**Commonwealth Ave** S11293.2	Repave	1 Urgent	$148,970 State revolving loan	9.28	Failed arterial road (condition 0), paved 2004, 13,448 vehicles/day
641	2029	**Chelsea St** S1614.1	Repave	1 Urgent	$123,112 State revolving loan	9.22	Failed arterial road (condition 6), paved 2007, 15,945 vehicles/day
642	2029	**Hyde Park Ave** S20100	Repave	1 Urgent	$132,109 State revolving loan	9.19	Failed arterial road (condition 4), paved 2006, 14,792 vehicles/day
643	2029	**Brighton Ave** S10959	Repave	1 Urgent	$129,536 State revolving loan	9.08	Failed arterial road (condition 4), paved 2006, 14,862 vehicles/day
644	2029	**Park St** S17883	Repave	1 Urgent	$139,135 State revolving loan	9.00	Failed arterial road (condition 0), paved 2004, 13,734 vehicles/day
645	2029	**Beacon St** S14151	Repave	1 Urgent	$121,818 State revolving loan	8.99	Failed arterial road (condition 2), paved 2006, 15,525 vehicles/day

646	2029	**Martin Luther King Jr Blvd** S17652.2	Repave	1 Urgent	$142,899 State revolving loan	8.92	Failed arterial road (condition 0), paved 2002, 13,323 vehicles/day
647	2029	**Commonwealth Ave** S9938.1	Repave	1 Urgent	$138,650 State revolving loan	8.76	Failed arterial road (condition 0), paved 2003, 13,398 vehicles/day
648	2029	**Rutherford Ave** S20393	Repave	1 Urgent	$138,195 State revolving loan	8.69	Failed arterial road (condition 0), paved 1998, 13,320 vehicles/day
649	2029	**Congress St** S21095.2	Repave	1 Urgent	$125,964 State revolving loan	8.67	Failed arterial road (condition 0), paved 2005, 14,418 vehicles/day
650	2029	**Washington St** S13064	Repave	1 Urgent	$136,386 State revolving loan	8.62	Failed arterial road (condition 0), paved 2002, 13,361 vehicles/day
651	2029	**Morton St** S18007	Repave	1 Urgent	$123,156 State revolving loan	8.55	Failed arterial road (condition 0), paved 2005, 14,533 vehicles/day
652	2029	**Dorchester Ave** S9784	Repave	1 Urgent	$115,409 State revolving loan	8.53	Failed arterial road (condition 1), paved 2006, 15,608 vehicles/day
653	2029	**Warren St** S17601	Repave	1 Urgent	$126,302 State revolving loan	8.34	Failed arterial road (condition 0), paved 2004, 13,821 vehicles/day
654	2029	**Belgrade Ave** S595	Repave	1 Urgent	$128,816 State revolving loan	8.31	Failed arterial road (condition 0), paved 2003, 13,534 vehicles/day
655	2029	**Brighton Ave** S14483	Repave	1 Urgent	$130,565 State revolving loan	8.30	Failed arterial road (condition 0), paved 1999, 13,352 vehicles/day
656	2029	**Arlington St** S16551	Repave	1 Urgent	$114,174 State revolving loan	8.18	Failed arterial road (condition 3), paved 2006, 15,184 vehicles/day
657	2029	**West St** S8365	Repave	1 Urgent	$117,732 State revolving loan	8.07	Failed arterial road (condition 0), paved 2005, 14,381 vehicles/day
658	2029	**E Broadway** S13932	Repave	1 Urgent	$126,375 State revolving loan	8.02	Failed arterial road (condition 0), paved 1999, 13,291 vehicles/day
659	2029	**John F. Fitzgerald Surface Rd** S19607	Repave	1 Urgent	$123,068 State revolving loan	7.97	Failed arterial road (condition 0), paved 1998, 13,543 vehicles/day
660	2029	**Boylston St** S11085	Repave	1 Urgent	$123,920 State revolving loan	7.94	Failed arterial road (condition 0), paved 2001, 13,401 vehicles/day
661	2029	**Babson St** S13970	Repave	1 Urgent	$117,805 State revolving loan	7.94	Failed arterial road (condition 0), paved 2005, 14,136 vehicles/day
662	2029	**Washington St** S20615	Repave	1 Urgent	$121,127 State revolving loan	7.72	Failed arterial road (condition 0), paved 2003, 13,329 vehicles/day
663	2029	**Washington St** S17529	Repave	1 Urgent	$105,457 Interest-free loan	7.64	Failed arterial road (condition 6), paved 2007, 15,862 vehicles/day
664	2029	**Porter St** S12664	Repave	1 Urgent	$113,733 State revolving loan	7.63	Failed arterial road (condition 0), paved 2005, 14,139 vehicles/day
665	2029	**Shawmut Ave** S10086	Repave	1 Urgent	$117,893 State revolving loan	7.62	Failed arterial road (condition 0), paved 1998, 13,533 vehicles/day
666	2029	**Blue Hill Ave** S13683	Repave	1 Urgent	$119,055 State revolving loan	7.59	Failed arterial road (condition 0), paved 2003, 13,339 vehicles/day

667	2029	**Austin St** S12049	Repave	1 Urgent	$110,102 Interest-free loan	7.54	Failed arterial road (condition 4), paved 2006, 14,670 vehicles/day
668	2029	**W Newton St** S10452	Repave	1 Urgent	$106,530 Interest-free loan	7.47	Failed arterial road (condition 3), paved 2006, 15,134 vehicles/day
669	2029	**Commonwealth Ave** S10694	Repave	1 Urgent	$109,396 Interest-free loan	7.45	Failed arterial road (condition 0), paved 2005, 14,475 vehicles/day
670	2029	**Federal St** S3107	Repave	1 Urgent	$112,777 Interest-free loan	7.36	Failed arterial road (condition 0), paved 2004, 13,756 vehicles/day
671	2029	**Commonwealth Ave** S10703	Repave	1 Urgent	$106,515 Interest-free loan	7.28	Failed arterial road (condition 0), paved 2005, 14,644 vehicles/day
672	2029	**Adams St** S98	Repave	1 Urgent	$105,016 Interest-free loan	7.25	Failed arterial road (condition 3), paved 2006, 14,998 vehicles/day
673	2029	**Lincoln St** S15663	Repave	1 Urgent	$111,205 Interest-free loan	7.14	Failed arterial road (condition 0), paved 1998, 13,566 vehicles/day
674	2029	**Perkins St** S6194	Repave	1 Urgent	$104,486 Interest-free loan	7.01	Failed arterial road (condition 0), paved 2005, 14,479 vehicles/day
675	2029	**Hyde Park Ave** S23058	Repave	1 Urgent	$103,575 Interest-free loan	6.97	Failed arterial road (condition 4), paved 2006, 14,723 vehicles/day
676	2029	**E Berkeley St** S14769	Repave	1 Urgent	$109,940 Interest-free loan	6.91	Failed arterial road (condition 0), paved 2001, 13,324 vehicles/day
677	2029	**Maverick St** S5136	Repave	1 Urgent	$99,768 Interest-free loan	6.85	Failed arterial road (condition 2), paved 2006, 15,276 vehicles/day
678	2029	**Wood Ave** S8630	Repave	1 Urgent	$98,636 Interest-free loan	6.84	Failed arterial road (condition 2), paved 2006, 15,498 vehicles/day
679	2029	**Washington St** S10550	Repave	1 Urgent	$98,812 Interest-free loan	6.78	Failed arterial road (condition 2), paved 2006, 15,341 vehicles/day
680	2029	**Norfolk St** S5733	Repave	1 Urgent	$106,324 Interest-free loan	6.75	Failed arterial road (condition 0), paved 2000, 13,600 vehicles/day
681	2029	**Lagrange St** S4529	Repave	1 Urgent	$106,280 Interest-free loan	6.70	Failed arterial road (condition 0), paved 1999, 13,505 vehicles/day
682	2029	**Border St** S21158	Repave	1 Urgent	$106,250 Interest-free loan	6.66	Failed arterial road (condition 0), paved 1998, 13,420 vehicles/day
683	2029	**Maverick St** S14279	Repave	1 Urgent	$104,016 Interest-free loan	6.65	Failed arterial road (condition 0), paved 2004, 13,813 vehicles/day
684	2029	**Brookline Ave** S15043	Repave	1 Urgent	$96,357 Interest-free loan	6.61	Failed arterial road (condition 1), paved 2006, 15,573 vehicles/day
685	2029	**John F. Fitzgerald Surface Rd** S20115	Repave	1 Urgent	$103,898 Interest-free loan	6.53	Failed arterial road (condition 0), paved 2001, 13,578 vehicles/day
686	2029	**Tremont St** S25002	Repave	1 Urgent	$99,503 Interest-free loan	6.49	Failed arterial road (condition 5), paved 2006, 14,593 vehicles/day
687	2029	**Hyde Park Ave** S22810	Repave	1 Urgent	$103,604 Interest-free loan	6.48	Failed arterial road (condition 0), paved 2002, 13,542 vehicles/day

688	2029	**Geneva Ave** S3379	Repave	1 Urgent	$98,224 Interest-free loan	6.38	Failed arterial road (condition 0), paved 2005, 14,480 vehicles/day
689	2029	**A St** S16291	Repave	1 Urgent	$95,607 Interest-free loan	6.37	Failed arterial road (condition 2), paved 2006, 15,243 vehicles/day
690	2029	**Cummins Hwy** S18256	Repave	1 Urgent	$99,150 Interest-free loan	6.34	Failed arterial road (condition 0), paved 2005, 14,179 vehicles/day
691	2029	**Columbus Ave** S23423	Repave	1 Urgent	$101,311 Interest-free loan	6.30	Failed arterial road (condition 0), paved 2001, 13,604 vehicles/day
692	2029	**Washington St** S8117	Repave	1 Urgent	$102,502 Interest-free loan	6.26	Failed arterial road (condition 0), paved 2000, 13,282 vehicles/day
693	2029	**D St** S12337	Repave	1 Urgent	$100,811 Interest-free loan	6.24	Failed arterial road (condition 0), paved 1998, 13,566 vehicles/day
694	2029	**Commonwealth Ave** S15426	Repave	1 Urgent	$98,165 Interest-free loan	6.00	Failed arterial road (condition 0), paved 1999, 13,628 vehicles/day
695	2029	**Dorchester Ave** S24051	Repave	1 Urgent	$95,431 Interest-free loan	5.79	Failed arterial road (condition 0), paved 2004, 13,816 vehicles/day
696	2029	**Centre St** S26039	Repave	1 Urgent	$96,945 Interest-free loan	5.79	Failed arterial road (condition 0), paved 2004, 13,419 vehicles/day
697	2029	**Warren St** S17302	Repave	1 Urgent	$93,049 Interest-free loan	5.78	Failed arterial road (condition 0), paved 2005, 14,452 vehicles/day
698	2029	**Washington St** S8158	Repave	1 Urgent	$95,651 Interest-free loan	5.76	Failed arterial road (condition 0), paved 2004, 13,686 vehicles/day
699	2029	**Saratoga St** S24809	Repave	1 Urgent	$92,946 Interest-free loan	5.76	Failed arterial road (condition 5), paved 2006, 14,589 vehicles/day
700	2029	**Blue Hill Ave** S862	Repave	1 Urgent	$95,695 Interest-free loan	5.73	Failed arterial road (condition 0), paved 2003, 13,601 vehicles/day
701	2029	**New Rutherford Ave** S23674	Repave	1 Urgent	$95,254 Interest-free loan	5.72	Failed arterial road (condition 0), paved 2004, 13,689 vehicles/day
702	2029	**Columbus Ave** S17439	Repave	1 Urgent	$89,345 Interest-free loan	5.71	Failed arterial road (condition 7), paved 2007, 15,820 vehicles/day
703	2029	**Columbus Ave** S21252	Repave	1 Urgent	$96,283 Interest-free loan	5.71	Failed arterial road (condition 0), paved 1999, 13,401 vehicles/day
704	2029	**Washington St** S8022	Repave	1 Urgent	$91,021 Interest-free loan	5.69	Failed arterial road (condition 3), paved 2006, 14,993 vehicles/day
705	2029	**American Legion Hwy** S26109	Repave	1 Urgent	$92,799 Interest-free loan	5.60	Failed arterial road (condition 0), paved 2005, 14,090 vehicles/day
706	2029	**Broadway** S24090	Repave	1 Urgent	$87,948 Interest-free loan	5.55	Failed arterial road (condition 6), paved 2007, 15,898 vehicles/day
707	2029	**Lagrange St** S4538	Repave	1 Urgent	$93,931 Interest-free loan	5.48	Failed arterial road (condition 0), paved 1998, 13,440 vehicles/day
708	2029	**Centre St** S1493	Repave	1 Urgent	$92,329 Interest-free loan	5.46	Failed arterial road (condition 0), paved 2004, 13,851 vehicles/day

709	2029	**Dorchester St** S24220	Repave	1 Urgent	$94,152 Interest-free loan	5.45	Failed arterial road (condition 0), paved 2003, 13,302 vehicles/day
710	2029	**Cambridge St** S1307	Repave	1 Urgent	$90,227 Interest-free loan	5.44	Failed arterial road (condition 4), paved 2006, 14,626 vehicles/day
711	2029	**Causeway St** S21937	Repave	1 Urgent	$89,066 Interest-free loan	5.42	Failed arterial road (condition 3), paved 2006, 14,953 vehicles/day
712	2029	**Dudley St** S2523	Repave	1 Urgent	$86,346 Interest-free loan	5.30	Failed arterial road (condition 1), paved 2006, 15,646 vehicles/day
713	2029	**India St** S13927	Repave	1 Urgent	$90,580 Interest-free loan	5.14	Failed arterial road (condition 0), paved 2001, 13,550 vehicles/day
714	2029	**Lagrange St** S4550	Repave	1 Urgent	$90,168 Interest-free loan	5.10	Failed arterial road (condition 0), paved 2004, 13,582 vehicles/day
715	2029	**Columbus Ave** S16547	Repave	1 Urgent	$85,155 Interest-free loan	5.05	Failed arterial road (condition 7), paved 2007, 15,702 vehicles/day
716	2029	**Boylston St** S12332	Repave	1 Urgent	$90,124 Interest-free loan	5.02	Failed arterial road (condition 0), paved 1998, 13,388 vehicles/day
717	2029	**Dorchester Ave** S2442	Repave	1 Urgent	$89,771 Interest-free loan	4.99	Failed arterial road (condition 0), paved 2004, 13,413 vehicles/day
718	2029	**Bennington St** S19783	Repave	1 Urgent	$89,609 Interest-free loan	4.97	Failed arterial road (condition 0), paved 2004, 13,415 vehicles/day
719	2029	**Washington St** S8139	Repave	1 Urgent	$84,317 Interest-free loan	4.96	Failed arterial road (condition 7), paved 2007, 15,789 vehicles/day
720	2029	**Washington St** S17521	Repave	1 Urgent	$86,434 Interest-free loan	4.95	Failed arterial road (condition 4), paved 2006, 14,684 vehicles/day
721	2029	**Bennington St** S12156	Repave	1 Urgent	$87,434 Interest-free loan	4.94	Failed arterial road (condition 0), paved 2005, 14,098 vehicles/day
722	2029	**Washington St** S17533	Repave	1 Urgent	$88,404 Interest-free loan	4.89	Failed arterial road (condition 0), paved 1999, 13,584 vehicles/day
723	2029	**Shawmut Ave** S8777	Repave	1 Urgent	$84,685 Interest-free loan	4.87	Failed arterial road (condition 3), paved 2006, 15,144 vehicles/day
724	2029	**Dorchester Ave** S15370	Repave	1 Urgent	$87,992 Interest-free loan	4.82	Failed arterial road (condition 0), paved 2000, 13,552 vehicles/day
725	2029	**Causeway St** S21964	Repave	1 Urgent	$87,816 Interest-free loan	4.79	Failed arterial road (condition 0), paved 2003, 13,519 vehicles/day
726	2029	**Medford St** S9053	Repave	1 Urgent	$83,303 Interest-free loan	4.78	Failed arterial road (condition 7), paved 2007, 15,751 vehicles/day
727	2029	**Washington St** S21842	Repave	1 Urgent	$87,757 Interest-free loan	4.71	Failed arterial road (condition 0), paved 2004, 13,303 vehicles/day
728	2029	**Bowdoin St** S935	Repave	1 Urgent	$86,772 Interest-free loan	4.69	Failed arterial road (condition 0), paved 2001, 13,629 vehicles/day
729	2029	**Centre St** S1470	Repave	1 Urgent	$87,595 Interest-free loan	4.69	Failed arterial road (condition 0), paved 2000, 13,318 vehicles/day

730	2029	**Warren St** S17607	Repave	1 Urgent	$85,332 Interest-free loan	4.48	Failed arterial road (condition 0), paved 2004, 13,566 vehicles/day
731	2029	**Saint Alphonsus St** S17389	Repave	1 Urgent	$85,552 Interest-free loan	4.47	Failed arterial road (condition 0), paved 2000, 13,441 vehicles/day
732	2029	**Berkeley St** S750	Repave	1 Urgent	$84,979 Rate revenue	4.44	Failed arterial road (condition 0), paved 2000, 13,573 vehicles/day
733	2029	**S Huntington Ave** S7192	Repave	1 Urgent	$82,597 Rate revenue	4.36	Failed arterial road (condition 0), paved 2005, 14,413 vehicles/day
734	2029	**W Newton St** S25246	Repave	1 Urgent	$84,200 Rate revenue	4.30	Failed arterial road (condition 0), paved 2004, 13,472 vehicles/day
735	2029	**Washington St** S8168	Repave	1 Urgent	$82,686 Rate revenue	4.17	Failed arterial road (condition 0), paved 2004, 13,733 vehicles/day
736	2029	**Chestnut Hill Ave** S1660	Repave	1 Urgent	$79,187 Rate revenue	4.15	Failed arterial road (condition 6), paved 2007, 15,937 vehicles/day
737	2029	**Bowdoin St** S19824	Repave	1 Urgent	$79,937 Rate revenue	4.13	Failed arterial road (condition 3), paved 2006, 15,194 vehicles/day
738	2029	**S Huntington Ave** S18426	Repave	1 Urgent	$82,788 Rate revenue	4.12	Failed arterial road (condition 0), paved 1998, 13,537 vehicles/day
739	2029	**Harrison Ave** S3823	Repave	1 Urgent	$80,186 Rate revenue	4.08	Failed arterial road (condition 4), paved 2006, 14,900 vehicles/day
740	2029	**New Chardon St** S23951	Repave	1 Urgent	$82,156 Rate revenue	3.99	Failed arterial road (condition 0), paved 2000, 13,370 vehicles/day
741	2029	**John F. Fitzgerald Surface Rd** S20377	Repave	1 Urgent	$81,568 Rate revenue	3.93	Failed arterial road (condition 0), paved 2003, 13,457 vehicles/day
742	2029	**Brookline Ave** S27122	Repave	1 Urgent	$80,216 Rate revenue	3.91	Failed arterial road (condition 0), paved 2005, 14,145 vehicles/day
743	2029	**Centre St** S1496	Repave	1 Urgent	$78,893 Rate revenue	3.89	Failed arterial road (condition 3), paved 2006, 14,985 vehicles/day
744	2029	**Washington St** S8147	Repave	1 Urgent	$79,334 Rate revenue	3.79	Failed arterial road (condition 0), paved 2005, 14,212 vehicles/day
745	2029	**Chelsea St** S1602	Repave	1 Urgent	$79,981 Rate revenue	3.65	Failed arterial road (condition 0), paved 2003, 13,293 vehicles/day
746	2029	**Brookline Ave** S12679	Repave	1 Urgent	$76,776 Rate revenue	3.54	Failed arterial road (condition 3), paved 2006, 15,093 vehicles/day
747	2029	**Perkins St** S26930	Repave	1 Urgent	$75,497 Rate revenue	3.45	Failed arterial road (condition 1), paved 2006, 15,695 vehicles/day
748	2029	**American Legion Hwy** S18071	Repave	1 Urgent	$76,482 Rate revenue	3.28	Failed arterial road (condition 1), paved 2005, 14,067 vehicles/day
749	2029	**Centre St** S1458	Repave	1 Urgent	$76,144 Rate revenue	3.12	Failed arterial road (condition 0), paved 2003, 13,621 vehicles/day
750	2029	**Dorchester St** S2486	Repave	1 Urgent	$75,732 Rate revenue	3.08	Failed arterial road (condition 0), paved 2004, 13,763 vehicles/day
751	2029	**Centre St** S18510	Repave	1 Urgent	$74,762 Rate revenue	2.99	Failed arterial road (condition 0), paved 2005, 14,158 vehicles/day
752	2029	**Southampton St** S12479	Repave	1 Urgent	$75,085 Rate revenue	2.92	Failed arterial road (condition 0), paved 2004, 13,533 vehicles/day
753	2029	**River St** S26850	Repave	1 Urgent	$73,939 Rate revenue	2.77	Failed arterial road (condition 0), paved 2004, 13,809 vehicles/day
754	2029	**Beacon St** S24931	Repave shared dig B-2029-S24931	1 Urgent	$47,076 State revolving loan	2.74	Failed arterial road (condition 0), paved 2005, 14,764 vehicles/day
755	2029	**Massachusetts Ave** S16378	Repave	1 Urgent	$73,924 Rate revenue	2.72	Failed arterial road (condition 0), paved 2004, 13,525 vehicles/day
756	2029	**Adams St** S27575	Repave shared dig B-2029-S27575	1 Urgent	$45,268 Rate revenue	2.67	Failed arterial road (condition 0), paved 2002, 13,528 vehicles/day

757	2029	**Fairmount Ave** S18978	Repave	1 Urgent	$104,633 Rate revenue	2.56	Failed collector road (condition 23), paved 2004, 6,168 vehicles/day
758	2029	**Washington St** S25140	Repave	1 Urgent	$73,218 Rate revenue	2.55	Failed arterial road (condition 0), paved 1998, 13,311 vehicles/day
759	2029	**Bennington St** S20441	Repave	1 Urgent	$71,748 Rate revenue	2.45	Failed arterial road (condition 0), paved 2005, 14,333 vehicles/day
760	2029	**Norfolk St** S5735	Repave	1 Urgent	$70,381 Rate revenue	2.37	Failed arterial road (condition 1), paved 2006, 15,685 vehicles/day
761	2029	**D St** S26947	Repave shared dig B-2029-S26947	1 Urgent	$41,299 Interest-free loan	2.22	Failed arterial road (condition 3), paved 2006, 15,053 vehicles/day
762	2029	**Longwood Ave** S4808	Repave	1 Urgent	$71,116 Rate revenue	2.21	Failed arterial road (condition 0), paved 2000, 13,625 vehicles/day
763	2029	**Dorchester St** S2387	Repave	1 Urgent	$69,573 Rate revenue	2.11	Failed arterial road (condition 3), paved 2006, 15,161 vehicles/day
764	2029	**Shawmut Ave** S8786	Repave	1 Urgent	$70,087 Rate revenue	2.04	Failed arterial road (condition 0), paved 2004, 13,791 vehicles/day
765	2029	**Morton St** S26989	Repave	1 Urgent	$68,985 Rate revenue	2.02	Failed arterial road (condition 2), paved 2006, 15,483 vehicles/day
766	2029	**Columbia Rd** S25731	Repave	1 Urgent	$69,881 Rate revenue	1.96	Failed arterial road (condition 0), paved 2002, 13,555 vehicles/day
767	2029	**Norfolk St** S25830	Repave	1 Urgent	$69,690 Rate revenue	1.90	Failed arterial road (condition 0), paved 2000, 13,372 vehicles/day
768	2029	**New Chardon St** S23949	Repave shared dig B-2029-S23949	1 Urgent	$37,741 Rate revenue	1.69	Failed arterial road (condition 2), paved 2006, 15,330 vehicles/day
769	2029	**Commonwealth Ave** S19533	Repave	1 Urgent	$68,441 Rate revenue	1.66	Failed arterial road (condition 0), paved 1999, 13,467 vehicles/day
770	2029	**Warren St** S17610	Repave shared dig B-2029-S17610	1 Urgent	$37,094 Rate revenue	1.60	Failed arterial road (condition 2), paved 2005, 13,769 vehicles/day
771	2029	**Bowdoin St** S945	Repave	1 Urgent	$67,794 Rate revenue	1.54	Failed arterial road (condition 0), paved 1999, 13,624 vehicles/day
772	2029	**Devonshire St** S2364	Repave shared dig B-2029-S2364	1 Urgent	$37,388 Rate revenue	1.53	Failed arterial road (condition 0), paved 1999, 13,577 vehicles/day
773	2029	**Warren St** S27321	Repave shared dig B-2029-S27321	1 Urgent	$36,933 Rate revenue	1.40	Failed arterial road (condition 0), paved 2003, 13,349 vehicles/day
774	2029	**Chelsea St** S13999	Repave shared dig B-2029-S13999	1 Urgent	$35,183 Rate revenue	1.35	Failed arterial road (condition 0), paved 2005, 14,414 vehicles/day
775	2029	**Hyde Park Ave** S27275	Repave engineering review	1 Urgent	$65,780 Rate revenue	1.09	Failed arterial road (condition 0), paved 2004, 13,561 vehicles/day
776	2029	**Beacon St** S24931	Replace water main shared dig B-2029-S24931	4 Monitor	$71,751 Rate revenue	2.74	Moderate risk (index 27): cast iron main from 1914, 1 prior breaks, PoF 78
777	2029	**Adams St** S27575	Reline water main shared dig B-2029-S27575	4 Monitor	$48,928 Rate revenue	2.67	Low risk (index 23): cast iron main from 1939, 1 prior breaks, PoF 74
778	2029	**D St** S26947	Replace water main shared dig B-2029-S26947	4 Monitor	$57,308 Rate revenue	2.22	Moderate risk (index 29): cast iron main from 1924, 1 prior breaks, PoF 87
779	2029	**New Chardon St** S23949	Replace water main shared dig B-2029-S23949	4 Monitor	$48,414 Rate revenue	1.69	Low risk (index 20): cast iron main from 1895, 0 prior breaks, PoF 60
780	2029	**Warren St** S17610	Replace water main shared dig B-2029-S17610	4 Monitor	$46,797 Rate revenue	1.60	Moderate risk (index 26): cast iron main from 1911, 1 prior breaks, PoF 80
781	2029	**Devonshire St** S2364	Replace water main shared dig B-2029-S2364	4 Monitor	$47,532 Rate revenue	1.53	Low risk (index 19): cast iron main from 1904, 1 prior breaks, PoF 80
782	2029	**Warren St** S27321	Replace water main shared dig B-2029-S27321	4 Monitor	$46,392 Rate revenue	1.40	Low risk (index 19): cast iron main from 1899, 0 prior breaks, PoF 64
783	2029	**Chelsea St** S13999	Replace water main shared dig B-2029-S13999	4 Monitor	$42,019 Rate revenue	1.35	Low risk (index 25): cast iron main from 1892, 1 prior breaks, PoF 78
784	2029	**W Second St** S11811	Repave engineering review	4 Monitor	$101,179 Rate revenue	1.10	Fair arterial road (condition 73), paved 2019, 11,775 vehicles/day

785	2029	**Tremont St** S10161	Replace water main shared dig B-2029-S10161 engineering review	4 Monitor	$99,792 Rate revenue	1.02	High risk (index 67): cast iron main from 1893, 2 prior breaks, PoF 91, serves a critical facility
786	2029	**Tremont St** S10161	Repave shared dig B-2029-S10161 engineering review	4 Monitor	$58,292 Rate revenue	1.02	Fair arterial road (condition 81), paved 2022, 15,592 vehicles/day
787	2030	**Boylston St** S975	Repave	1 Urgent	$172,831 State revolving loan	10.47	Failed arterial road (condition 7), paved 2008, 15,726 vehicles/day
788	2030	**E Brookline St** S10771	Repave	1 Urgent	$169,968 State revolving loan	10.07	Failed arterial road (condition 3), paved 2007, 15,109 vehicles/day
789	2030	**Blue Hill Ave** S12671	Repave	1 Urgent	$167,593 State revolving loan	10.00	Failed arterial road (condition 3), paved 2007, 15,131 vehicles/day
790	2030	**Commonwealth Ave** S10029	Repave	1 Urgent	$162,921 State revolving loan	9.95	Failed arterial road (condition 2), paved 2007, 15,324 vehicles/day
791	2030	**Saratoga St** S6941	Repave	1 Urgent	$162,025 State revolving loan	9.54	Failed arterial road (condition 4), paved 2007, 14,789 vehicles/day
792	2030	**E Broadway** S2407	Repave	1 Urgent	$152,697 State revolving loan	9.33	Failed arterial road (condition 3), paved 2007, 15,066 vehicles/day
793	2030	**Huntington Ave** S21786.2	Repave	1 Urgent	$168,380 State revolving loan	9.21	Failed arterial road (condition 1), paved 2006, 13,820 vehicles/day
794	2030	**Hyde Park Ave** S19601	Repave	1 Urgent	$171,510 State revolving loan	9.00	Failed arterial road (condition 0), paved 2005, 13,296 vehicles/day
795	2030	**Melnea Cass Blvd** S19768	Repave	1 Urgent	$147,145 State revolving loan	8.85	Failed arterial road (condition 4), paved 2007, 14,747 vehicles/day
796	2030	**Talbot Ave** S10955	Repave	1 Urgent	$136,574 State revolving loan	8.75	Failed arterial road (condition 7), paved 2008, 15,692 vehicles/day
797	2030	**Malcolm X Blvd** S6814	Repave	1 Urgent	$168,647 State revolving loan	8.75	Failed arterial road (condition 0), paved 2002, 13,060 vehicles/day
798	2030	**Hyde Park Ave** S13082.3	Repave	1 Urgent	$169,701 State revolving loan	8.72	Failed arterial road (condition 0), paved 2002, 12,972 vehicles/day
799	2030	**Beacon St** S10511	Repave	1 Urgent	$153,987 State revolving loan	8.63	Failed arterial road (condition 0), paved 2005, 13,726 vehicles/day
800	2030	**American Legion Hwy** S18642	Repave	1 Urgent	$130,912 State revolving loan	8.56	Failed arterial road (condition 6), paved 2008, 15,951 vehicles/day
801	2030	**Tremont St** S25516	Repave	1 Urgent	$160,263 State revolving loan	8.53	Failed arterial road (condition 0), paved 2000, 13,178 vehicles/day
802	2030	**Chelsea St** S1610	Repave	1 Urgent	$160,609 State revolving loan	8.49	Failed arterial road (condition 0), paved 1999, 13,093 vehicles/day
803	2030	**Maffa Way** S15287	Repave	1 Urgent	$160,955 State revolving loan	8.44	Failed arterial road (condition 0), paved 2005, 13,001 vehicles/day
804	2030	**Hyde Park Ave** S21779	Repave	1 Urgent	$158,140 State revolving loan	8.42	Failed arterial road (condition 0), paved 1999, 13,124 vehicles/day
805	2030	**Seaver St** S14562.1	Repave	1 Urgent	$158,627 State revolving loan	8.39	Failed arterial road (condition 0), paved 1998, 13,050 vehicles/day

806	2030	**N Beacon St** S12233.1	Repave	1 Urgent	$152,902 State revolving loan	8.28	Failed arterial road (condition 0), paved 2001, 13,235 vehicles/day
807	2030	**E Broadway** S2404	Repave	1 Urgent	$153,562 State revolving loan	8.19	Failed arterial road (condition 0), paved 2003, 13,052 vehicles/day
808	2030	**W Milton St** S18956	Repave	1 Urgent	$153,625 State revolving loan	8.12	Failed arterial road (condition 0), paved 2003, 12,922 vehicles/day
809	2030	**Marginal Rd** S17536	Repave	1 Urgent	$134,939 State revolving loan	8.05	Failed arterial road (condition 0), paved 2006, 14,311 vehicles/day
810	2030	**Townsend St** S7641	Repave	1 Urgent	$129,103 State revolving loan	8.00	Failed arterial road (condition 3), paved 2007, 14,990 vehicles/day
811	2030	**Summer St** S19506	Repave	1 Urgent	$146,799 State revolving loan	7.98	Failed arterial road (condition 0), paved 2000, 13,165 vehicles/day
812	2030	**Summer St** S19476	Repave	1 Urgent	$148,765 State revolving loan	7.98	Failed arterial road (condition 0), paved 1999, 13,024 vehicles/day
813	2030	**Commonwealth Ave** S16867	Repave	1 Urgent	$126,287 State revolving loan	7.73	Failed arterial road (condition 4), paved 2007, 14,834 vehicles/day
814	2030	**Washington St** S20128	Repave	1 Urgent	$136,653 State revolving loan	7.68	Failed arterial road (condition 2), paved 2006, 13,559 vehicles/day
815	2030	**E Broadway** S11617	Repave	1 Urgent	$118,957 State revolving loan	7.53	Failed arterial road (condition 2), paved 2007, 15,413 vehicles/day
816	2030	**Freeport St** S14254	Repave	1 Urgent	$138,305 State revolving loan	7.52	Failed arterial road (condition 0), paved 2000, 13,047 vehicles/day
817	2030	**Dorchester Ave** S22768	Repave	1 Urgent	$121,757 State revolving loan	7.35	Failed arterial road (condition 4), paved 2007, 14,702 vehicles/day
818	2030	**American Legion Hwy** S11889.2	Repave	1 Urgent	$131,399 State revolving loan	7.34	Failed arterial road (condition 0), paved 2005, 13,369 vehicles/day
819	2030	**Seaver St** S17460	Repave	1 Urgent	$116,205 State revolving loan	7.31	Failed arterial road (condition 7), paved 2008, 15,658 vehicles/day
820	2030	**Cummins Hwy** S10950	Repave	1 Urgent	$123,613 State revolving loan	7.31	Failed arterial road (condition 5), paved 2007, 14,395 vehicles/day
821	2030	**Maverick St** S5142	Repave	1 Urgent	$132,469 State revolving loan	7.19	Failed arterial road (condition 0), paved 1998, 12,996 vehicles/day
822	2030	**Congress St** S19479	Repave	1 Urgent	$129,418 State revolving loan	7.14	Failed arterial road (condition 0), paved 2001, 13,203 vehicles/day
823	2030	**Dorchester Ave** S10558	Repave	1 Urgent	$130,298 State revolving loan	7.09	Failed arterial road (condition 0), paved 2002, 13,022 vehicles/day
824	2030	**Cummins Hwy** S15277	Repave	1 Urgent	$122,591 State revolving loan	7.07	Failed arterial road (condition 1), paved 2006, 13,914 vehicles/day
825	2030	**Dorchester Ave** S22025	Repave	1 Urgent	$116,850 State revolving loan	6.98	Failed arterial road (condition 4), paved 2007, 14,692 vehicles/day
826	2030	**Andrew P Mcardle Brg** S26352	Repave	1 Urgent	$117,730 Interest-free loan	6.92	Failed arterial road (condition 0), paved 2006, 14,262 vehicles/day

827	2030	**Walk Hill St** S10401	Repave	1 Urgent	$126,696 State revolving loan	6.91	Failed arterial road (condition 0), paved 2004, 13,074 vehicles/day
828	2030	**Washington St** S19579	Repave	1 Urgent	$115,953 Interest-free loan	6.89	Failed arterial road (condition 0), paved 2006, 14,493 vehicles/day
829	2030	**Saratoga St** S16770	Repave	1 Urgent	$114,632 Interest-free loan	6.89	Failed arterial road (condition 4), paved 2007, 14,847 vehicles/day
830	2030	**Magazine St** S25611	Repave	1 Urgent	$110,574 Interest-free loan	6.87	Failed arterial road (condition 2), paved 2007, 15,514 vehicles/day
831	2030	**Old Colony Ave** S10566	Repave	1 Urgent	$110,165 Interest-free loan	6.81	Failed arterial road (condition 7), paved 2008, 15,684 vehicles/day
832	2030	**Huntington Ave** S13770	Repave	1 Urgent	$125,202 Interest-free loan	6.78	Failed arterial road (condition 0), paved 2001, 12,984 vehicles/day
833	2030	**Heath St** S17357	Repave	1 Urgent	$120,656 Interest-free loan	6.67	Failed arterial road (condition 0), paved 2005, 13,337 vehicles/day
834	2030	**Essex St** S14173	Repave	1 Urgent	$119,099 Interest-free loan	6.65	Failed arterial road (condition 0), paved 2005, 13,515 vehicles/day
835	2030	**Congress St** S12512	Repave	1 Urgent	$112,854 Interest-free loan	6.52	Failed arterial road (condition 5), paved 2007, 14,402 vehicles/day
836	2030	**Sudbury St** S22059	Repave	1 Urgent	$107,679 Interest-free loan	6.48	Failed arterial road (condition 2), paved 2007, 15,247 vehicles/day
837	2030	**Washington St** S21574	Repave	1 Urgent	$115,387 Interest-free loan	6.32	Failed arterial road (condition 0), paved 2005, 13,366 vehicles/day
838	2030	**Dorchester Ave** S2423	Repave	1 Urgent	$116,472 Interest-free loan	6.32	Failed arterial road (condition 0), paved 2001, 13,192 vehicles/day
839	2030	**Belvidere St** S15314	Repave	1 Urgent	$108,481 Interest-free loan	6.28	Failed arterial road (condition 4), paved 2007, 14,656 vehicles/day
840	2030	**Harrison Ave** S10316	Repave	1 Urgent	$104,848 Interest-free loan	6.24	Failed arterial road (condition 7), paved 2008, 15,552 vehicles/day
841	2030	**Dudley St** S19534	Repave	1 Urgent	$107,082 Interest-free loan	6.23	Failed arterial road (condition 4), paved 2007, 14,825 vehicles/day
842	2030	**Adams St** S38	Repave	1 Urgent	$114,144 Interest-free loan	6.15	Failed arterial road (condition 0), paved 2005, 13,182 vehicles/day
843	2030	**Francis St** S3145	Repave	1 Urgent	$107,176 Interest-free loan	6.09	Failed arterial road (condition 5), paved 2007, 14,495 vehicles/day
844	2030	**Columbia Rd** S1869	Repave	1 Urgent	$113,830 Interest-free loan	6.08	Failed arterial road (condition 0), paved 2003, 13,095 vehicles/day
845	2030	**Tremont St** S22399	Repave	1 Urgent	$113,326 Interest-free loan	6.07	Failed arterial road (condition 0), paved 2000, 13,141 vehicles/day
846	2030	**Washington St** S8166	Repave	1 Urgent	$110,400 Interest-free loan	5.90	Failed arterial road (condition 0), paved 2002, 13,260 vehicles/day
847	2030	**Blue Hill Ave** S17720	Repave	1 Urgent	$103,999 Interest-free loan	5.89	Failed arterial road (condition 0), paved 2006, 14,557 vehicles/day

848	2030	**Neponset Ave** S5608	Repave	1 Urgent	$102,347 Interest-free loan	5.74	Failed arterial road (condition 4), paved 2007, 14,738 vehicles/day
849	2030	**Washington St** S17894	Repave	1 Urgent	$102,614 Interest-free loan	5.74	Failed arterial road (condition 4), paved 2007, 14,671 vehicles/day
850	2030	**Washington St** S8151	Repave	1 Urgent	$108,308 Interest-free loan	5.71	Failed arterial road (condition 0), paved 2003, 13,209 vehicles/day
851	2030	**A St** S16293	Repave	1 Urgent	$109,095 Interest-free loan	5.71	Failed arterial road (condition 0), paved 2002, 13,047 vehicles/day
852	2030	**Columbia Rd** S10197	Repave	1 Urgent	$100,255 Interest-free loan	5.62	Failed arterial road (condition 3), paved 2007, 14,977 vehicles/day
853	2030	**Harrison Ave** S3822	Repave	1 Urgent	$99,689 Interest-free loan	5.61	Failed arterial road (condition 8), paved 2008, 15,353 vehicles/day
854	2030	**Marginal Rd** S10598	Repave	1 Urgent	$96,606 Interest-free loan	5.47	Failed arterial road (condition 7), paved 2008, 15,854 vehicles/day
855	2030	**Saratoga St** S21746	Repave	1 Urgent	$97,770 Interest-free loan	5.44	Failed arterial road (condition 8), paved 2008, 15,440 vehicles/day
856	2030	**Kneeland St** S4505	Repave	1 Urgent	$97,675 Interest-free loan	5.43	Failed arterial road (condition 8), paved 2008, 15,460 vehicles/day
857	2030	**Adams St** S17880	Repave	1 Urgent	$96,275 Interest-free loan	5.40	Failed arterial road (condition 7), paved 2008, 15,778 vehicles/day
858	2030	**Washington St** S8098	Repave	1 Urgent	$104,313 Interest-free loan	5.36	Failed arterial road (condition 0), paved 2002, 13,160 vehicles/day
859	2030	**Dorchester Ave** S2419	Repave	1 Urgent	$96,810 Interest-free loan	5.32	Failed arterial road (condition 8), paved 2008, 15,432 vehicles/day
860	2030	**Cummins Hwy** S10076	Repave	1 Urgent	$104,187 Interest-free loan	5.30	Failed arterial road (condition 0), paved 2001, 13,053 vehicles/day
861	2030	**Centre St** S15251	Repave	1 Urgent	$95,646 Interest-free loan	5.29	Failed arterial road (condition 2), paved 2007, 15,465 vehicles/day
862	2030	**Adams St** S73	Repave	1 Urgent	$102,614 Interest-free loan	5.25	Failed arterial road (condition 0), paved 2005, 13,279 vehicles/day
863	2030	**Blue Hill Ave** S839	Repave	1 Urgent	$103,291 Interest-free loan	5.21	Failed arterial road (condition 0), paved 2003, 13,002 vehicles/day
864	2030	**Columbus Ave** S23164	Repave	1 Urgent	$95,284 Interest-free loan	5.13	Failed arterial road (condition 3), paved 2007, 15,142 vehicles/day
865	2030	**Belvidere St** S8941	Repave	1 Urgent	$93,995 Interest-free loan	5.10	Failed arterial road (condition 2), paved 2007, 15,500 vehicles/day
866	2030	**Norfolk St** S18030	Repave	1 Urgent	$93,790 Interest-free loan	5.01	Failed arterial road (condition 7), paved 2008, 15,549 vehicles/day
867	2030	**Dorchester Ave** S2434	Repave	1 Urgent	$95,583 Interest-free loan	4.92	Failed arterial road (condition 0), paved 2006, 14,326 vehicles/day
868	2030	**Columbus Ave** S22364	Repave	1 Urgent	$92,343 Interest-free loan	4.88	Failed arterial road (condition 7), paved 2008, 15,686 vehicles/day

869	2030	**Heath St** S15239	Repave	1 Urgent	$96,118 Interest-free loan	4.86	Failed arterial road (condition 1), paved 2006, 13,990 vehicles/day
870	2030	**Beacon St** S22275	Repave	1 Urgent	$99,028 Interest-free loan	4.80	Failed arterial road (condition 0), paved 1999, 12,958 vehicles/day
871	2030	**Main St** S4914	Repave	1 Urgent	$92,249 Interest-free loan	4.74	Failed arterial road (condition 3), paved 2007, 15,102 vehicles/day
872	2030	**Centre St** S1483	Repave	1 Urgent	$93,350 Interest-free loan	4.72	Failed arterial road (condition 0), paved 2006, 14,498 vehicles/day
873	2030	**Milk St** S10351	Repave	1 Urgent	$97,329 Interest-free loan	4.70	Failed arterial road (condition 0), paved 2003, 13,126 vehicles/day
874	2030	**Columbus Ave** S20241	Repave	1 Urgent	$91,714 Interest-free loan	4.67	Failed arterial road (condition 3), paved 2007, 15,087 vehicles/day
875	2030	**Washington St** S8106	Repave	1 Urgent	$93,145 Interest-free loan	4.65	Failed arterial road (condition 0), paved 2006, 14,360 vehicles/day
876	2030	**Main St** S4905	Repave	1 Urgent	$96,747 Interest-free loan	4.65	Failed arterial road (condition 0), paved 2003, 13,153 vehicles/day
877	2030	**N Harvard St** S12774	Repave	1 Urgent	$95,615 Interest-free loan	4.64	Failed arterial road (condition 0), paved 2005, 13,484 vehicles/day
878	2030	**Milk St** S5211	Repave	1 Urgent	$89,433 Interest-free loan	4.53	Failed arterial road (condition 7), paved 2008, 15,793 vehicles/day
879	2030	**Harvard St** S3877	Repave	1 Urgent	$89,512 Interest-free loan	4.49	Failed arterial road (condition 7), paved 2008, 15,644 vehicles/day
880	2030	**Columbus Ave** S15302	Repave	1 Urgent	$95,363 Interest-free loan	4.47	Failed arterial road (condition 0), paved 2000, 13,048 vehicles/day
881	2030	**Dartmouth St** S2244	Repave	1 Urgent	$90,912 Interest-free loan	4.47	Failed arterial road (condition 4), paved 2007, 14,787 vehicles/day
882	2030	**E First St** S2648	Repave	1 Urgent	$95,221 Interest-free loan	4.46	Failed arterial road (condition 0), paved 2001, 13,073 vehicles/day
883	2030	**Portland St** S16111	Repave	1 Urgent	$88,851 Interest-free loan	4.36	Failed arterial road (condition 2), paved 2007, 15,284 vehicles/day
884	2030	**Federal St** S16408	Repave	1 Urgent	$94,639 Interest-free loan	4.35	Failed arterial road (condition 0), paved 2003, 12,926 vehicles/day
885	2030	**Clarendon St** S1756	Repave	1 Urgent	$89,496 Rate revenue	4.31	Failed arterial road (condition 4), paved 2007, 14,864 vehicles/day
886	2030	**Columbia Rd** S1856	Repave	1 Urgent	$93,350 Interest-free loan	4.31	Failed arterial road (condition 0), paved 2000, 13,207 vehicles/day
887	2030	**Blue Hill Ave** S18147	Repave	1 Urgent	$90,628 Interest-free loan	4.29	Failed arterial road (condition 0), paved 2006, 14,171 vehicles/day
888	2030	**D St** S2080	Repave	1 Urgent	$93,413 Interest-free loan	4.28	Failed arterial road (condition 0), paved 2001, 13,103 vehicles/day
889	2030	**Centre St** S26125	Repave	1 Urgent	$92,799 Interest-free loan	4.24	Failed arterial road (condition 0), paved 2000, 13,175 vehicles/day

890	2030	**Adams St** S91	Repave	1 Urgent	$87,294 Rate revenue	4.19	Failed arterial road (condition 2), paved 2007, 15,464 vehicles/day
891	2030	**Arlington St** S345	Repave	1 Urgent	$91,808 Rate revenue	4.15	Failed arterial road (condition 0), paved 1999, 13,230 vehicles/day
892	2030	**Winship St** S8594	Repave	1 Urgent	$92,579 Rate revenue	4.14	Failed arterial road (condition 0), paved 1999, 12,929 vehicles/day
893	2030	**Dorchester Ave** S9778	Repave	1 Urgent	$91,258 Rate revenue	4.10	Failed arterial road (condition 0), paved 1999, 13,277 vehicles/day
894	2030	**Cummins Hwy** S27267	Repave	1 Urgent	$91,226 Rate revenue	4.05	Failed arterial road (condition 0), paved 2001, 13,142 vehicles/day
895	2030	**Harrison Ave** S3818	Repave	1 Urgent	$87,294 Rate revenue	4.04	Failed arterial road (condition 3), paved 2007, 14,954 vehicles/day
896	2030	**Vine St** S9385	Repave	1 Urgent	$90,833 Rate revenue	3.99	Failed arterial road (condition 0), paved 2003, 13,078 vehicles/day
897	2030	**Exeter St** S3000	Repave	1 Urgent	$86,838 Rate revenue	3.92	Failed arterial road (condition 4), paved 2007, 14,770 vehicles/day
898	2030	**Brookline Ave** S11743	Repave	1 Urgent	$88,269 Rate revenue	3.89	Failed arterial road (condition 1), paved 2006, 13,842 vehicles/day
899	2030	**Kneeland St** S16008	Repave	1 Urgent	$88,379 Rate revenue	3.88	Failed arterial road (condition 1), paved 2006, 13,781 vehicles/day
900	2030	**Morton St** S18008	Repave	1 Urgent	$84,321 Rate revenue	3.70	Failed arterial road (condition 2), paved 2007, 15,302 vehicles/day
901	2030	**Belgrade Ave** S18698	Repave	1 Urgent	$84,982 Rate revenue	3.69	Failed arterial road (condition 4), paved 2007, 14,899 vehicles/day
902	2030	**Washington St** S8137	Repave	1 Urgent	$88,552 Rate revenue	3.69	Failed arterial road (condition 0), paved 2001, 12,969 vehicles/day
903	2030	**Essex St** S13551	Repave	1 Urgent	$84,714 Rate revenue	3.69	Failed arterial road (condition 3), paved 2007, 15,031 vehicles/day
904	2030	**W Newton St** S8308	Repave	1 Urgent	$87,498 Rate revenue	3.62	Failed arterial road (condition 0), paved 1998, 13,176 vehicles/day
905	2030	**Hanover St** S3755	Repave	1 Urgent	$87,184 Rate revenue	3.57	Failed arterial road (condition 0), paved 2000, 13,114 vehicles/day
906	2030	**Centre St** S18419	Repave	1 Urgent	$82,654 Rate revenue	3.53	Failed arterial road (condition 6), paved 2008, 15,885 vehicles/day
907	2030	**Shawmut Ave** S10600	Repave	1 Urgent	$85,642 Rate revenue	3.41	Failed arterial road (condition 0), paved 1998, 13,259 vehicles/day
908	2030	**Hancock St** S21286	Repave	1 Urgent	$85,831 Rate revenue	3.39	Failed arterial road (condition 0), paved 2000, 13,073 vehicles/day
909	2030	**Shawmut Ave** S8782	Repave	1 Urgent	$85,548 Rate revenue	3.36	Failed arterial road (condition 0), paved 1999, 13,130 vehicles/day
910	2030	**Warren St** S26887	Repave	1 Urgent	$85,107 Rate revenue	3.30	Failed arterial road (condition 0), paved 2003, 13,090 vehicles/day
911	2030	**Washington St** S22796	Repave	1 Urgent	$83,220 Rate revenue	3.24	Failed arterial road (condition 1), paved 2006, 13,955 vehicles/day
912	2030	**Centre St** S20842	Repave	1 Urgent	$84,242 Rate revenue	3.17	Failed arterial road (condition 0), paved 1999, 13,022 vehicles/day
913	2030	**Commonwealth Ave** S13214	Repave	1 Urgent	$83,833 Rate revenue	3.14	Failed arterial road (condition 0), paved 2001, 13,137 vehicles/day
914	2030	**Shawmut Ave** S10599	Repave	1 Urgent	$80,436 Rate revenue	3.05	Failed arterial road (condition 3), paved 2007, 15,176 vehicles/day
915	2030	**Porter St** S12663	Repave	1 Urgent	$82,827 Rate revenue	3.02	Failed arterial road (condition 0), paved 2005, 13,231 vehicles/day
916	2030	**Chelsea St** S14000	Repave	1 Urgent	$81,049 Rate revenue	2.96	Failed arterial road (condition 0), paved 2006, 14,153 vehicles/day
917	2030	**Warren St** S25485	Repave	1 Urgent	$82,543 Rate revenue	2.96	Failed arterial road (condition 0), paved 1998, 13,123 vehicles/day
918	2030	**Clarendon St** S1559	Repave	1 Urgent	$82,638 Rate revenue	2.95	Failed arterial road (condition 0), paved 2002, 13,023 vehicles/day

919	2030	**Summer St** S15223	Repave	1 Urgent	$81,584 Rate revenue	2.92	Failed arterial road (condition 0), paved 2005, 13,582 vehicles/day
920	2030	**A St** S27471	Repave	1 Urgent	$78,328 Rate revenue	2.76	Failed arterial road (condition 7), paved 2008, 15,763 vehicles/day
921	2030	**Harrison Ave** S3816	Repave	1 Urgent	$79,020 Rate revenue	2.47	Failed arterial road (condition 0), paved 2004, 13,230 vehicles/day
922	2030	**Lincoln St** S15768	Repave	1 Urgent	$78,281 Rate revenue	2.42	Failed arterial road (condition 2), paved 2006, 13,662 vehicles/day
923	2030	**Sumner St** S10324	Repave shared dig B-2030-S10324	1 Urgent	$47,162 Rate revenue	2.30	Failed arterial road (condition 0), paved 2006, 14,368 vehicles/day
924	2030	**Preble St** S6367	Repave shared dig B-2030-S6367	1 Urgent	$46,093 Interest-free loan	2.23	Failed arterial road (condition 4), paved 2007, 14,815 vehicles/day
925	2030	**Washington St** S8112	Repave shared dig B-2030-S8112	1 Urgent	$44,803 Rate revenue	2.22	Failed arterial road (condition 0), paved 2006, 14,290 vehicles/day
926	2030	**Dudley St** S20013	Repave shared dig B-2030-S20013	1 Urgent	$39,439 Rate revenue	1.48	Failed arterial road (condition 2), paved 2007, 15,405 vehicles/day
927	2030	**Ruggles St** S14287	Repave shared dig B-2030-S14287	1 Urgent	$38,810 Rate revenue	1.38	Failed arterial road (condition 2), paved 2007, 15,430 vehicles/day
928	2030	**Old Colony Ave** S27390	Repave shared dig B-2030-S27390 engineering review	1 Urgent	$38,197 Rate revenue	1.09	Failed arterial road (condition 0), paved 2004, 12,943 vehicles/day
929	2030	**Sumner St** S10324	Replace water main shared dig B-2030-S10324	4 Monitor	$68,751 Rate revenue	2.30	Moderate risk (index 27): cast iron main from 1937, 2 prior breaks, PoF 84
930	2030	**Preble St** S6367	Replace water main shared dig B-2030-S6367	4 Monitor	$66,077 Rate revenue	2.23	Moderate risk (index 26): cast iron main from 1924, 1 prior breaks, PoF 87
931	2030	**Washington St** S8112	Reline water main shared dig B-2030-S8112	4 Monitor	$47,811 Rate revenue	2.22	Moderate risk (index 25): cast iron main from 1946, 1 prior breaks, PoF 84
932	2030	**Dudley St** S20013	Replace water main shared dig B-2030-S20013	4 Monitor	$49,443 Rate revenue	1.48	Low risk (index 21): cast iron main from 1894, 0 prior breaks, PoF 60
933	2030	**Ruggles St** S14287	Replace water main shared dig B-2030-S14287	4 Monitor	$47,870 Rate revenue	1.38	Low risk (index 20): cast iron main from 1903, 0 prior breaks, PoF 60
934	2030	**Old Colony Ave** S27390	Replace water main shared dig B-2030-S27390 engineering review	4 Monitor	$46,337 Rate revenue	1.09	Low risk (index 18): cast iron main from 1894, 0 prior breaks, PoF 67
935	2031	**Bremen St** S11662	Repave	1 Urgent	$195,987 State revolving loan	9.86	Failed arterial road (condition 3), paved 2008, 15,133 vehicles/day
936	2031	**Commonwealth Ave** S11073	Repave	1 Urgent	$183,145 State revolving loan	9.36	Failed arterial road (condition 8), paved 2009, 15,242 vehicles/day
937	2031	**Old Colony Ave** S12482	Repave	1 Urgent	$169,984 State revolving loan	8.85	Failed arterial road (condition 4), paved 2008, 14,883 vehicles/day
938	2031	**Columbus Ave** S21839	Repave	1 Urgent	$157,479 State revolving loan	8.55	Failed arterial road (condition 3), paved 2008, 15,195 vehicles/day
939	2031	**Rutherford Ave** S19776.1	Repave	1 Urgent	$197,855 State revolving loan	8.43	Failed arterial road (condition 0), paved 2002, 12,746 vehicles/day
940	2031	**Tremont St** S11012	Repave	1 Urgent	$187,100 State revolving loan	8.22	Failed arterial road (condition 0), paved 1998, 12,838 vehicles/day
941	2031	**Boardman St** S15667.1	Repave	1 Urgent	$157,125 State revolving loan	8.10	Failed arterial road (condition 5), paved 2008, 14,485 vehicles/day
942	2031	**Seaver St** S9747	Repave	1 Urgent	$184,189 State revolving loan	8.04	Failed arterial road (condition 0), paved 2004, 12,672 vehicles/day
943	2031	**Seaver St** S15361.2	Repave	1 Urgent	$169,176 State revolving loan	7.98	Failed arterial road (condition 3), paved 2007, 13,416 vehicles/day

944	2031	**Commonwealth Ave** S1885	Repave	1 Urgent	$151,251 State revolving loan	7.87	Failed arterial road (condition 5), paved 2008, 14,523 vehicles/day
945	2031	**Commonwealth Ave** S12956	Repave	1 Urgent	$174,865 State revolving loan	7.85	Failed arterial road (condition 0), paved 2005, 12,800 vehicles/day
946	2031	**Ashmont St** S390	Repave	1 Urgent	$157,664 State revolving loan	7.83	Failed arterial road (condition 1), paved 2007, 13,839 vehicles/day
947	2031	**Boylston St** S977	Repave	1 Urgent	$172,626 State revolving loan	7.83	Failed arterial road (condition 0), paved 2005, 12,874 vehicles/day
948	2031	**Geneva Ave** S17882	Repave	1 Urgent	$147,969 State revolving loan	7.62	Failed arterial road (condition 5), paved 2008, 14,346 vehicles/day
949	2031	**W Dedham St** S11971	Repave	1 Urgent	$162,679 State revolving loan	7.40	Failed arterial road (condition 0), paved 1998, 12,700 vehicles/day
950	2031	**Ruggles St** S16853	Repave	1 Urgent	$161,989 State revolving loan	7.39	Failed arterial road (condition 0), paved 1998, 12,731 vehicles/day
951	2031	**E First St** S2646	Repave	1 Urgent	$161,265 State revolving loan	7.37	Failed arterial road (condition 0), paved 2006, 12,738 vehicles/day
952	2031	**Reservation Rd** S19005	Repave	1 Urgent	$156,267 State revolving loan	7.27	Failed arterial road (condition 0), paved 2001, 12,880 vehicles/day
953	2031	**Quincy St** S6460	Repave	1 Urgent	$128,261 State revolving loan	7.18	Failed arterial road (condition 7), paved 2009, 15,790 vehicles/day
954	2031	**Blue Hill Ave** S9074	Repave	1 Urgent	$137,484 State revolving loan	7.11	Failed arterial road (condition 5), paved 2008, 14,379 vehicles/day
955	2031	**Martha Rd** S23980	Repave	1 Urgent	$143,459 State revolving loan	7.08	Failed arterial road (condition 2), paved 2007, 13,610 vehicles/day
956	2031	**Malcolm X Blvd** S14432	Repave	1 Urgent	$151,369 State revolving loan	7.06	Failed arterial road (condition 0), paved 2003, 12,855 vehicles/day
957	2031	**Federal St** S3106	Repave	1 Urgent	$148,979 State revolving loan	7.05	Failed arterial road (condition 0), paved 2006, 13,008 vehicles/day
958	2031	**Congress St** S22287	Repave	1 Urgent	$137,063 State revolving loan	6.94	Failed arterial road (condition 1), paved 2007, 13,936 vehicles/day
959	2031	**Atlantic Ave** S15997	Repave	1 Urgent	$149,198 State revolving loan	6.94	Failed arterial road (condition 0), paved 1999, 12,784 vehicles/day
960	2031	**Hyde Park Ave** S23814	Repave	1 Urgent	$146,185 State revolving loan	6.89	Failed arterial road (condition 0), paved 2006, 12,930 vehicles/day
961	2031	**Andrew P Mcardle Brg** S26565	Repave	1 Urgent	$146,926 State revolving loan	6.88	Failed arterial road (condition 0), paved 1999, 12,849 vehicles/day
962	2031	**Hyde Park Ave** S21314	Repave	1 Urgent	$126,746 State revolving loan	6.87	Failed arterial road (condition 8), paved 2009, 15,411 vehicles/day
963	2031	**Chelsea St** S10790	Repave	1 Urgent	$143,240 State revolving loan	6.75	Failed arterial road (condition 0), paved 2004, 12,919 vehicles/day
964	2031	**Reservation Rd** S15099.1	Repave	1 Urgent	$145,815 State revolving loan	6.74	Failed arterial road (condition 0), paved 2003, 12,685 vehicles/day

965	2031	**Granite Ave** S3560	Repave	1 Urgent	$140,513 State revolving loan	6.60	Failed arterial road (condition 0), paved 2006, 12,873 vehicles/day
966	2031	**Old Colony Ave** S5870	Repave	1 Urgent	$122,521 State revolving loan	6.50	Failed arterial road (condition 8), paved 2009, 15,271 vehicles/day
967	2031	**Talbot Ave** S7512	Repave	1 Urgent	$133,125 State revolving loan	6.25	Failed arterial road (condition 0), paved 2001, 12,894 vehicles/day
968	2031	**Dorchester Ave** S2449	Repave	1 Urgent	$120,973 Interest-free loan	6.25	Failed arterial road (condition 4), paved 2008, 14,690 vehicles/day
969	2031	**Washington St** S8017	Repave	1 Urgent	$122,134 State revolving loan	6.23	Failed arterial road (condition 5), paved 2008, 14,480 vehicles/day
970	2031	**Tremont St** S7661	Repave	1 Urgent	$132,973 State revolving loan	6.17	Failed arterial road (condition 0), paved 2000, 12,745 vehicles/day
971	2031	**Dorchester Ave** S17886	Repave	1 Urgent	$129,960 State revolving loan	6.05	Failed arterial road (condition 0), paved 2000, 12,833 vehicles/day
972	2031	**Centre St** S1452	Repave	1 Urgent	$130,937 State revolving loan	6.03	Failed arterial road (condition 0), paved 2001, 12,673 vehicles/day
973	2031	**Washington St** S8083	Repave	1 Urgent	$114,308 Interest-free loan	6.00	Failed arterial road (condition 7), paved 2009, 15,539 vehicles/day
974	2031	**Bennington St** S9484	Repave	1 Urgent	$129,035 State revolving loan	5.95	Failed arterial road (condition 0), paved 1999, 12,736 vehicles/day
975	2031	**Dorchester Ave** S2440	Repave	1 Urgent	$128,883 Interest-free loan	5.89	Failed arterial road (condition 0), paved 2003, 12,619 vehicles/day
976	2031	**Cambridge St** S24512	Repave	1 Urgent	$114,426 Interest-free loan	5.85	Failed arterial road (condition 4), paved 2008, 14,920 vehicles/day
977	2031	**Harvard St** S3871	Repave	1 Urgent	$118,061 Interest-free loan	5.84	Failed arterial road (condition 6), paved 2008, 14,260 vehicles/day
978	2031	**Columbus Ave** S12867	Repave	1 Urgent	$113,887 Interest-free loan	5.83	Failed arterial road (condition 8), paved 2009, 15,250 vehicles/day
979	2031	**Seaver St** S17456	Repave	1 Urgent	$126,308 Interest-free loan	5.82	Failed arterial road (condition 0), paved 1998, 12,786 vehicles/day
980	2031	**Cross St** S22269	Repave	1 Urgent	$126,359 Interest-free loan	5.81	Failed arterial road (condition 0), paved 1998, 12,758 vehicles/day
981	2031	**Porter St** S20055	Repave	1 Urgent	$125,972 Interest-free loan	5.76	Failed arterial road (condition 0), paved 2002, 12,680 vehicles/day
982	2031	**E First St** S19331	Repave	1 Urgent	$125,618 Interest-free loan	5.75	Failed arterial road (condition 0), paved 2003, 12,712 vehicles/day
983	2031	**Washington St** S20586	Repave	1 Urgent	$111,480 Interest-free loan	5.71	Failed arterial road (condition 8), paved 2009, 15,421 vehicles/day
984	2031	**Stuart St** S24453	Repave	1 Urgent	$123,767 Interest-free loan	5.65	Failed arterial road (condition 0), paved 1999, 12,738 vehicles/day
985	2031	**Grove St** S15711	Repave	1 Urgent	$123,312 Interest-free loan	5.64	Failed arterial road (condition 0), paved 2003, 12,771 vehicles/day

986	2031	**Wood Ave** S18802	Repave	1 Urgent	$122,000 Interest-free loan	5.58	Failed arterial road (condition 0), paved 2004, 12,822 vehicles/day
987	2031	**Harvard St** S13603	Repave	1 Urgent	$120,922 Interest-free loan	5.55	Failed arterial road (condition 0), paved 2004, 12,897 vehicles/day
988	2031	**Columbus Ave** S11628	Repave	1 Urgent	$121,629 Interest-free loan	5.54	Failed arterial road (condition 0), paved 1998, 12,772 vehicles/day
989	2031	**South St** S18509	Repave	1 Urgent	$120,956 Interest-free loan	5.52	Failed arterial road (condition 0), paved 2001, 12,837 vehicles/day
990	2031	**Tremont St** S13288	Repave	1 Urgent	$117,270 Interest-free loan	5.50	Failed arterial road (condition 3), paved 2007, 13,466 vehicles/day
991	2031	**Meridian St** S19283	Repave	1 Urgent	$105,724 Interest-free loan	5.42	Failed arterial road (condition 6), paved 2009, 15,997 vehicles/day
992	2031	**Bennington St** S10632	Repave	1 Urgent	$117,371 Interest-free loan	5.21	Failed arterial road (condition 0), paved 2001, 12,644 vehicles/day
993	2031	**N Harvard St** S14652	Repave	1 Urgent	$116,765 Interest-free loan	5.21	Failed arterial road (condition 0), paved 2001, 12,730 vehicles/day
994	2031	**Cambridge St** S20125	Repave	1 Urgent	$112,305 Interest-free loan	5.15	Failed arterial road (condition 3), paved 2007, 13,480 vehicles/day
995	2031	**Western Ave** S25213	Repave	1 Urgent	$105,051 Interest-free loan	5.10	Failed arterial road (condition 8), paved 2009, 15,378 vehicles/day
996	2031	**Washington St** S15420	Repave	1 Urgent	$104,950 Interest-free loan	5.01	Failed arterial road (condition 4), paved 2008, 14,917 vehicles/day
997	2031	**Washington St** S15421	Repave	1 Urgent	$109,175 Interest-free loan	5.00	Failed arterial road (condition 2), paved 2007, 13,712 vehicles/day
998	2031	**Harrison Ave** S22941	Repave	1 Urgent	$105,876 Interest-free loan	4.98	Failed arterial road (condition 5), paved 2008, 14,599 vehicles/day
999	2031	**Massachusetts Ave** S21868	Repave	1 Urgent	$112,726 Interest-free loan	4.94	Failed arterial road (condition 0), paved 1999, 12,772 vehicles/day
1000	2031	**Seaport Blvd** S19853	Repave	1 Urgent	$111,632 Interest-free loan	4.89	Failed arterial road (condition 0), paved 2001, 12,845 vehicles/day
1001	2031	**Porter St** S6351	Repave	1 Urgent	$112,709 Interest-free loan	4.89	Failed arterial road (condition 0), paved 2002, 12,636 vehicles/day
1002	2031	**Boston St** S11410	Repave	1 Urgent	$105,118 Interest-free loan	4.87	Failed arterial road (condition 0), paved 2007, 14,301 vehicles/day
1003	2031	**Washington St** S8055	Repave	1 Urgent	$102,779 Interest-free loan	4.86	Failed arterial road (condition 3), paved 2008, 15,091 vehicles/day
1004	2031	**American Legion Hwy** S18656	Repave	1 Urgent	$111,800 Interest-free loan	4.84	Failed arterial road (condition 0), paved 2006, 12,682 vehicles/day
1005	2031	**Washington St** S15466	Repave	1 Urgent	$110,841 Interest-free loan	4.83	Failed arterial road (condition 0), paved 1999, 12,840 vehicles/day
1006	2031	**Centre St** S19567	Repave	1 Urgent	$109,814 Interest-free loan	4.77	Failed arterial road (condition 0), paved 2002, 12,902 vehicles/day

1007	2031	**Washington St** S8036	Repave	1 Urgent	$109,730 Interest-free loan	4.74	Failed arterial road (condition 0), paved 1998, 12,818 vehicles/day
1008	2031	**Franklin St** S3155	Repave	1 Urgent	$109,410 Interest-free loan	4.72	Failed arterial road (condition 0), paved 1998, 12,832 vehicles/day
1009	2031	**Blue Hill Ave** S871	Repave	1 Urgent	$106,701 Interest-free loan	4.64	Failed arterial road (condition 0), paved 2006, 13,231 vehicles/day
1010	2031	**Causeway St** S24039	Repave	1 Urgent	$104,041 Interest-free loan	4.64	Failed arterial road (condition 1), paved 2007, 13,942 vehicles/day
1011	2031	**New Chardon St** S16062	Repave	1 Urgent	$107,895 Interest-free loan	4.63	Failed arterial road (condition 0), paved 2000, 12,912 vehicles/day
1012	2031	**Ruggles St** S19128	Repave	1 Urgent	$99,497 Interest-free loan	4.62	Failed arterial road (condition 7), paved 2009, 15,639 vehicles/day
1013	2031	**Columbia Rd** S1782	Repave	1 Urgent	$104,967 Interest-free loan	4.56	Failed arterial road (condition 0), paved 2006, 13,418 vehicles/day
1014	2031	**Columbia Rd** S1863	Repave	1 Urgent	$99,598 Interest-free loan	4.34	Failed arterial road (condition 0), paved 2007, 14,344 vehicles/day
1015	2031	**Washington St** S8037	Repave	1 Urgent	$98,252 Interest-free loan	4.33	Failed arterial road (condition 8), paved 2009, 15,206 vehicles/day
1016	2031	**E First St** S19330	Repave	1 Urgent	$103,940 Interest-free loan	4.27	Failed arterial road (condition 0), paved 2000, 12,829 vehicles/day
1017	2031	**Shawmut Ave** S8787	Repave	1 Urgent	$97,646 Interest-free loan	4.25	Failed arterial road (condition 4), paved 2008, 14,889 vehicles/day
1018	2031	**Tremont St** S15643	Repave	1 Urgent	$95,575 Interest-free loan	4.24	Failed arterial road (condition 6), paved 2009, 15,868 vehicles/day
1019	2031	**Washington St** S8097	Repave	1 Urgent	$103,637 Interest-free loan	4.22	Failed arterial road (condition 0), paved 2001, 12,743 vehicles/day
1020	2031	**Hyde Park Ave** S13229	Repave	1 Urgent	$98,958 Interest-free loan	4.18	Failed arterial road (condition 6), paved 2008, 14,227 vehicles/day
1021	2031	**Old Colony Ave** S12506	Repave	1 Urgent	$102,628 Interest-free loan	4.15	Failed arterial road (condition 0), paved 2005, 12,789 vehicles/day
1022	2031	**Centre St** S18427	Repave	1 Urgent	$101,971 Interest-free loan	4.10	Failed arterial road (condition 0), paved 2004, 12,830 vehicles/day
1023	2031	**Dorchester Ave** S2439	Repave	1 Urgent	$101,803 Interest-free loan	4.03	Failed arterial road (condition 0), paved 2001, 12,640 vehicles/day
1024	2031	**Meridian St** S19417	Repave	1 Urgent	$99,379 Interest-free loan	4.02	Failed arterial road (condition 3), paved 2007, 13,433 vehicles/day
1025	2031	**Dartmouth St** S2242	Repave	1 Urgent	$98,403 Interest-free loan	4.01	Failed arterial road (condition 2), paved 2007, 13,716 vehicles/day
1026	2031	**Arlington St** S344	Repave	1 Urgent	$94,869 Interest-free loan	3.98	Failed arterial road (condition 8), paved 2009, 15,303 vehicles/day
1027	2031	**Geneva Ave** S10035	Repave	1 Urgent	$100,271 Interest-free loan	3.92	Failed arterial road (condition 0), paved 2002, 12,742 vehicles/day

1028	2031	**W Newton St** S15556	Repave	1 Urgent	$95,845 Interest-free loan	3.90	Failed arterial road (condition 5), paved 2008, 14,401 vehicles/day
1029	2031	**Avenue Louis Pasteur** S24892	Repave	1 Urgent	$92,512 Rate revenue	3.88	Failed arterial road (condition 6), paved 2009, 15,955 vehicles/day
1030	2031	**Adams St** S99	Repave	1 Urgent	$94,364 Rate revenue	3.77	Failed arterial road (condition 0), paved 2007, 14,350 vehicles/day
1031	2031	**Saratoga St** S24898	Repave	1 Urgent	$98,740 Interest-free loan	3.76	Failed arterial road (condition 0), paved 2003, 12,680 vehicles/day
1032	2031	**Border St** S799	Repave	1 Urgent	$98,083 Interest-free loan	3.76	Failed arterial road (condition 0), paved 2005, 12,888 vehicles/day
1033	2031	**Stuart St** S12894	Repave	1 Urgent	$94,852 Rate revenue	3.75	Failed arterial road (condition 0), paved 2007, 14,079 vehicles/day
1034	2031	**Hereford St** S10381	Repave	1 Urgent	$97,848 Rate revenue	3.71	Failed arterial road (condition 0), paved 1999, 12,797 vehicles/day
1035	2031	**Milk St** S16042	Repave	1 Urgent	$98,134 Rate revenue	3.69	Failed arterial road (condition 0), paved 2004, 12,621 vehicles/day
1036	2031	**Warren St** S25489	Repave	1 Urgent	$95,054 Rate revenue	3.64	Failed arterial road (condition 2), paved 2007, 13,633 vehicles/day
1037	2031	**Shawmut Ave** S8781	Repave	1 Urgent	$96,838 Rate revenue	3.63	Failed arterial road (condition 0), paved 2005, 12,856 vehicles/day
1038	2031	**Massachusetts Ave** S9109	Repave	1 Urgent	$97,040 Rate revenue	3.59	Failed arterial road (condition 0), paved 2002, 12,644 vehicles/day
1039	2031	**Huntington Ave** S22919	Repave	1 Urgent	$97,073 Rate revenue	3.59	Failed arterial road (condition 0), paved 2004, 12,613 vehicles/day
1040	2031	**Meridian St** S5253	Repave	1 Urgent	$96,350 Rate revenue	3.55	Failed arterial road (condition 0), paved 2002, 12,723 vehicles/day
1041	2031	**Albany St** S17512	Repave	1 Urgent	$96,030 Rate revenue	3.50	Failed arterial road (condition 0), paved 1999, 12,685 vehicles/day
1042	2031	**Morton St** S5453	Repave	1 Urgent	$90,493 Rate revenue	3.40	Failed arterial road (condition 4), paved 2008, 14,909 vehicles/day
1043	2031	**Maffa Way** S24687	Repave	1 Urgent	$93,202 Rate revenue	3.40	Failed arterial road (condition 2), paved 2007, 13,491 vehicles/day
1044	2031	**Bowdoin St** S14738	Repave shared dig B-2031-S14738	1 Urgent	$70,694 Rate revenue	3.38	Failed arterial road (condition 0), paved 2005, 12,710 vehicles/day
1045	2031	**Dorchester St** S11855	Repave	1 Urgent	$93,421 Rate revenue	3.29	Failed arterial road (condition 0), paved 2002, 12,893 vehicles/day
1046	2031	**South St** S7203	Repave	1 Urgent	$93,640 Rate revenue	3.27	Failed arterial road (condition 0), paved 2004, 12,728 vehicles/day
1047	2031	**City Sq** S16143	Repave	1 Urgent	$92,916 Rate revenue	3.19	Failed arterial road (condition 0), paved 2002, 12,701 vehicles/day
1048	2031	**Hancock St** S20458	Repave	1 Urgent	$92,142 Rate revenue	3.15	Failed arterial road (condition 0), paved 1999, 12,894 vehicles/day
1049	2031	**Huntington Ave** S26990	Repave	1 Urgent	$92,294 Rate revenue	3.13	Failed arterial road (condition 0), paved 2002, 12,743 vehicles/day
1050	2031	**Columbus Ave** S22141	Repave	1 Urgent	$91,452 Rate revenue	3.06	Failed arterial road (condition 0), paved 2000, 12,834 vehicles/day
1051	2031	**Vine St** S7847	Repave	1 Urgent	$87,648 Rate revenue	2.92	Failed arterial road (condition 0), paved 2007, 14,313 vehicles/day
1052	2031	**Cummins Hwy** S9243	Repave	1 Urgent	$90,408 Rate revenue	2.91	Failed arterial road (condition 0), paved 2004, 12,651 vehicles/day
1053	2031	**E First St** S11657	Repave	1 Urgent	$86,975 Rate revenue	2.81	Failed arterial road (condition 5), paved 2008, 14,388 vehicles/day
1054	2031	**Milton St** S5368	Repave	1 Urgent	$85,831 Rate revenue	2.58	Failed arterial road (condition 1), paved 2007, 13,829 vehicles/day
1055	2031	**Chestnut Hill Ave** S1658	Repave	1 Urgent	$83,407 Rate revenue	2.46	Failed arterial road (condition 3), paved 2008, 15,211 vehicles/day

1056	2031	**Cummins Hwy** S23268	Repave	1 Urgent	$84,282 Rate revenue	2.45	Failed arterial road (condition 0), paved 2007, 14,300 vehicles/day
1057	2031	**Chelsea St** S11735	Repave shared dig B-2031-S11735	1 Urgent	$49,370 Rate revenue	2.34	Failed arterial road (condition 4), paved 2008, 14,800 vehicles/day
1058	2031	**Main St** S11821	Repave	1 Urgent	$81,892 Rate revenue	2.31	Failed arterial road (condition 1), paved 2008, 15,771 vehicles/day
1059	2031	**Saratoga St** S24838	Repave	1 Urgent	$85,006 Rate revenue	2.30	Failed arterial road (condition 0), paved 2006, 12,816 vehicles/day
1060	2031	**Freeport St** S21910	Repave	1 Urgent	$83,727 Rate revenue	2.19	Failed arterial road (condition 0), paved 2006, 13,174 vehicles/day
1061	2031	**Commonwealth Ave** S19274	Repave	1 Urgent	$83,390 Rate revenue	2.18	Failed arterial road (condition 0), paved 2006, 13,395 vehicles/day
1062	2031	**Longwood Ave** S20940	Repave	1 Urgent	$81,758 Rate revenue	2.14	Failed arterial road (condition 4), paved 2008, 14,847 vehicles/day
1063	2031	**Centre St** S1454	Repave	1 Urgent	$83,575 Rate revenue	2.12	Failed arterial road (condition 0), paved 2002, 12,887 vehicles/day
1064	2031	**Milk St** S10350	Repave	1 Urgent	$82,868 Rate revenue	2.08	Failed arterial road (condition 0), paved 2001, 13,234 vehicles/day
1065	2031	**Commonwealth Ave** S24959	Repave shared dig B-2031-S24959	1 Urgent	$44,035 Rate revenue	1.87	Failed arterial road (condition 4), paved 2008, 14,836 vehicles/day
1066	2031	**Stuart St** S22568	Repave shared dig B-2031-S22568	1 Urgent	$48,831 Rate revenue	1.82	Failed arterial road (condition 0), paved 2006, 12,819 vehicles/day
1067	2031	**Dartmouth St** S27150	Repave shared dig B-2031-S27150	1 Urgent	$40,062 Rate revenue	1.27	Failed arterial road (condition 3), paved 2008, 15,043 vehicles/day
1068	2031	**Washington St** S27405	Repave shared dig B-2031-S27405	1 Urgent	$42,368 Rate revenue	1.25	Failed arterial road (condition 0), paved 1999, 12,780 vehicles/day
1069	2031	**Norfolk St** S20800	Repave shared dig B-2031-S20800 engineering review	1 Urgent	$40,837 Rate revenue	1.01	Failed arterial road (condition 0), paved 2006, 12,807 vehicles/day
1070	2031	**Bowdoin St** S14738	Reline water main shared dig B-2031-S14738	4 Monitor	$79,602 Rate revenue	3.38	Moderate risk (index 46): cast iron main from 1944, 1 prior breaks, PoF 77, serves a critical facility
1071	2031	**Chelsea St** S11735	Replace water main shared dig B-2031-S11735	4 Monitor	$70,829 Rate revenue	2.34	High risk (index 56): cast iron main from 1920, 1 prior breaks, PoF 91, serves a critical facility
1072	2031	**Commonwealth Ave** S24959	Replace water main shared dig B-2031-S24959	4 Monitor	$57,491 Rate revenue	1.87	Moderate risk (index 44): cast iron main from 1909, 1 prior breaks, PoF 78, serves a critical facility
1073	2031	**Stuart St** S22568	Replace water main shared dig B-2031-S22568	4 Monitor	$69,482 Rate revenue	1.82	Low risk (index 24): cast iron main from 1888, 1 prior breaks, PoF 84
1074	2031	**Dartmouth St** S27150	Replace water main shared dig B-2031-S27150	4 Monitor	$47,561 Rate revenue	1.27	Moderate risk (index 42): cast iron main from 1855, 0 prior breaks, PoF 67, serves a critical facility
1075	2031	**Washington St** S27405	Replace water main shared dig B-2031-S27405	4 Monitor	$53,325 Rate revenue	1.25	Low risk (index 19): ductile iron main from 1957, 2 prior breaks, PoF 67
1076	2031	**Melnea Cass Blvd** S20063	Repave engineering review	4 Monitor	$190,870 Rate revenue	1.04	Fair arterial road (condition 83), paved 2024, 13,653 vehicles/day
1077	2031	**Norfolk St** S20800	Replace water main shared dig B-2031-S20800 engineering review	4 Monitor	$49,496 Rate revenue	1.01	Low risk (index 17): cast iron main from 1902, 0 prior breaks, PoF 64
1078	2031	**Stoughton St** S17836	Repave engineering review	4 Monitor	$120,199 Rate revenue	1.00	Fair arterial road (condition 76), paved 2022, 13,041 vehicles/day
1079	2032	**Adams St** S18014	Repave	1 Urgent	$201,836 State revolving loan	8.83	Failed arterial road (condition 9), paved 2010, 15,122 vehicles/day
1080	2032	**Summer St** S19415	Repave	1 Urgent	$184,836 State revolving loan	8.32	Failed arterial road (condition 4), paved 2009, 14,810 vehicles/day
1081	2032	**Blue Hill Ave** S15616	Repave	1 Urgent	$176,300 State revolving loan	8.27	Failed arterial road (condition 8), paved 2010, 15,433 vehicles/day
1082	2032	**Blue Hill Ave** S17679	Repave	1 Urgent	$161,875 State revolving loan	7.99	Failed arterial road (condition 6), paved 2010, 15,880 vehicles/day

1083	2032	**Melnea Cass Blvd** S23259	Repave	1 Urgent	$175,345 State revolving loan	7.79	Failed arterial road (condition 5), paved 2009, 14,434 vehicles/day
1084	2032	**Beacon St** S13736	Repave	1 Urgent	$167,259 State revolving loan	7.61	Failed arterial road (condition 5), paved 2009, 14,606 vehicles/day
1085	2032	**Bremen St** S1052	Repave	1 Urgent	$192,021 State revolving loan	7.51	Failed arterial road (condition 0), paved 2007, 12,881 vehicles/day
1086	2032	**Union Park St** S14726	Repave	1 Urgent	$196,974 State revolving loan	7.45	Failed arterial road (condition 0), paved 2006, 12,580 vehicles/day
1087	2032	**Chelsea St** S10787.1	Repave	1 Urgent	$165,891 State revolving loan	7.42	Failed arterial road (condition 5), paved 2009, 14,355 vehicles/day
1088	2032	**Rutherford Ave** S14204.1	Repave	1 Urgent	$152,240 State revolving loan	7.23	Failed arterial road (condition 3), paved 2009, 15,047 vehicles/day
1089	2032	**Saint James Ave** S12261	Repave	1 Urgent	$186,763 State revolving loan	7.20	Failed arterial road (condition 0), paved 2005, 12,569 vehicles/day
1090	2032	**Cambridge St** S14588	Repave	1 Urgent	$188,816 State revolving loan	7.19	Failed arterial road (condition 0), paved 2005, 12,459 vehicles/day
1091	2032	**Commonwealth Ave** S15096.2	Repave	1 Urgent	$150,187 State revolving loan	7.18	Failed arterial road (condition 8), paved 2010, 15,386 vehicles/day
1092	2032	**Rutherford Ave** S24732.2	Repave	1 Urgent	$184,692 State revolving loan	7.13	Failed arterial road (condition 0), paved 2006, 12,545 vehicles/day
1093	2032	**Dorchester Ave** S2456	Repave	1 Urgent	$146,982 State revolving loan	7.11	Failed arterial road (condition 7), paved 2010, 15,555 vehicles/day
1094	2032	**Seaver St** S17446	Repave	1 Urgent	$186,133 State revolving loan	7.10	Failed arterial road (condition 0), paved 1999, 12,433 vehicles/day
1095	2032	**Hyde Park Ave** S20146.1	Repave	1 Urgent	$167,656 State revolving loan	7.06	Failed arterial road (condition 3), paved 2008, 13,445 vehicles/day
1096	2032	**Congress St** S15449	Repave	1 Urgent	$166,323 State revolving loan	6.94	Failed arterial road (condition 0), paved 2007, 13,210 vehicles/day
1097	2032	**Martin Luther King Jr Blvd** S17660.2	Repave	1 Urgent	$177,110 State revolving loan	6.86	Failed arterial road (condition 0), paved 2006, 12,436 vehicles/day
1098	2032	**Tremont St** S11315	Repave	1 Urgent	$148,746 State revolving loan	6.82	Failed arterial road (condition 5), paved 2009, 14,576 vehicles/day
1099	2032	**Congress St** S15639	Repave	1 Urgent	$169,474 State revolving loan	6.66	Failed arterial road (condition 0), paved 2004, 12,490 vehicles/day
1100	2032	**Freeport St** S17947	Repave	1 Urgent	$140,732 State revolving loan	6.48	Failed arterial road (condition 4), paved 2009, 14,689 vehicles/day
1101	2032	**Malden St** S4935.1	Repave	1 Urgent	$154,095 State revolving loan	6.47	Failed arterial road (condition 0), paved 2007, 13,176 vehicles/day
1102	2032	**Harrison Ave** S25356	Repave	1 Urgent	$145,253 State revolving loan	6.44	Failed arterial road (condition 6), paved 2009, 14,149 vehicles/day
1103	2032	**Hyde Park Ave** S21509	Repave	1 Urgent	$155,338 State revolving loan	6.38	Failed arterial road (condition 0), paved 2007, 12,895 vehicles/day

1104	2032	**Hyde Park Ave** S4237	Repave	1 Urgent	$159,101 State revolving loan	6.32	Failed arterial road (condition 0), paved 1998, 12,493 vehicles/day
1105	2032	**River St** S6625	Repave	1 Urgent	$158,867 State revolving loan	6.29	Failed arterial road (condition 0), paved 2003, 12,456 vehicles/day
1106	2032	**Hemenway St** S3965	Repave	1 Urgent	$135,204 State revolving loan	6.27	Failed arterial road (condition 9), paved 2010, 15,159 vehicles/day
1107	2032	**Commonwealth Ave** S11773.1	Repave	1 Urgent	$155,716 State revolving loan	6.18	Failed arterial road (condition 0), paved 1998, 12,453 vehicles/day
1108	2032	**E Berkeley St** S25353	Repave	1 Urgent	$128,883 Interest-free loan	6.16	Failed arterial road (condition 7), paved 2010, 15,733 vehicles/day
1109	2032	**Saratoga St** S6943	Repave	1 Urgent	$154,383 State revolving loan	6.15	Failed arterial road (condition 0), paved 2002, 12,510 vehicles/day
1110	2032	**Western Ave** S17063	Repave	1 Urgent	$132,557 State revolving loan	6.14	Failed arterial road (condition 3), paved 2009, 14,953 vehicles/day
1111	2032	**Columbia Rd** S1858	Repave	1 Urgent	$128,036 Interest-free loan	6.06	Failed arterial road (condition 7), paved 2010, 15,660 vehicles/day
1112	2032	**W Newton St** S25247.1	Repave	1 Urgent	$152,114 State revolving loan	6.03	Failed arterial road (condition 0), paved 1998, 12,432 vehicles/day
1113	2032	**Congress St** S1954	Repave	1 Urgent	$126,181 Interest-free loan	6.02	Failed arterial road (condition 7), paved 2010, 15,829 vehicles/day
1114	2032	**Cummins Hwy** S18634	Repave	1 Urgent	$128,541 Interest-free loan	6.01	Failed arterial road (condition 8), paved 2010, 15,472 vehicles/day
1115	2032	**American Legion Hwy** S11889.1	Repave	1 Urgent	$150,439 State revolving loan	6.00	Failed arterial road (condition 0), paved 2003, 12,499 vehicles/day
1116	2032	**Washington St** S14853	Repave	1 Urgent	$136,608 State revolving loan	5.97	Failed arterial road (condition 1), paved 2008, 13,891 vehicles/day
1117	2032	**Bowdoin St** S943	Repave	1 Urgent	$129,333 Interest-free loan	5.93	Failed arterial road (condition 4), paved 2009, 14,910 vehicles/day
1118	2032	**American Legion Hwy** S229	Repave	1 Urgent	$132,665 Interest-free loan	5.87	Failed arterial road (condition 0), paved 2008, 14,155 vehicles/day
1119	2032	**Harvard St** S3888	Repave	1 Urgent	$127,064 Interest-free loan	5.86	Failed arterial road (condition 3), paved 2009, 15,108 vehicles/day
1120	2032	**Blue Hill Ave** S10545	Repave	1 Urgent	$138,193 Interest-free loan	5.85	Failed arterial road (condition 3), paved 2008, 13,473 vehicles/day
1121	2032	**L St** S4522	Repave	1 Urgent	$128,721 Interest-free loan	5.81	Failed arterial road (condition 9), paved 2010, 15,023 vehicles/day
1122	2032	**Bunker Hill St** S16692	Repave	1 Urgent	$138,625 Interest-free loan	5.80	Failed arterial road (condition 3), paved 2008, 13,328 vehicles/day
1123	2032	**Centre St** S1457	Repave	1 Urgent	$143,650 State revolving loan	5.75	Failed arterial road (condition 0), paved 2006, 12,586 vehicles/day
1124	2032	**Cummins Hwy** S18259	Repave	1 Urgent	$142,371 Interest-free loan	5.65	Failed arterial road (condition 0), paved 2005, 12,472 vehicles/day

1125	2032	**Centre St** S1513	Repave	1 Urgent	$123,624 Interest-free loan	5.57	Failed arterial road (condition 3), paved 2009, 14,976 vehicles/day
1126	2032	**N Beacon St** S5572	Repave	1 Urgent	$136,122 Interest-free loan	5.40	Failed arterial road (condition 0), paved 2004, 12,563 vehicles/day
1127	2032	**Market St** S10616	Repave	1 Urgent	$135,654 Interest-free loan	5.38	Failed arterial road (condition 0), paved 2002, 12,578 vehicles/day
1128	2032	**Cambridge St** S17029	Repave	1 Urgent	$117,195 Interest-free loan	5.32	Failed arterial road (condition 7), paved 2010, 15,787 vehicles/day
1129	2032	**Warren St** S17563	Repave	1 Urgent	$119,932 Interest-free loan	5.25	Failed arterial road (condition 9), paved 2010, 15,108 vehicles/day
1130	2032	**Bennington St** S9589	Repave	1 Urgent	$132,088 Interest-free loan	5.21	Failed arterial road (condition 0), paved 2002, 12,602 vehicles/day
1131	2032	**Bennington St** S12158	Repave	1 Urgent	$116,169 Interest-free loan	5.20	Failed arterial road (condition 7), paved 2010, 15,690 vehicles/day
1132	2032	**Wood Ave** S10760	Repave	1 Urgent	$118,312 Interest-free loan	5.17	Failed arterial road (condition 9), paved 2010, 15,192 vehicles/day
1133	2032	**Washington St** S18688	Repave	1 Urgent	$131,674 Interest-free loan	5.17	Failed arterial road (condition 0), paved 2004, 12,547 vehicles/day
1134	2032	**Stuart St** S24447	Repave	1 Urgent	$132,214 Interest-free loan	5.16	Failed arterial road (condition 0), paved 2002, 12,452 vehicles/day
1135	2032	**Dorchester Ave** S22476	Repave	1 Urgent	$123,444 Interest-free loan	5.15	Failed arterial road (condition 1), paved 2008, 13,793 vehicles/day
1136	2032	**Washington St** S20616	Repave	1 Urgent	$120,347 Interest-free loan	4.98	Failed arterial road (condition 1), paved 2008, 13,890 vehicles/day
1137	2032	**Albany St** S17330	Repave	1 Urgent	$119,014 Interest-free loan	4.98	Failed arterial road (condition 6), paved 2009, 14,304 vehicles/day
1138	2032	**Sprague St** S9689	Repave	1 Urgent	$119,680 Interest-free loan	4.96	Failed arterial road (condition 6), paved 2009, 14,115 vehicles/day
1139	2032	**Columbia Rd** S17783	Repave	1 Urgent	$115,664 Interest-free loan	4.83	Failed arterial road (condition 5), paved 2009, 14,551 vehicles/day
1140	2032	**Perkins St** S18417	Repave	1 Urgent	$112,117 Interest-free loan	4.82	Failed arterial road (condition 7), paved 2010, 15,587 vehicles/day
1141	2032	**A St** S13527	Repave	1 Urgent	$122,652 Interest-free loan	4.67	Failed arterial road (condition 0), paved 2000, 12,572 vehicles/day
1142	2032	**Atlantic Ave** S15998	Repave	1 Urgent	$118,492 Interest-free loan	4.67	Failed arterial road (condition 3), paved 2008, 13,405 vehicles/day
1143	2032	**Brookline Ave** S12680	Repave	1 Urgent	$122,328 Interest-free loan	4.66	Failed arterial road (condition 0), paved 2000, 12,588 vehicles/day
1144	2032	**Hancock St** S25693	Repave	1 Urgent	$120,563 Interest-free loan	4.63	Failed arterial road (condition 0), paved 2007, 12,812 vehicles/day
1145	2032	**Albany St** S10345	Repave	1 Urgent	$114,620 Interest-free loan	4.63	Failed arterial road (condition 1), paved 2008, 14,043 vehicles/day

1146	2032	**Waltham St** S7949	Repave	1 Urgent	$113,665 Interest-free loan	4.57	Failed arterial road (condition 6), paved 2009, 14,271 vehicles/day
1147	2032	**N Beacon St** S12791	Repave	1 Urgent	$121,319 Interest-free loan	4.55	Failed arterial road (condition 0), paved 2000, 12,452 vehicles/day
1148	2032	**Mckinley Sq** S8889	Repave	1 Urgent	$109,793 Interest-free loan	4.43	Failed arterial road (condition 4), paved 2009, 14,798 vehicles/day
1149	2032	**Western Ave** S25163	Repave	1 Urgent	$118,942 Interest-free loan	4.43	Failed arterial road (condition 0), paved 2007, 12,538 vehicles/day
1150	2032	**Bennington St** S9553	Repave	1 Urgent	$115,970 Interest-free loan	4.40	Failed arterial road (condition 0), paved 2007, 13,037 vehicles/day
1151	2032	**Shawmut Ave** S8784	Repave	1 Urgent	$118,330 Interest-free loan	4.38	Failed arterial road (condition 0), paved 2005, 12,502 vehicles/day
1152	2032	**Cambridge St** S19808	Repave	1 Urgent	$114,170 Interest-free loan	4.33	Failed arterial road (condition 0), paved 2007, 13,206 vehicles/day
1153	2032	**Warren St** S17523	Repave	1 Urgent	$116,619 Interest-free loan	4.30	Failed arterial road (condition 0), paved 2005, 12,599 vehicles/day
1154	2032	**Preble St** S24205	Repave	1 Urgent	$106,174 State revolving loan	4.29	Failed arterial road (condition 7), paved 2010, 15,640 vehicles/day
1155	2032	**Harrison Ave** S3811	Repave	1 Urgent	$109,721 Interest-free loan	4.11	Failed arterial road (condition 2), paved 2008, 13,650 vehicles/day
1156	2032	**Washington St** S24390	Repave	1 Urgent	$109,271 Interest-free loan	4.06	Failed arterial road (condition 2), paved 2008, 13,608 vehicles/day
1157	2032	**Cummins Hwy** S18284	Repave	1 Urgent	$104,391 Interest-free loan	4.01	Failed arterial road (condition 3), paved 2009, 15,037 vehicles/day
1158	2032	**Washington St** S19643	Repave	1 Urgent	$106,948 Interest-free loan	3.97	Failed arterial road (condition 6), paved 2009, 14,123 vehicles/day
1159	2032	**Main St** S4923	Repave	1 Urgent	$111,558 Interest-free loan	3.90	Failed arterial road (condition 0), paved 2006, 12,454 vehicles/day
1160	2032	**Main St** S4910	Repave	1 Urgent	$104,913 Interest-free loan	3.80	Failed arterial road (condition 6), paved 2009, 14,181 vehicles/day
1161	2032	**Centre St** S1478	Repave	1 Urgent	$101,401 Interest-free loan	3.78	Failed arterial road (condition 7), paved 2010, 15,553 vehicles/day
1162	2032	**Cambridge St** S1324	Repave	1 Urgent	$109,469 Interest-free loan	3.75	Failed arterial road (condition 0), paved 2001, 12,452 vehicles/day
1163	2032	**Dartmouth St** S2247	Repave	1 Urgent	$103,400 Interest-free loan	3.74	Failed arterial road (condition 5), paved 2009, 14,440 vehicles/day
1164	2032	**Maverick St** S5141	Repave	1 Urgent	$99,582 Interest-free loan	3.66	Failed arterial road (condition 7), paved 2010, 15,850 vehicles/day
1165	2032	**Causeway St** S16094	Repave	1 Urgent	$103,851 Interest-free loan	3.66	Failed arterial road (condition 1), paved 2008, 13,830 vehicles/day
1166	2032	**D St** S20097	Repave	1 Urgent	$106,552 Interest-free loan	3.64	Failed arterial road (condition 0), paved 2007, 12,870 vehicles/day

1167	2032	**Saratoga St** S24895	Repave	1 Urgent	$107,830 Interest-free loan	3.63	Failed arterial road (condition 0), paved 1998, 12,484 vehicles/day
1168	2032	**Berkeley St** S13138	Repave	1 Urgent	$102,914 Rate revenue	3.51	Failed arterial road (condition 2), paved 2008, 13,615 vehicles/day
1169	2032	**Norfolk St** S5731	Repave	1 Urgent	$99,240 Rate revenue	3.48	Failed arterial road (condition 8), paved 2010, 15,313 vehicles/day
1170	2032	**Brookline Ave** S1160	Repave	1 Urgent	$105,579 Rate revenue	3.47	Failed arterial road (condition 0), paved 2006, 12,544 vehicles/day
1171	2032	**Hereford St** S9909	Repave	1 Urgent	$105,075 Rate revenue	3.42	Failed arterial road (condition 0), paved 2002, 12,500 vehicles/day
1172	2032	**Cambridge St** S19803	Repave	1 Urgent	$104,139 Rate revenue	3.37	Failed arterial road (condition 0), paved 2002, 12,613 vehicles/day
1173	2032	**Norfolk St** S13856	Repave	1 Urgent	$103,941 Rate revenue	3.32	Failed arterial road (condition 0), paved 1998, 12,471 vehicles/day
1174	2032	**Dorchester Ave** S2465	Repave	1 Urgent	$103,400 Rate revenue	3.31	Failed arterial road (condition 0), paved 2007, 12,591 vehicles/day
1175	2032	**Market St** S5073	Repave	1 Urgent	$96,845 Rate revenue	3.29	Failed arterial road (condition 7), paved 2010, 15,611 vehicles/day
1176	2032	**Berkeley St** S10482	Repave	1 Urgent	$103,328 Rate revenue	3.28	Failed arterial road (condition 0), paved 1999, 12,517 vehicles/day
1177	2032	**Washington St** S8033	Repave	1 Urgent	$98,610 Rate revenue	3.23	Failed arterial road (condition 5), paved 2009, 14,346 vehicles/day
1178	2032	**Columbus Ave** S17440	Repave	1 Urgent	$99,582 Rate revenue	3.20	Failed arterial road (condition 2), paved 2008, 13,638 vehicles/day
1179	2032	**Dorchester Ave** S19407	Repave	1 Urgent	$100,735 Rate revenue	3.07	Failed arterial road (condition 0), paved 1998, 12,578 vehicles/day
1180	2032	**Blue Hill Ave** S18165	Repave	1 Urgent	$98,070 Rate revenue	2.97	Failed arterial road (condition 0), paved 2007, 13,220 vehicles/day
1181	2032	**Bennington St** S9552	Repave	1 Urgent	$95,332 Rate revenue	2.93	Failed arterial road (condition 5), paved 2009, 14,590 vehicles/day
1182	2032	**Harrison Ave** S17254	Repave	1 Urgent	$95,242 Rate revenue	2.85	Failed arterial road (condition 0), paved 2008, 14,086 vehicles/day
1183	2032	**Beacon St** S24886	Repave	1 Urgent	$98,106 Rate revenue	2.84	Failed arterial road (condition 0), paved 2007, 12,619 vehicles/day
1184	2032	**South St** S7208	Repave	1 Urgent	$96,881 Rate revenue	2.84	Failed arterial road (condition 0), paved 2007, 13,144 vehicles/day
1185	2032	**Ruggles St** S6752	Repave	1 Urgent	$98,250 Rate revenue	2.83	Failed arterial road (condition 0), paved 1999, 12,518 vehicles/day
1186	2032	**Harrison Ave** S14328	Repave	1 Urgent	$93,532 Rate revenue	2.78	Failed arterial road (condition 9), paved 2010, 15,148 vehicles/day
1187	2032	**Huntington Ave** S26677	Repave	1 Urgent	$95,639 Rate revenue	2.78	Failed arterial road (condition 2), paved 2008, 13,571 vehicles/day
1188	2032	**E Eagle St** S16816	Repave	1 Urgent	$94,684 Rate revenue	2.76	Failed arterial road (condition 6), paved 2009, 14,144 vehicles/day
1189	2032	**Huntington Ave** S16597	Repave	1 Urgent	$96,215 Rate revenue	2.63	Failed arterial road (condition 0), paved 1998, 12,462 vehicles/day
1190	2032	**Tremont St** S13286	Repave	1 Urgent	$96,233 Rate revenue	2.62	Failed arterial road (condition 0), paved 2002, 12,441 vehicles/day
1191	2032	**Berkeley St** S751	Repave shared dig B-2032-S751	1 Urgent	$64,189 Rate revenue	2.59	Failed arterial road (condition 0), paved 2008, 14,196 vehicles/day
1192	2032	**Bunker Hill St** S1201	Repave	1 Urgent	$95,422 Rate revenue	2.56	Failed arterial road (condition 0), paved 2004, 12,516 vehicles/day
1193	2032	**Centre St** S1464	Repave	1 Urgent	$93,892 Rate revenue	2.55	Failed arterial road (condition 0), paved 2007, 13,302 vehicles/day
1194	2032	**Tremont St** S7668	Repave	1 Urgent	$94,072 Rate revenue	2.42	Failed arterial road (condition 0), paved 1999, 12,499 vehicles/day

1195	2032	**Southampton St** S23859	Repave	1 Urgent	$90,542 Rate revenue	2.41	Failed arterial road (condition 9), paved 2010, 15,154 vehicles/day
1196	2032	**Centre St** S21475	Repave	1 Urgent	$93,045 Rate revenue	2.33	Failed arterial road (condition 0), paved 2003, 12,580 vehicles/day
1197	2032	**Monsignor John J. O'Donnell Sq** S27089	Repave	1 Urgent	$89,732 Rate revenue	2.31	Failed arterial road (condition 9), paved 2010, 15,192 vehicles/day
1198	2032	**State St** S7330	Repave	1 Urgent	$92,541 Rate revenue	2.28	Failed arterial road (condition 0), paved 2000, 12,597 vehicles/day
1199	2032	**Quincy St** S6459	Repave shared dig B-2032-S6459	1 Urgent	$52,069 Rate revenue	1.76	Failed arterial road (condition 3), paved 2008, 13,356 vehicles/day
1200	2032	**Commonwealth Ave** S20778	Repave shared dig B-2032-S20778	1 Urgent	$49,566 Rate revenue	1.72	Failed arterial road (condition 0), paved 2008, 14,116 vehicles/day
1201	2032	**Washington St** S7991	Repave shared dig B-2032-S7991	1 Urgent	$48,324 Rate revenue	1.56	Failed arterial road (condition 6), paved 2009, 14,230 vehicles/day
1202	2032	**Woodhaven St** S25831	Repave shared dig B-2032-S25831	1 Urgent	$46,847 Rate revenue	1.32	Failed arterial road (condition 0), paved 2007, 12,595 vehicles/day
1203	2032	**Massachusetts Ave** S22551	Repave shared dig B-2032-S22551	1 Urgent	$46,703 Rate revenue	1.30	Failed arterial road (condition 0), paved 2002, 12,508 vehicles/day
1204	2032	**Savin Hill Ave** S11336	Repave shared dig B-2032-S11336 engineering review	1 Urgent	$69,268 Rate revenue	1.01	Poor collector road (condition 44), paved 2012, 6,270 vehicles/day
1205	2032	**Berkeley St** S751	Replace water main shared dig B-2032-S751	4 Monitor	$104,196 Rate revenue	2.59	Moderate risk (index 44): cast iron main from 1936, 1 prior breaks, PoF 74, serves a critical facility
1206	2032	**Quincy St** S6459	Replace water main shared dig B-2032-S6459	4 Monitor	$73,896 Rate revenue	1.76	Low risk (index 23): cast iron main from 1904, 1 prior breaks, PoF 78
1207	2032	**Commonwealth Ave** S20778	Replace water main shared dig B-2032-S20778	4 Monitor	$67,638 Rate revenue	1.72	Moderate risk (index 32): cast iron main from 1937, 0 prior breaks, PoF 53, serves a critical facility
1208	2032	**Washington St** S7991	Replace water main shared dig B-2032-S7991	4 Monitor	$64,531 Rate revenue	1.56	Low risk (index 23): cast iron main from 1908, 1 prior breaks, PoF 80
1209	2032	**Woodhaven St** S25831	Replace water main shared dig B-2032-S25831	4 Monitor	$60,840 Rate revenue	1.32	Low risk (index 23): cast iron main from 1940, 1 prior breaks, PoF 77
1210	2032	**Massachusetts Ave** S22551	Replace water main shared dig B-2032-S22551	4 Monitor	$60,479 Rate revenue	1.30	Low risk (index 24): cast iron main from 1906, 2 prior breaks, PoF 91
1211	2032	**Saratoga St** S6944	Repave engineering review	4 Monitor	$178,173 Rate revenue	1.13	Fair arterial road (condition 74), paved 2022, 10,883 vehicles/day
1212	2032	**Savin Hill Ave** S11336	Reline water main shared dig B-2032-S11336 engineering review	4 Monitor	$77,205 Rate revenue	1.01	High risk (index 53): cast iron main from 1927, 1 prior breaks, PoF 91, serves a critical facility
1213	2033	**Harvard St** S10296.4	Repave	1 Urgent	$220,821 State revolving loan	7.97	Failed arterial road (condition 6), paved 2010, 14,216 vehicles/day
1214	2033	**Bennington St** S15227	Repave	1 Urgent	$186,637 State revolving loan	7.47	Failed arterial road (condition 4), paved 2010, 14,831 vehicles/day
1215	2033	**Huntington Ave** S17346	Repave	1 Urgent	$177,869 State revolving loan	7.39	Failed arterial road (condition 8), paved 2011, 15,442 vehicles/day
1216	2033	**Centre St** S14807	Repave	1 Urgent	$192,321 State revolving loan	7.32	Failed arterial road (condition 6), paved 2010, 14,268 vehicles/day
1217	2033	**Commonwealth Ave** S9278	Repave	1 Urgent	$176,443 State revolving loan	7.23	Failed arterial road (condition 8), paved 2011, 15,262 vehicles/day
1218	2033	**Commonwealth Ave** S12821	Repave	1 Urgent	$210,569 State revolving loan	7.20	Failed arterial road (condition 0), paved 2008, 13,008 vehicles/day
1219	2033	**Beacon St** S14157	Repave	1 Urgent	$199,143 State revolving loan	7.16	Failed arterial road (condition 2), paved 2009, 13,507 vehicles/day

1220	2033	**Tremont St** S23114.1	Repave	1 Urgent	$173,900 State revolving loan	7.11	Failed arterial road (condition 9), paved 2011, 15,190 vehicles/day
1221	2033	**Hyde Park Ave** S19649	Repave	1 Urgent	$174,516 State revolving loan	7.04	Failed arterial road (condition 4), paved 2010, 14,753 vehicles/day
1222	2033	**Commonwealth Ave** S14566.2	Repave	1 Urgent	$180,625 State revolving loan	7.02	Failed arterial road (condition 5), paved 2010, 14,344 vehicles/day
1223	2033	**Albany St** S15097	Repave	1 Urgent	$167,753 State revolving loan	6.73	Failed arterial road (condition 4), paved 2010, 14,620 vehicles/day
1224	2033	**Terminal St** S10843.3	Repave	1 Urgent	$204,268 State revolving loan	6.71	Failed arterial road (condition 0), paved 2003, 12,358 vehicles/day
1225	2033	**Chelsea St** S16791	Repave	1 Urgent	$173,842 State revolving loan	6.70	Failed arterial road (condition 1), paved 2009, 13,963 vehicles/day
1226	2033	**E First St** S10800	Repave	1 Urgent	$161,432 State revolving loan	6.68	Failed arterial road (condition 3), paved 2010, 15,005 vehicles/day
1227	2033	**Washington St** S24373.1	Repave	1 Urgent	$165,999 State revolving loan	6.56	Failed arterial road (condition 5), paved 2010, 14,398 vehicles/day
1228	2033	**Congress St** S21095.1	Repave	1 Urgent	$165,113 State revolving loan	6.55	Failed arterial road (condition 5), paved 2010, 14,458 vehicles/day
1229	2033	**River St** S14180	Repave	1 Urgent	$159,814 State revolving loan	6.51	Failed arterial road (condition 4), paved 2010, 14,806 vehicles/day
1230	2033	**Centre St** S18774	Repave	1 Urgent	$191,955 State revolving loan	6.46	Failed arterial road (condition 0), paved 2007, 12,411 vehicles/day
1231	2033	**Washington St** S25134	Repave	1 Urgent	$183,303 State revolving loan	6.25	Failed arterial road (condition 0), paved 2004, 12,426 vehicles/day
1232	2033	**Somerset St** S14078	Repave	1 Urgent	$146,499 State revolving loan	6.20	Failed arterial road (condition 7), paved 2011, 15,686 vehicles/day
1233	2033	**Commonwealth Ave** S12296	Repave	1 Urgent	$168,986 State revolving loan	6.05	Failed arterial road (condition 0), paved 2008, 12,899 vehicles/day
1234	2033	**Hyde Park Ave** S13231	Repave	1 Urgent	$174,439 State revolving loan	5.98	Failed arterial road (condition 0), paved 2003, 12,373 vehicles/day
1235	2033	**Blue Hill Ave** S11416	Repave	1 Urgent	$155,517 State revolving loan	5.97	Failed arterial road (condition 1), paved 2009, 13,861 vehicles/day
1236	2033	**Gordon Ave** S10078	Repave	1 Urgent	$147,019 State revolving loan	5.95	Failed arterial road (condition 4), paved 2010, 14,825 vehicles/day
1237	2033	**River St** S6662	Repave	1 Urgent	$147,231 State revolving loan	5.90	Failed arterial road (condition 9), paved 2011, 14,978 vehicles/day
1238	2033	**James J Storrow Memorial Dr** S23014	Repave	1 Urgent	$150,988 State revolving loan	5.86	Failed arterial road (condition 6), paved 2010, 14,212 vehicles/day
1239	2033	**Columbus Ave** S11624	Repave	1 Urgent	$158,041 State revolving loan	5.75	Failed arterial road (condition 0), paved 2008, 13,068 vehicles/day
1240	2033	**Washington St** S18012	Repave	1 Urgent	$157,868 State revolving loan	5.71	Failed arterial road (condition 0), paved 2008, 12,996 vehicles/day

1241	2033	**Bennington St** S744	Repave	1 Urgent	$147,693 State revolving loan	5.58	Failed arterial road (condition 2), paved 2009, 13,747 vehicles/day
1242	2033	**Dudley St** S17557	Repave	1 Urgent	$144,302 State revolving loan	5.57	Failed arterial road (condition 0), paved 2009, 14,075 vehicles/day
1243	2033	**University Rd** S20092	Repave	1 Urgent	$149,293 State revolving loan	5.57	Failed arterial road (condition 2), paved 2009, 13,552 vehicles/day
1244	2033	**Boston St** S896	Repave	1 Urgent	$132,471 Interest-free loan	5.41	Failed arterial road (condition 7), paved 2011, 15,702 vehicles/day
1245	2033	**Cambridge St** S1309	Repave	1 Urgent	$156,615 State revolving loan	5.39	Failed arterial road (condition 0), paved 2004, 12,359 vehicles/day
1246	2033	**Ashmont St** S388	Repave	1 Urgent	$135,477 State revolving loan	5.37	Failed arterial road (condition 9), paved 2011, 15,178 vehicles/day
1247	2033	**Dorchester Ave** S11421	Repave	1 Urgent	$131,565 Interest-free loan	5.35	Failed arterial road (condition 7), paved 2011, 15,704 vehicles/day
1248	2033	**Atlantic Ave** S14403	Repave	1 Urgent	$142,086 State revolving loan	5.32	Failed arterial road (condition 2), paved 2009, 13,736 vehicles/day
1249	2033	**Washington St** S7995	Repave	1 Urgent	$141,450 Interest-free loan	5.16	Failed arterial road (condition 3), paved 2009, 13,434 vehicles/day
1250	2033	**Harrison Ave** S3819	Repave	1 Urgent	$132,451 Interest-free loan	4.98	Failed arterial road (condition 5), paved 2010, 14,340 vehicles/day
1251	2033	**Merrimac St** S19414	Repave	1 Urgent	$132,683 Interest-free loan	4.89	Failed arterial road (condition 6), paved 2010, 14,088 vehicles/day
1252	2033	**Franklin St** S3153	Repave	1 Urgent	$132,047 Interest-free loan	4.89	Failed arterial road (condition 1), paved 2009, 13,993 vehicles/day
1253	2033	**Norfolk St** S5725	Repave	1 Urgent	$126,516 Interest-free loan	4.79	Failed arterial road (condition 9), paved 2011, 15,113 vehicles/day
1254	2033	**River St** S11431	Repave	1 Urgent	$126,921 Interest-free loan	4.78	Failed arterial road (condition 9), paved 2011, 15,019 vehicles/day
1255	2033	**Roxbury St** S13822	Repave	1 Urgent	$127,846 Interest-free loan	4.76	Failed arterial road (condition 5), paved 2010, 14,514 vehicles/day
1256	2033	**Neponset Ave** S5616	Repave	1 Urgent	$139,793 Interest-free loan	4.76	Failed arterial road (condition 0), paved 2008, 12,508 vehicles/day
1257	2033	**Centre St** S1500	Repave	1 Urgent	$129,580 Interest-free loan	4.74	Failed arterial road (condition 1), paved 2009, 13,990 vehicles/day
1258	2033	**Blue Hill Ave** S873	Repave	1 Urgent	$122,759 Interest-free loan	4.72	Failed arterial road (condition 7), paved 2011, 15,618 vehicles/day
1259	2033	**Dorchester Ave** S2474	Repave	1 Urgent	$129,195 Interest-free loan	4.71	Failed arterial road (condition 1), paved 2009, 13,956 vehicles/day
1260	2033	**Cummins Hwy** S18281	Repave	1 Urgent	$121,660 Interest-free loan	4.64	Failed arterial road (condition 7), paved 2011, 15,612 vehicles/day
1261	2033	**Meridian St** S5255	Repave	1 Urgent	$123,953 Interest-free loan	4.59	Failed arterial road (condition 9), paved 2011, 15,019 vehicles/day

1262	2033	**Bowdoin St** S942	Repave	1 Urgent	$122,759 Interest-free loan	4.56	Failed arterial road (condition 4), paved 2010, 14,912 vehicles/day
1263	2033	**South St** S7209	Repave	1 Urgent	$122,855 Interest-free loan	4.55	Failed arterial road (condition 4), paved 2010, 14,851 vehicles/day
1264	2033	**Massachusetts Ave** S21835	Repave	1 Urgent	$121,641 Interest-free loan	4.52	Failed arterial road (condition 3), paved 2010, 15,015 vehicles/day
1265	2033	**Harvard St** S18349	Repave	1 Urgent	$122,084 Interest-free loan	4.52	Failed arterial road (condition 9), paved 2011, 15,182 vehicles/day
1266	2033	**Cambridge St** S25116	Repave	1 Urgent	$124,223 Interest-free loan	4.45	Failed arterial road (condition 0), paved 2009, 14,095 vehicles/day
1267	2033	**Commercial St** S14869	Repave	1 Urgent	$121,159 Interest-free loan	4.43	Failed arterial road (condition 9), paved 2011, 15,135 vehicles/day
1268	2033	**Washington St** S8109	Repave	1 Urgent	$120,774 Interest-free loan	4.42	Failed arterial road (condition 4), paved 2010, 14,914 vehicles/day
1269	2033	**Meridian St** S5249	Repave	1 Urgent	$133,299 Interest-free loan	4.41	Failed arterial road (condition 0), paved 2001, 12,401 vehicles/day
1270	2033	**Centre St** S1495	Repave	1 Urgent	$119,599 Interest-free loan	4.39	Failed arterial road (condition 8), paved 2011, 15,345 vehicles/day
1271	2033	**Lagrange St** S4528	Repave	1 Urgent	$132,008 Interest-free loan	4.34	Failed arterial road (condition 0), paved 2005, 12,385 vehicles/day
1272	2033	**Washington St** S8043	Repave	1 Urgent	$128,135 Interest-free loan	4.30	Failed arterial road (condition 0), paved 2008, 12,865 vehicles/day
1273	2033	**Tremont St** S20046	Repave	1 Urgent	$130,736 Interest-free loan	4.27	Failed arterial road (condition 0), paved 2006, 12,365 vehicles/day
1274	2033	**High St** S14993	Repave	1 Urgent	$124,878 Interest-free loan	4.20	Failed arterial road (condition 0), paved 2008, 13,171 vehicles/day
1275	2033	**Harvard St** S3880	Repave	1 Urgent	$118,308 Interest-free loan	4.14	Failed arterial road (condition 5), paved 2010, 14,597 vehicles/day
1276	2033	**Cambridge St** S24548	Repave	1 Urgent	$116,015 Interest-free loan	4.13	Failed arterial road (condition 8), paved 2011, 15,402 vehicles/day
1277	2033	**Washington St** S19144	Repave	1 Urgent	$128,058 Interest-free loan	4.13	Failed arterial road (condition 0), paved 1998, 12,379 vehicles/day
1278	2033	**Harrison Ave** S3808	Repave	1 Urgent	$127,345 Interest-free loan	4.11	Failed arterial road (condition 0), paved 1999, 12,424 vehicles/day
1279	2033	**Blue Hill Ave** S18130	Repave	1 Urgent	$115,090 Interest-free loan	4.03	Failed arterial road (condition 8), paved 2011, 15,306 vehicles/day
1280	2033	**Chelsea St** S19588	Repave	1 Urgent	$125,322 Interest-free loan	3.99	Failed arterial road (condition 0), paved 2004, 12,415 vehicles/day
1281	2033	**Ashmont St** S391	Repave	1 Urgent	$121,371 Interest-free loan	3.95	Failed arterial road (condition 0), paved 2008, 13,061 vehicles/day
1282	2033	**Corinth St** S2012	Repave	1 Urgent	$124,165 Interest-free loan	3.92	Failed arterial road (condition 0), paved 2004, 12,406 vehicles/day

1283	2033	**Tremont St** S19527	Repave	1 Urgent	$112,469 Interest-free loan	3.79	Failed arterial road (condition 8), paved 2011, 15,231 vehicles/day
1284	2033	**Louis Prang St** S16910	Repave	1 Urgent	$113,220 Interest-free loan	3.78	Failed arterial road (condition 4), paved 2010, 14,723 vehicles/day
1285	2033	**Harrison Ave** S3831	Repave	1 Urgent	$117,614 Interest-free loan	3.76	Failed arterial road (condition 3), paved 2009, 13,351 vehicles/day
1286	2033	**South St** S18691	Repave	1 Urgent	$112,527 Interest-free loan	3.61	Failed arterial road (condition 6), paved 2010, 14,286 vehicles/day
1287	2033	**Boylston St** S9600	Repave	1 Urgent	$109,925 Interest-free loan	3.53	Failed arterial road (condition 4), paved 2010, 14,816 vehicles/day
1288	2033	**Centre St** S1455	Repave	1 Urgent	$117,113 Interest-free loan	3.52	Failed arterial road (condition 0), paved 2007, 12,499 vehicles/day
1289	2033	**Louis Prang St** S16852	Repave	1 Urgent	$107,054 Interest-free loan	3.45	Failed arterial road (condition 7), paved 2011, 15,765 vehicles/day
1290	2033	**Spring St** S19173	Repave	1 Urgent	$109,405 Interest-free loan	3.44	Failed arterial road (condition 4), paved 2010, 14,624 vehicles/day
1291	2033	**Cambridge St** S24477	Repave	1 Urgent	$114,897 Interest-free loan	3.39	Failed arterial road (condition 0), paved 2008, 12,581 vehicles/day
1292	2033	**Stuart St** S27589	Repave	1 Urgent	$107,517 Interest-free loan	3.36	Failed arterial road (condition 3), paved 2010, 15,002 vehicles/day
1293	2033	**River St** S6620	Repave	1 Urgent	$112,103 Interest-free loan	3.34	Failed arterial road (condition 0), paved 2008, 13,179 vehicles/day
1294	2033	**Warren St** S26892	Repave	1 Urgent	$114,511 Interest-free loan	3.32	Failed arterial road (condition 0), paved 1998, 12,409 vehicles/day
1295	2033	**Centre St** S18749	Repave	1 Urgent	$112,797 Interest-free loan	3.30	Failed arterial road (condition 0), paved 2008, 12,821 vehicles/day
1296	2033	**Cummins Hwy** S9901	Repave	1 Urgent	$105,898 Rate revenue	3.28	Failed arterial road (condition 7), paved 2011, 15,548 vehicles/day
1297	2033	**Harvard Ave** S25274	Repave	1 Urgent	$109,174 Interest-free loan	3.23	Failed arterial road (condition 2), paved 2009, 13,732 vehicles/day
1298	2033	**City Sq** S16142	Repave	1 Urgent	$111,987 Interest-free loan	3.23	Failed arterial road (condition 0), paved 2008, 12,745 vehicles/day
1299	2033	**Market St** S11531	Repave	1 Urgent	$113,105 Interest-free loan	3.22	Failed arterial road (condition 0), paved 2001, 12,390 vehicles/day
1300	2033	**Chestnut Hill Ave** S10687	Repave	1 Urgent	$107,786 Rate revenue	3.21	Failed arterial road (condition 6), paved 2010, 14,272 vehicles/day
1301	2033	**Tremont St** S7689	Repave	1 Urgent	$106,553 Rate revenue	3.17	Failed arterial road (condition 5), paved 2010, 14,561 vehicles/day
1302	2033	**E Newton St** S17282	Repave	1 Urgent	$104,453 Rate revenue	3.15	Failed arterial road (condition 7), paved 2011, 15,568 vehicles/day
1303	2033	**Milk St** S5210	Repave	1 Urgent	$103,277 Rate revenue	3.09	Failed arterial road (condition 6), paved 2011, 15,859 vehicles/day
1304	2033	**Bowdoin St** S21379	Repave	1 Urgent	$104,472 Rate revenue	3.08	Failed arterial road (condition 8), paved 2011, 15,288 vehicles/day
1305	2033	**Arlington St** S16546	Repave	1 Urgent	$106,669 Rate revenue	3.04	Failed arterial road (condition 1), paved 2009, 13,815 vehicles/day

1306	2033	**India St** S16036	Repave	1 Urgent	$107,131 Rate revenue	2.98	Failed arterial road (condition 3), paved 2009, 13,399 vehicles/day
1307	2033	**State St** S16446	Repave	1 Urgent	$103,836 Rate revenue	2.95	Failed arterial road (condition 4), paved 2010, 14,729 vehicles/day
1308	2033	**Columbia Rd** S17703	Repave	1 Urgent	$106,399 Rate revenue	2.76	Failed arterial road (condition 0), paved 2008, 12,567 vehicles/day
1309	2033	**Shawmut Ave** S8805	Repave	1 Urgent	$99,732 Rate revenue	2.73	Failed arterial road (condition 6), paved 2011, 15,933 vehicles/day
1310	2033	**Dudley St** S9993	Repave	1 Urgent	$101,428 Rate revenue	2.61	Failed arterial road (condition 6), paved 2010, 14,213 vehicles/day
1311	2033	**River St** S6644	Repave	1 Urgent	$104,260 Rate revenue	2.61	Failed arterial road (condition 0), paved 2008, 12,674 vehicles/day
1312	2033	**Shawmut Ave** S8793	Repave	1 Urgent	$104,279 Rate revenue	2.55	Failed arterial road (condition 0), paved 2007, 12,412 vehicles/day
1313	2033	**Preble St** S6366	Repave	1 Urgent	$104,299 Rate revenue	2.55	Failed arterial road (condition 0), paved 2003, 12,365 vehicles/day
1314	2033	**Harrison Ave** S25394	Repave	1 Urgent	$103,470 Rate revenue	2.54	Failed arterial road (condition 0), paved 2008, 12,687 vehicles/day
1315	2033	**Norfolk St** S12607	Repave	1 Urgent	$103,682 Rate revenue	2.54	Failed arterial road (condition 0), paved 2008, 12,572 vehicles/day
1316	2033	**Tremont St** S7662	Repave	1 Urgent	$99,057 Rate revenue	2.51	Failed arterial road (condition 3), paved 2010, 14,946 vehicles/day
1317	2033	**Centre St** S22271	Repave	1 Urgent	$103,393 Rate revenue	2.48	Failed arterial road (condition 0), paved 1998, 12,386 vehicles/day
1318	2033	**Essex St** S2927	Repave	1 Urgent	$99,385 Rate revenue	2.38	Failed arterial road (condition 6), paved 2010, 14,107 vehicles/day
1319	2033	**Medford St** S5187	Repave	1 Urgent	$96,514 Rate revenue	2.33	Failed arterial road (condition 7), paved 2011, 15,836 vehicles/day
1320	2033	**Harrison Ave** S10217	Repave	1 Urgent	$100,599 Rate revenue	2.25	Failed arterial road (condition 0), paved 2007, 12,445 vehicles/day
1321	2033	**Avenue Louis Pasteur** S27579	Repave	1 Urgent	$99,154 Rate revenue	2.21	Failed arterial road (condition 0), paved 2008, 12,981 vehicles/day
1322	2033	**Dorchester St** S14784	Repave	1 Urgent	$99,867 Rate revenue	2.17	Failed arterial road (condition 0), paved 2003, 12,371 vehicles/day
1323	2033	**Harrison Ave** S3820	Repave	1 Urgent	$99,346 Rate revenue	2.16	Failed arterial road (condition 0), paved 2008, 12,587 vehicles/day
1324	2033	**Washington St** S18697	Repave	1 Urgent	$98,807 Rate revenue	2.07	Failed arterial road (condition 0), paved 2001, 12,361 vehicles/day
1325	2033	**Blue Hill Ave** S17733	Repave	1 Urgent	$97,709 Rate revenue	2.06	Failed arterial road (condition 0), paved 2007, 12,924 vehicles/day
1326	2033	**Bennington St** S20440	Repave	1 Urgent	$95,184 Rate revenue	2.06	Failed arterial road (condition 4), paved 2010, 14,876 vehicles/day
1327	2033	**Centre St** S1472	Repave	1 Urgent	$94,510 Rate revenue	2.03	Failed arterial road (condition 8), paved 2011, 15,439 vehicles/day
1328	2033	**E Brookline St** S17277	Repave shared dig B-2033-S17277	1 Urgent	$51,379 Rate revenue	1.54	Failed arterial road (condition 8), paved 2011, 15,397 vehicles/day
1329	2033	**Northampton St** S27288	Repave shared dig B-2033-S27288 engineering review	1 Urgent	$45,077 Rate revenue	1.02	Failed arterial road (condition 8), paved 2011, 15,444 vehicles/day
1330	2033	**E Brookline St** S17277	Replace water main shared dig B-2033-S17277	4 Monitor	$68,230 State revolving loan	1.54	Moderate risk (index 27): cast iron main from 1925, 1 prior breaks, PoF 84
1331	2033	**Bremen St** S1048	Repave engineering review	4 Monitor	$202,823 Rate revenue	1.15	Fair arterial road (condition 81), paved 2026, 15,722 vehicles/day
1332	2033	**Geneva Ave** S10039	Repave engineering review	4 Monitor	$204,557 Rate revenue	1.10	Fair arterial road (condition 82), paved 2026, 15,339 vehicles/day
1333	2033	**Washington St** S10285	Repave engineering review	4 Monitor	$225,696 Rate revenue	1.09	Fair arterial road (condition 82), paved 2026, 14,807 vehicles/day

1334	2033	**Northampton St** S27288	Replace water main shared dig B-2033-S27288 engineering review	4 Monitor	$52,477 Rate revenue	1.02	Moderate risk (index 31): cast iron main from 1914, 0 prior breaks, PoF 54, serves a critical facility
1335	2034	**D St** S11718	Repave	1 Urgent	$245,804 State revolving loan	7.94	Failed arterial road (condition 4), paved 2011, 14,780 vehicles/day
1336	2034	**American Legion Hwy** S10782	Repave	1 Urgent	$227,412 State revolving loan	7.59	Failed arterial road (condition 4), paved 2011, 14,764 vehicles/day
1337	2034	**Canal St** S14989	Repave	1 Urgent	$194,361 State revolving loan	6.93	Failed arterial road (condition 8), paved 2012, 15,283 vehicles/day
1338	2034	**Adams St** S12376.1	Repave	1 Urgent	$184,052 State revolving loan	6.87	Failed arterial road (condition 7), paved 2012, 15,753 vehicles/day
1339	2034	**Commonwealth Ave** S14566.1	Repave	1 Urgent	$193,268 State revolving loan	6.62	Failed arterial road (condition 5), paved 2011, 14,453 vehicles/day
1340	2034	**Rutherford Ave** S24711.1	Repave	1 Urgent	$191,763 State revolving loan	6.57	Failed arterial road (condition 5), paved 2011, 14,442 vehicles/day
1341	2034	**S Huntington Ave** S25444	Repave	1 Urgent	$180,093 State revolving loan	6.39	Failed arterial road (condition 9), paved 2012, 15,061 vehicles/day
1342	2034	**Commonwealth Ave** S10248	Repave	1 Urgent	$203,083 State revolving loan	6.33	Failed arterial road (condition 3), paved 2010, 13,246 vehicles/day
1343	2034	**Bennington St** S23328	Repave	1 Urgent	$181,681 State revolving loan	6.14	Failed arterial road (condition 1), paved 2010, 13,981 vehicles/day
1344	2034	**Harvard St** S18386.1	Repave	1 Urgent	$172,382 State revolving loan	5.96	Failed arterial road (condition 5), paved 2011, 14,407 vehicles/day
1345	2034	**Commonwealth Ave** S9938.2	Repave	1 Urgent	$194,464 State revolving loan	5.79	Failed arterial road (condition 0), paved 2008, 12,409 vehicles/day
1346	2034	**Western Ave** S10634	Repave	1 Urgent	$164,444 State revolving loan	5.78	Failed arterial road (condition 4), paved 2011, 14,664 vehicles/day
1347	2034	**Washington St** S8059	Repave	1 Urgent	$163,908 State revolving loan	5.77	Failed arterial road (condition 9), paved 2012, 14,984 vehicles/day
1348	2034	**Adams St** S12376.2	Repave	1 Urgent	$184,052 State revolving loan	5.69	Failed arterial road (condition 0), paved 2009, 12,758 vehicles/day
1349	2034	**W Newton St** S25247.2	Repave	1 Urgent	$174,155 State revolving loan	5.60	Failed arterial road (condition 3), paved 2010, 13,324 vehicles/day
1350	2034	**Commonwealth Ave** S25071	Repave	1 Urgent	$183,722 State revolving loan	5.49	Failed arterial road (condition 0), paved 2001, 12,325 vehicles/day
1351	2034	**Hampden St** S25555	Repave	1 Urgent	$155,022 State revolving loan	5.48	Failed arterial road (condition 4), paved 2011, 14,879 vehicles/day
1352	2034	**Cambridge St** S14305	Repave	1 Urgent	$183,145 State revolving loan	5.47	Failed arterial road (condition 0), paved 2005, 12,329 vehicles/day
1353	2034	**Dorchester St** S21832	Repave	1 Urgent	$179,207 State revolving loan	5.47	Failed arterial road (condition 0), paved 2009, 12,561 vehicles/day
1354	2034	**Washington St** S25592	Repave	1 Urgent	$154,341 State revolving loan	5.44	Failed arterial road (condition 9), paved 2012, 15,124 vehicles/day

1355	2034	**Adams St** S25797	Repave	1 Urgent	$174,836 State revolving loan	5.25	Failed arterial road (condition 0), paved 2008, 12,341 vehicles/day
1356	2034	**L St** S9797	Repave	1 Urgent	$147,269 State revolving loan	5.24	Failed arterial road (condition 8), paved 2012, 15,441 vehicles/day
1357	2034	**Blue Hill Ave** S15724	Repave	1 Urgent	$173,063 State revolving loan	5.19	Failed arterial road (condition 0), paved 2007, 12,329 vehicles/day
1358	2034	**Washington St** S19795	Repave	1 Urgent	$171,434 State revolving loan	5.16	Failed arterial road (condition 0), paved 2000, 12,358 vehicles/day
1359	2034	**Warren St** S17599	Repave	1 Urgent	$148,321 State revolving loan	5.13	Failed arterial road (condition 4), paved 2011, 14,748 vehicles/day
1360	2034	**Cambridge St** S20278	Repave	1 Urgent	$143,393 State revolving loan	4.77	Failed arterial road (condition 5), paved 2011, 14,442 vehicles/day
1361	2034	**Commonwealth Ave** S10696	Repave	1 Urgent	$148,774 State revolving loan	4.73	Failed arterial road (condition 3), paved 2010, 13,478 vehicles/day
1362	2034	**Devonshire St** S15281	Repave	1 Urgent	$149,991 State revolving loan	4.69	Failed arterial road (condition 3), paved 2010, 13,237 vehicles/day
1363	2034	**Cummins Hwy** S18067	Repave	1 Urgent	$138,259 State revolving loan	4.69	Failed arterial road (condition 3), paved 2011, 14,962 vehicles/day
1364	2034	**Hyde Park Ave** S12550	Repave	1 Urgent	$151,702 State revolving loan	4.63	Failed arterial road (condition 0), paved 2009, 12,768 vehicles/day
1365	2034	**Adams St** S21345	Repave	1 Urgent	$145,475 State revolving loan	4.60	Failed arterial road (condition 2), paved 2010, 13,532 vehicles/day
1366	2034	**Blue Hill Ave** S18156	Repave	1 Urgent	$135,517 State revolving loan	4.59	Failed arterial road (condition 8), paved 2012, 15,385 vehicles/day
1367	2034	**Dorchester Ave** S9751	Repave	1 Urgent	$142,671 State revolving loan	4.56	Failed arterial road (condition 1), paved 2010, 13,787 vehicles/day
1368	2034	**Arch St** S66	Repave	1 Urgent	$149,125 State revolving loan	4.53	Failed arterial road (condition 0), paved 2009, 12,786 vehicles/day
1369	2034	**Washington St** S13368	Repave	1 Urgent	$139,640 Interest-free loan	4.51	Failed arterial road (condition 6), paved 2011, 14,242 vehicles/day
1370	2034	**Saratoga St** S16802	Repave	1 Urgent	$131,641 Interest-free loan	4.51	Failed arterial road (condition 7), paved 2012, 15,838 vehicles/day
1371	2034	**Shawmut Ave** S8804	Repave	1 Urgent	$138,218 Interest-free loan	4.49	Failed arterial road (condition 5), paved 2011, 14,389 vehicles/day
1372	2034	**N Beacon St** S5568	Repave	1 Urgent	$132,094 Interest-free loan	4.46	Failed arterial road (condition 7), paved 2012, 15,620 vehicles/day
1373	2034	**High St** S9770	Repave	1 Urgent	$138,857 Interest-free loan	4.46	Failed arterial road (condition 1), paved 2010, 14,027 vehicles/day
1374	2034	**Washington St** S11369	Repave	1 Urgent	$135,785 Interest-free loan	4.34	Failed arterial road (condition 5), paved 2011, 14,329 vehicles/day
1375	2034	**Washington St** S8081	Repave	1 Urgent	$139,640 Interest-free loan	4.29	Failed arterial road (condition 3), paved 2010, 13,427 vehicles/day

1376	2034	**Harrison Ave** S17556	Repave	1 Urgent	$140,589 Interest-free loan	4.22	Failed arterial road (condition 0), paved 2009, 12,994 vehicles/day
1377	2034	**Park Dr** S16843	Repave	1 Urgent	$133,063 Interest-free loan	4.21	Failed arterial road (condition 5), paved 2011, 14,422 vehicles/day
1378	2034	**Columbus Ave** S19311	Repave	1 Urgent	$133,146 Interest-free loan	4.17	Failed arterial road (condition 6), paved 2011, 14,271 vehicles/day
1379	2034	**S Huntington Ave** S17352	Repave	1 Urgent	$144,135 Interest-free loan	4.17	Failed arterial road (condition 0), paved 2008, 12,339 vehicles/day
1380	2034	**Centre St** S20356	Repave	1 Urgent	$137,579 Interest-free loan	4.05	Failed arterial road (condition 0), paved 2009, 12,906 vehicles/day
1381	2034	**D St** S24314	Repave	1 Urgent	$126,795 Interest-free loan	3.97	Failed arterial road (condition 4), paved 2011, 14,878 vehicles/day
1382	2034	**Centre St** S1498	Repave	1 Urgent	$134,651 Interest-free loan	3.96	Failed arterial road (condition 3), paved 2010, 13,212 vehicles/day
1383	2034	**Hancock St** S3737	Repave	1 Urgent	$123,434 Interest-free loan	3.82	Failed arterial road (condition 8), paved 2012, 15,431 vehicles/day
1384	2034	**Lagrange St** S4540	Repave	1 Urgent	$135,393 Interest-free loan	3.80	Failed arterial road (condition 0), paved 2008, 12,430 vehicles/day
1385	2034	**Dudley St** S25483	Repave	1 Urgent	$125,455 Interest-free loan	3.78	Failed arterial road (condition 5), paved 2011, 14,540 vehicles/day
1386	2034	**Chestnut Hill Ave** S20717	Repave	1 Urgent	$121,847 Interest-free loan	3.73	Failed arterial road (condition 8), paved 2012, 15,496 vehicles/day
1387	2034	**Hemenway St** S3972	Repave	1 Urgent	$124,032 Interest-free loan	3.73	Failed arterial road (condition 9), paved 2012, 14,968 vehicles/day
1388	2034	**Townsend St** S7366	Repave	1 Urgent	$127,888 Interest-free loan	3.70	Failed arterial road (condition 2), paved 2010, 13,567 vehicles/day
1389	2034	**Tremont St** S7694	Repave	1 Urgent	$128,074 Interest-free loan	3.67	Failed arterial road (condition 3), paved 2010, 13,429 vehicles/day
1390	2034	**River St** S6654	Repave	1 Urgent	$133,001 Interest-free loan	3.65	Failed arterial road (condition 0), paved 2005, 12,315 vehicles/day
1391	2034	**D St** S20081	Repave	1 Urgent	$123,084 Interest-free loan	3.54	Failed arterial road (condition 1), paved 2010, 14,049 vehicles/day
1392	2034	**N Beacon St** S21529	Repave	1 Urgent	$120,074 Interest-free loan	3.50	Failed arterial road (condition 4), paved 2011, 14,872 vehicles/day
1393	2034	**Bennington St** S23072	Repave	1 Urgent	$122,837 Interest-free loan	3.49	Failed arterial road (condition 6), paved 2011, 14,126 vehicles/day
1394	2034	**Tremont St** S16953	Repave	1 Urgent	$125,661 Interest-free loan	3.45	Failed arterial road (condition 0), paved 2009, 13,057 vehicles/day
1395	2034	**River St** S12863	Repave	1 Urgent	$120,775 Interest-free loan	3.36	Failed arterial road (condition 6), paved 2011, 14,158 vehicles/day
1396	2034	**Clarendon St** S12220	Repave	1 Urgent	$118,445 Interest-free loan	3.36	Failed arterial road (condition 9), paved 2012, 15,066 vehicles/day

1397	2034	**Boylston St** S13384	Repave	1 Urgent	$117,496 Interest-free loan	3.35	Failed arterial road (condition 8), paved 2012, 15,318 vehicles/day
1398	2034	**Tremont St** S7664	Repave	1 Urgent	$117,661 Interest-free loan	3.34	Failed arterial road (condition 8), paved 2012, 15,240 vehicles/day
1399	2034	**Kneeland St** S9831	Repave	1 Urgent	$125,311 Interest-free loan	3.24	Failed arterial road (condition 0), paved 2005, 12,316 vehicles/day
1400	2034	**Commonwealth Ave** S24915	Repave	1 Urgent	$116,280 Interest-free loan	3.22	Failed arterial road (condition 9), paved 2012, 15,178 vehicles/day
1401	2034	**Adams St** S17868	Repave	1 Urgent	$120,445 Interest-free loan	3.19	Failed arterial road (condition 3), paved 2010, 13,421 vehicles/day
1402	2034	**Ruggles St** S13634	Repave	1 Urgent	$122,507 Interest-free loan	3.19	Failed arterial road (condition 0), paved 2009, 12,786 vehicles/day
1403	2034	**Sumner St** S7435	Repave	1 Urgent	$124,404 Interest-free loan	3.19	Failed arterial road (condition 0), paved 2003, 12,334 vehicles/day
1404	2034	**Somerset St** S14081	Repave	1 Urgent	$122,362 Interest-free loan	3.17	Failed arterial road (condition 0), paved 2009, 12,738 vehicles/day
1405	2034	**Medford St** S5180	Repave	1 Urgent	$114,795 Interest-free loan	3.17	Failed arterial road (condition 8), paved 2012, 15,450 vehicles/day
1406	2034	**Massachusetts Ave** S16572	Repave	1 Urgent	$118,445 Interest-free loan	3.08	Failed arterial road (condition 2), paved 2010, 13,522 vehicles/day
1407	2034	**Columbia Rd** S17790	Repave	1 Urgent	$116,527 Interest-free loan	3.01	Failed arterial road (condition 2), paved 2010, 13,762 vehicles/day
1408	2034	**Massachusetts Ave** S24428	Repave	1 Urgent	$117,723 Interest-free loan	2.98	Failed arterial road (condition 0), paved 2009, 13,220 vehicles/day
1409	2034	**Clarendon St** S1752	Repave	1 Urgent	$117,579 Interest-free loan	2.95	Failed arterial road (condition 0), paved 2009, 13,094 vehicles/day
1410	2034	**Massachusetts Ave** S10625	Repave	1 Urgent	$116,094 Interest-free loan	2.90	Failed arterial road (condition 3), paved 2010, 13,458 vehicles/day
1411	2034	**Causeway St** S24504	Repave	1 Urgent	$115,971 Interest-free loan	2.86	Failed arterial road (condition 0), paved 2009, 13,216 vehicles/day
1412	2034	**D St** S2082	Repave	1 Urgent	$117,950 Interest-free loan	2.80	Failed arterial road (condition 0), paved 1999, 12,345 vehicles/day
1413	2034	**Sumner St** S12461	Repave	1 Urgent	$109,043 Interest-free loan	2.75	Failed arterial road (condition 7), paved 2012, 15,812 vehicles/day
1414	2034	**Cambridge St** S26809	Repave	1 Urgent	$110,713 Interest-free loan	2.70	Failed arterial road (condition 4), paved 2011, 14,626 vehicles/day
1415	2034	**Bowdoin St** S941	Repave	1 Urgent	$115,661 Interest-free loan	2.69	Failed arterial road (condition 0), paved 2009, 12,512 vehicles/day
1416	2034	**E Berkeley St** S13330	Repave	1 Urgent	$114,094 Interest-free loan	2.65	Failed arterial road (condition 0), paved 2009, 12,826 vehicles/day
1417	2034	**Warren St** S22061	Repave	1 Urgent	$112,795 Interest-free loan	2.62	Failed arterial road (condition 0), paved 2009, 13,170 vehicles/day

1418	2034	**Washington St** S8027	Repave	1 Urgent	$109,311 Interest-free loan	2.61	Failed arterial road (condition 4), paved 2011, 14,740 vehicles/day
1419	2034	**Atlantic Ave** S302	Repave	1 Urgent	$114,259 Interest-free loan	2.56	Failed arterial road (condition 0), paved 2007, 12,325 vehicles/day
1420	2034	**River St** S23123	Repave	1 Urgent	$112,878 Rate revenue	2.50	Failed arterial road (condition 0), paved 2009, 12,529 vehicles/day
1421	2034	**Cambridge St** S22510	Repave	1 Urgent	$108,342 Rate revenue	2.48	Failed arterial road (condition 5), paved 2011, 14,509 vehicles/day
1422	2034	**Cambridge St** S21438	Repave	1 Urgent	$105,806 Rate revenue	2.43	Failed arterial road (condition 7), paved 2012, 15,777 vehicles/day
1423	2034	**Arlington St** S350	Repave	1 Urgent	$111,476 Rate revenue	2.37	Failed arterial road (condition 0), paved 2000, 12,354 vehicles/day
1424	2034	**Cambridge St** S1320	Repave	1 Urgent	$106,095 Rate revenue	2.28	Failed arterial road (condition 5), paved 2011, 14,540 vehicles/day
1425	2034	**Freeport St** S27366	Repave	1 Urgent	$107,022 Rate revenue	2.28	Failed arterial road (condition 6), paved 2011, 14,069 vehicles/day
1426	2034	**Arlington St** S16614	Repave	1 Urgent	$105,497 Rate revenue	2.28	Failed arterial road (condition 4), paved 2011, 14,829 vehicles/day
1427	2034	**American Legion Hwy** S26880	Repave	1 Urgent	$109,187 Rate revenue	2.26	Failed arterial road (condition 0), paved 2009, 12,688 vehicles/day
1428	2034	**Boston St** S897	Repave	1 Urgent	$106,940 Rate revenue	2.11	Failed arterial road (condition 0), paved 2009, 12,865 vehicles/day
1429	2034	**Geneva Ave** S10037	Repave	1 Urgent	$105,394 Rate revenue	2.10	Failed arterial road (condition 2), paved 2010, 13,690 vehicles/day
1430	2034	**Centre St** S23638	Repave	1 Urgent	$102,342 Rate revenue	2.07	Failed arterial road (condition 7), paved 2012, 15,742 vehicles/day
1431	2034	**N Harvard St** S26950	Repave	1 Urgent	$103,517 Rate revenue	2.06	Failed arterial road (condition 4), paved 2011, 14,702 vehicles/day
1432	2034	**Babson St** S18211	Repave	1 Urgent	$105,827 Rate revenue	2.04	Failed arterial road (condition 0), paved 2009, 12,961 vehicles/day
1433	2034	**Washington St** S17524	Repave	1 Urgent	$106,796 Rate revenue	2.02	Failed arterial road (condition 0), paved 2006, 12,329 vehicles/day
1434	2034	**Hancock St** S25694	Repave	1 Urgent	$102,342 Rate revenue	1.97	Failed arterial road (condition 9), paved 2012, 15,142 vehicles/day
1435	2034	**Huntington Ave** S4281	Repave	1 Urgent	$100,486 Rate revenue	1.73	Failed arterial road (condition 5), paved 2011, 14,492 vehicles/day
1436	2034	**Massachusetts Ave** S14887	Repave	1 Urgent	$99,785 Rate revenue	1.70	Failed arterial road (condition 9), paved 2012, 15,085 vehicles/day
1437	2034	**Hancock St** S17802	Repave	1 Urgent	$101,992 Rate revenue	1.65	Failed arterial road (condition 0), paved 2004, 12,480 vehicles/day
1438	2034	**Congress St** S1958	Repave	1 Urgent	$101,146 Rate revenue	1.63	Failed arterial road (condition 0), paved 2009, 12,986 vehicles/day
1439	2034	**Washington St** S7990	Repave	1 Urgent	$101,311 Rate revenue	1.62	Failed arterial road (condition 0), paved 2008, 12,753 vehicles/day
1440	2034	**Washington St** S8095	Repave	1 Urgent	$101,022 Rate revenue	1.59	Failed arterial road (condition 0), paved 2001, 12,705 vehicles/day
1441	2034	**Wood Ave** S8633	Repave	1 Urgent	$97,579 Rate revenue	1.51	Failed arterial road (condition 0), paved 2007, 15,103 vehicles/day
1442	2034	**Commercial St** S1888	Repave shared dig B-2034-S1888	1 Urgent	$55,779 Rate revenue	1.50	Failed arterial road (condition 9), paved 2012, 15,078 vehicles/day
1443	2034	**Washington St** S8169	Repave shared dig B-2034-S8169	1 Urgent	$54,810 Rate revenue	1.49	Failed arterial road (condition 0), paved 2009, 15,644 vehicles/day
1444	2034	**Washington St** S8140	Repave	1 Urgent	$99,414 Rate revenue	1.48	Failed arterial road (condition 0), paved 2003, 13,077 vehicles/day
1445	2034	**Bunker Hill St** S1209	Repave	1 Urgent	$99,476 Rate revenue	1.47	Failed arterial road (condition 0), paved 2007, 12,898 vehicles/day

1446	2034	**Dorchester Ave** S2386	Repave	1 Urgent	$98,899 Rate revenue	1.46	Failed arterial road (condition 0), paved 2007, 13,319 vehicles/day
1447	2034	**Dorchester St** S2484	Repave shared dig B-2034-S2484	1 Urgent	$55,862 Rate revenue	1.46	Failed arterial road (condition 5), paved 2011, 14,459 vehicles/day
1448	2034	**Hancock St** S25688	Repave	1 Urgent	$98,157 Rate revenue	1.45	Failed arterial road (condition 0), paved 2006, 13,944 vehicles/day
1449	2034	**Market St** S27223	Repave	1 Urgent	$99,517 Rate revenue	1.44	Failed arterial road (condition 0), paved 1999, 12,595 vehicles/day
1450	2034	**N Washington St** S19525	Repave	1 Urgent	$98,280 Rate revenue	1.42	Failed arterial road (condition 0), paved 2008, 13,526 vehicles/day
1451	2034	**Hancock St** S22462	Repave shared dig B-2034-S22462	1 Urgent	$55,449 Rate revenue	1.39	Failed arterial road (condition 0), paved 2006, 14,106 vehicles/day
1452	2034	**Pleasant St** S6278	Repave shared dig B-2034-S6278	1 Urgent	$54,295 Rate revenue	1.36	Failed arterial road (condition 9), paved 2012, 14,985 vehicles/day
1453	2034	**Massachusetts Ave** S25551	Repave shared dig B-2034-S25551 engineering review	1 Urgent	$53,697 Rate revenue	1.18	Failed arterial road (condition 0), paved 2009, 13,020 vehicles/day
1454	2034	**Hancock St** S3740	Repave shared dig B-2034-S3740 engineering review	1 Urgent	$52,089 Rate revenue	1.16	Failed arterial road (condition 5), paved 2011, 14,479 vehicles/day
1455	2034	**Commercial St** S1888	Replace water main shared dig B-2034-S1888	4 Monitor	$75,016 Rate revenue	1.50	Moderate risk (index 28): cast iron main from 1899, 2 prior breaks, PoF 82
1456	2034	**Washington St** S8169	Replace water main shared dig B-2034-S8169	4 Monitor	$72,593 Rate revenue	1.49	Moderate risk (index 28): cast iron main from 1915, 1 prior breaks, PoF 84
1457	2034	**Dorchester St** S2484	Replace water main shared dig B-2034-S2484	4 Monitor	$75,222 Rate revenue	1.46	Moderate risk (index 30): cast iron main from 1866, 1 prior breaks, PoF 91
1458	2034	**Hancock St** S22462	Replace water main shared dig B-2034-S22462	4 Monitor	$74,191 Rate revenue	1.39	Moderate risk (index 26): cast iron main from 1896, 1 prior breaks, PoF 91
1459	2034	**Pleasant St** S6278	Replace water main shared dig B-2034-S6278	4 Monitor	$71,305 Rate revenue	1.36	Low risk (index 25): cast iron main from 1890, 1 prior breaks, PoF 84
1460	2034	**Commonwealth Ave** S24640	Repave	4 Monitor	$187,227 Rate revenue	1.19	Fair arterial road (condition 78), paved 2026, 15,441 vehicles/day
1461	2034	**Massachusetts Ave** S25551	Replace water main shared dig B-2034-S25551 engineering review	4 Monitor	$69,810 Rate revenue	1.18	Low risk (index 22): cast iron main from 1873, 1 prior breaks, PoF 84
1462	2034	**Blue Hill Ave** S12901	Repave engineering review	4 Monitor	$211,804 Rate revenue	1.17	Fair arterial road (condition 78), paved 2026, 14,624 vehicles/day
1463	2034	**Hancock St** S3740	Replace water main shared dig B-2034-S3740 engineering review	4 Monitor	$65,789 Rate revenue	1.16	Low risk (index 24): cast iron main from 1910, 1 prior breaks, PoF 91
1464	2034	**Lagrange St** S19073	Repave engineering review	4 Monitor	$162,465 Rate revenue	1.11	Fair arterial road (condition 77), paved 2026, 15,969 vehicles/day
1465	2034	**Summer St** S20206	Repave engineering review	4 Monitor	$253,123 Rate revenue	1.06	Fair arterial road (condition 79), paved 2026, 13,205 vehicles/day
1466	2034	**Summer St** S7424	Repave engineering review	4 Monitor	$147,785 Rate revenue	1.00	Fair arterial road (condition 72), paved 2024, 13,017 vehicles/day
1467	2035	**Columbus Ave** S13836.1	Repave	1 Urgent	$243,463 State revolving loan	6.77	Failed arterial road (condition 6), paved 2012, 14,146 vehicles/day
1468	2035	**Columbus Ave** S13836.2	Repave	1 Urgent	$243,463 State revolving loan	6.72	Failed arterial road (condition 1), paved 2011, 13,880 vehicles/day
1469	2035	**E Broadway** S2408	Repave	1 Urgent	$218,225 State revolving loan	6.67	Failed arterial road (condition 4), paved 2012, 14,906 vehicles/day
1470	2035	**Centre St** S13478	Repave	1 Urgent	$215,048 State revolving loan	6.66	Failed arterial road (condition 8), paved 2013, 15,297 vehicles/day
1471	2035	**American Legion Hwy** S18640.2	Repave	1 Urgent	$208,827 State revolving loan	6.56	Failed arterial road (condition 8), paved 2013, 15,399 vehicles/day

1472	2035	**Townsend St** S25631	Repave	1 Urgent	$232,521 State revolving loan	6.47	Failed arterial road (condition 2), paved 2011, 13,754 vehicles/day
1473	2035	**River St** S13582	Repave	1 Urgent	$211,165 State revolving loan	6.43	Failed arterial road (condition 9), paved 2013, 15,035 vehicles/day
1474	2035	**Sudbury St** S15671	Repave	1 Urgent	$263,937 State revolving loan	6.40	Failed arterial road (condition 0), paved 2010, 12,563 vehicles/day
1475	2035	**Huntington Ave** S4275	Repave	1 Urgent	$237,022 State revolving loan	6.36	Failed arterial road (condition 3), paved 2011, 13,395 vehicles/day
1476	2035	**Beacon St** S17172.2	Repave	1 Urgent	$230,910 State revolving loan	6.30	Failed arterial road (condition 2), paved 2011, 13,497 vehicles/day
1477	2035	**Columbia Rd** S17804	Repave	1 Urgent	$182,000 State revolving loan	6.02	Failed arterial road (condition 6), paved 2013, 15,885 vehicles/day
1478	2035	**Cambridge St** S25120	Repave	1 Urgent	$200,046 State revolving loan	5.78	Failed arterial road (condition 2), paved 2011, 13,766 vehicles/day
1479	2035	**Reservation Rd** S15099.2	Repave	1 Urgent	$191,134 State revolving loan	5.74	Failed arterial road (condition 5), paved 2012, 14,363 vehicles/day
1480	2035	**Dorchester Ave** S24164	Repave	1 Urgent	$172,514 State revolving loan	5.71	Failed arterial road (condition 6), paved 2013, 15,939 vehicles/day
1481	2035	**Centre St** S18732	Repave	1 Urgent	$172,492 State revolving loan	5.67	Failed arterial road (condition 6), paved 2013, 15,863 vehicles/day
1482	2035	**Rutherford Ave** S20510	Repave	1 Urgent	$213,195 State revolving loan	5.54	Failed arterial road (condition 0), paved 2010, 12,480 vehicles/day
1483	2035	**Washington St** S20069	Repave	1 Urgent	$174,587 State revolving loan	5.51	Failed arterial road (condition 8), paved 2013, 15,310 vehicles/day
1484	2035	**Medford St** S13986	Repave	1 Urgent	$176,154 State revolving loan	5.50	Failed arterial road (condition 4), paved 2012, 14,894 vehicles/day
1485	2035	**Warren St** S17589	Repave	1 Urgent	$171,433 State revolving loan	5.49	Failed arterial road (condition 7), paved 2013, 15,531 vehicles/day
1486	2035	**Commonwealth Ave** S10701.2	Repave	1 Urgent	$203,312 State revolving loan	5.45	Failed arterial road (condition 0), paved 2010, 12,743 vehicles/day
1487	2035	**West St** S8367	Repave	1 Urgent	$182,155 State revolving loan	5.43	Failed arterial road (condition 6), paved 2012, 14,240 vehicles/day
1488	2035	**Washington St** S18564.1	Repave	1 Urgent	$187,096 State revolving loan	5.40	Failed arterial road (condition 2), paved 2011, 13,660 vehicles/day
1489	2035	**Washington St** S17493	Repave	1 Urgent	$162,321 State revolving loan	5.25	Failed arterial road (condition 7), paved 2013, 15,810 vehicles/day
1490	2035	**American Legion Hwy** S18073	Repave	1 Urgent	$196,406 State revolving loan	5.17	Failed arterial road (condition 1), paved 2010, 12,448 vehicles/day
1491	2035	**Walk Hill St** S18399	Repave	1 Urgent	$196,848 State revolving loan	5.15	Failed arterial road (condition 0), paved 2009, 12,373 vehicles/day
1492	2035	**Dorchester Ave** S17845	Repave	1 Urgent	$169,579 State revolving loan	5.07	Failed arterial road (condition 5), paved 2012, 14,381 vehicles/day

1493	2035	**Blue Hill Ave** S13722	Repave	1 Urgent	$181,029 State revolving loan	4.87	Failed arterial road (condition 0), paved 2010, 12,657 vehicles/day
1494	2035	**Brighton Ave** S17001	Repave	1 Urgent	$159,277 Interest-free loan	4.82	Failed arterial road (condition 9), paved 2013, 15,035 vehicles/day
1495	2035	**Harvard St** S3889	Repave	1 Urgent	$157,534 Interest-free loan	4.80	Failed arterial road (condition 4), paved 2012, 14,918 vehicles/day
1496	2035	**Walk Hill St** S7901	Repave	1 Urgent	$166,050 State revolving loan	4.78	Failed arterial road (condition 1), paved 2011, 13,783 vehicles/day
1497	2035	**Washington St** S8154	Repave	1 Urgent	$154,622 Interest-free loan	4.78	Failed arterial road (condition 8), paved 2013, 15,465 vehicles/day
1498	2035	**Commonwealth Ave** S26857	Repave	1 Urgent	$156,938 Interest-free loan	4.71	Failed arterial road (condition 4), paved 2012, 14,716 vehicles/day
1499	2035	**Chestnut Hill Ave** S1669	Repave	1 Urgent	$179,375 State revolving loan	4.68	Failed arterial road (condition 0), paved 2007, 12,289 vehicles/day
1500	2035	**Dorchester Ave** S20827	Repave	1 Urgent	$165,785 Interest-free loan	4.66	Failed arterial road (condition 3), paved 2011, 13,472 vehicles/day
1501	2035	**Sumner St** S14069	Repave	1 Urgent	$154,600 Interest-free loan	4.59	Failed arterial road (condition 9), paved 2013, 14,956 vehicles/day
1502	2035	**Charles St** S1563	Repave	1 Urgent	$157,799 Interest-free loan	4.51	Failed arterial road (condition 6), paved 2012, 14,075 vehicles/day
1503	2035	**Tremont St** S20047	Repave	1 Urgent	$149,526 Interest-free loan	4.40	Failed arterial road (condition 9), paved 2013, 15,070 vehicles/day
1504	2035	**Causeway St** S19742	Repave	1 Urgent	$162,012 Interest-free loan	4.39	Failed arterial road (condition 0), paved 2010, 13,006 vehicles/day
1505	2035	**W Milton St** S8307	Repave	1 Urgent	$145,003 Interest-free loan	4.37	Failed arterial road (condition 7), paved 2013, 15,639 vehicles/day
1506	2035	**Blue Hill Ave** S18176	Repave	1 Urgent	$158,019 Interest-free loan	4.36	Failed arterial road (condition 3), paved 2011, 13,448 vehicles/day
1507	2035	**W Second St** S13616	Repave	1 Urgent	$152,835 Interest-free loan	4.33	Failed arterial road (condition 1), paved 2011, 13,957 vehicles/day
1508	2035	**Columbus Ave** S15937	Repave	1 Urgent	$151,401 Interest-free loan	4.27	Failed arterial road (condition 1), paved 2011, 13,963 vehicles/day
1509	2035	**Atlantic Ave** S19997	Repave	1 Urgent	$157,181 Interest-free loan	4.27	Failed arterial road (condition 0), paved 2010, 13,166 vehicles/day
1510	2035	**Victory Rd** S7834	Repave	1 Urgent	$145,532 Interest-free loan	4.15	Failed arterial road (condition 5), paved 2012, 14,607 vehicles/day
1511	2035	**Merrimac St** S22207	Repave	1 Urgent	$140,569 Interest-free loan	3.99	Failed arterial road (condition 4), paved 2012, 14,909 vehicles/day
1512	2035	**N Harvard St** S11524	Repave	1 Urgent	$150,143 Interest-free loan	3.98	Failed arterial road (condition 0), paved 2010, 13,143 vehicles/day
1513	2035	**Clarendon St** S1560	Repave	1 Urgent	$155,592 Interest-free loan	3.98	Failed arterial road (condition 1), paved 2010, 12,454 vehicles/day

1514	2035	**Beacon St** S25314	Repave	1 Urgent	$139,068 Interest-free loan	3.96	Failed arterial road (condition 8), paved 2013, 15,369 vehicles/day
1515	2035	**Dartmouth St** S16564	Repave	1 Urgent	$138,936 Interest-free loan	3.88	Failed arterial road (condition 4), paved 2012, 14,835 vehicles/day
1516	2035	**Blue Hill Ave** S14134	Repave	1 Urgent	$167,197 Interest-free loan	3.87	Failed arterial road (condition 0), paved 2006, 10,989 vehicles/day
1517	2035	**River St** S10294	Repave	1 Urgent	$142,201 Interest-free loan	3.85	Failed arterial road (condition 1), paved 2011, 13,974 vehicles/day
1518	2035	**Dudley St** S11488	Repave	1 Urgent	$135,384 Interest-free loan	3.83	Failed arterial road (condition 7), paved 2013, 15,622 vehicles/day
1519	2035	**Norfolk St** S5736	Repave	1 Urgent	$150,165 Interest-free loan	3.79	Failed arterial road (condition 0), paved 2010, 12,526 vehicles/day
1520	2035	**Cummins Hwy** S18064	Repave	1 Urgent	$136,928 Interest-free loan	3.77	Failed arterial road (condition 4), paved 2012, 14,866 vehicles/day
1521	2035	**A St** S7	Repave	1 Urgent	$145,797 Interest-free loan	3.74	Failed arterial road (condition 0), paved 2010, 12,964 vehicles/day
1522	2035	**River St** S6633	Repave	1 Urgent	$133,288 Interest-free loan	3.71	Failed arterial road (condition 7), paved 2013, 15,655 vehicles/day
1523	2035	**Arlington St** S11083	Repave	1 Urgent	$133,046 Interest-free loan	3.66	Failed arterial road (condition 7), paved 2013, 15,543 vehicles/day
1524	2035	**Harrison Ave** S3832	Repave	1 Urgent	$133,178 Interest-free loan	3.65	Failed arterial road (condition 8), paved 2013, 15,475 vehicles/day
1525	2035	**Cambridge St** S15059	Repave	1 Urgent	$144,253 Interest-free loan	3.61	Failed arterial road (condition 0), paved 2010, 12,728 vehicles/day
1526	2035	**Preble St** S19681	Repave	1 Urgent	$134,833 Interest-free loan	3.57	Failed arterial road (condition 5), paved 2012, 14,533 vehicles/day
1527	2035	**Main St** S20392	Repave	1 Urgent	$140,811 Interest-free loan	3.56	Failed arterial road (condition 3), paved 2011, 13,243 vehicles/day
1528	2035	**N Harvard St** S11985	Repave	1 Urgent	$138,804 Interest-free loan	3.52	Failed arterial road (condition 3), paved 2011, 13,448 vehicles/day
1529	2035	**Boylston St** S26689	Repave	1 Urgent	$134,458 Interest-free loan	3.52	Failed arterial road (condition 5), paved 2012, 14,440 vehicles/day
1530	2035	**Heath St** S25423	Repave	1 Urgent	$136,024 Interest-free loan	3.51	Failed arterial road (condition 6), paved 2012, 14,104 vehicles/day
1531	2035	**Oliver St** S23905	Repave	1 Urgent	$136,951 Interest-free loan	3.49	Failed arterial road (condition 2), paved 2011, 13,671 vehicles/day
1532	2035	**Centre St** S1497	Repave	1 Urgent	$131,369 Interest-free loan	3.48	Failed arterial road (condition 8), paved 2013, 15,263 vehicles/day
1533	2035	**Washington St** S8132	Repave	1 Urgent	$145,069 Interest-free loan	3.47	Failed arterial road (condition 2), paved 2010, 12,156 vehicles/day
1534	2035	**Kneeland St** S10867	Repave	1 Urgent	$131,788 Interest-free loan	3.43	Failed arterial road (condition 9), paved 2013, 14,994 vehicles/day

1535	2035	**Washington St** S18563	Repave	1 Urgent	$133,597 Interest-free loan	3.43	Failed arterial road (condition 6), paved 2012, 14,289 vehicles/day
1536	2035	**Tremont St** S7665	Repave	1 Urgent	$128,567 Interest-free loan	3.41	Failed arterial road (condition 7), paved 2013, 15,652 vehicles/day
1537	2035	**Commonwealth Ave** S10698	Repave	1 Urgent	$137,679 Interest-free loan	3.40	Failed arterial road (condition 3), paved 2011, 13,207 vehicles/day
1538	2035	**Huntington Ave** S13766	Repave	1 Urgent	$136,884 Interest-free loan	3.31	Failed arterial road (condition 0), paved 2010, 12,888 vehicles/day
1539	2035	**Dudley St** S2521	Repave	1 Urgent	$129,781 Interest-free loan	3.27	Failed arterial road (condition 5), paved 2012, 14,524 vehicles/day
1540	2035	**Commonwealth Ave** S24943	Repave	1 Urgent	$128,677 Rate revenue	3.25	Failed arterial road (condition 4), paved 2012, 14,751 vehicles/day
1541	2035	**Columbus Ave** S12872	Repave	1 Urgent	$134,038 Rate revenue	3.24	Failed arterial road (condition 3), paved 2011, 13,297 vehicles/day
1542	2035	**Centre St** S1494	Repave	1 Urgent	$127,530 Rate revenue	3.22	Failed arterial road (condition 3), paved 2012, 14,937 vehicles/day
1543	2035	**W Dedham St** S17311	Repave	1 Urgent	$134,325 Rate revenue	3.20	Failed arterial road (condition 0), paved 2010, 12,969 vehicles/day
1544	2035	**L St** S4520	Repave	1 Urgent	$127,133 Rate revenue	3.10	Failed arterial road (condition 5), paved 2012, 14,504 vehicles/day
1545	2035	**Dudley St** S13237	Repave	1 Urgent	$122,346 Rate revenue	2.92	Failed arterial road (condition 8), paved 2013, 15,415 vehicles/day
1546	2035	**Exeter St** S3003	Repave	1 Urgent	$124,442 Rate revenue	2.89	Failed arterial road (condition 5), paved 2012, 14,353 vehicles/day
1547	2035	**Market St** S15202	Repave	1 Urgent	$122,765 Rate revenue	2.86	Failed arterial road (condition 4), paved 2012, 14,761 vehicles/day
1548	2035	**Blue Hill Ave** S861	Repave	1 Urgent	$125,942 Rate revenue	2.85	Failed arterial road (condition 2), paved 2011, 13,576 vehicles/day
1549	2035	**Centre St** S1451	Repave	1 Urgent	$122,103 Rate revenue	2.84	Failed arterial road (condition 4), paved 2012, 14,883 vehicles/day
1550	2035	**Dartmouth St** S2241	Repave	1 Urgent	$124,375 Rate revenue	2.82	Failed arterial road (condition 1), paved 2011, 13,888 vehicles/day
1551	2035	**Ashmont St** S397	Repave	1 Urgent	$127,905 Rate revenue	2.77	Failed arterial road (condition 0), paved 2010, 12,607 vehicles/day
1552	2035	**Causeway St** S13017	Repave	1 Urgent	$121,905 Rate revenue	2.71	Failed arterial road (condition 5), paved 2012, 14,314 vehicles/day
1553	2035	**Maverick Sq** S24855	Repave	1 Urgent	$124,618 Rate revenue	2.70	Failed arterial road (condition 0), paved 2010, 13,164 vehicles/day
1554	2035	**Main St** S4922	Repave	1 Urgent	$125,479 Rate revenue	2.66	Failed arterial road (condition 0), paved 2010, 12,724 vehicles/day
1555	2035	**Norfolk St** S5727	Repave	1 Urgent	$124,133 Rate revenue	2.56	Failed arterial road (condition 0), paved 2010, 12,615 vehicles/day
1556	2035	**Preble St** S6365	Repave	1 Urgent	$119,809 Rate revenue	2.53	Failed arterial road (condition 1), paved 2011, 13,976 vehicles/day
1557	2035	**Dartmouth St** S2235	Repave	1 Urgent	$122,765 Rate revenue	2.42	Failed arterial road (condition 0), paved 2009, 12,340 vehicles/day
1558	2035	**Columbus Ave** S23434	Repave	1 Urgent	$119,720 Rate revenue	2.38	Failed arterial road (condition 0), paved 2010, 13,110 vehicles/day
1559	2035	**Tremont St** S27147	Repave	1 Urgent	$116,080 Rate revenue	2.37	Failed arterial road (condition 4), paved 2012, 14,760 vehicles/day
1560	2035	**Saratoga St** S24867	Repave	1 Urgent	$117,669 Rate revenue	2.37	Failed arterial road (condition 6), paved 2012, 14,090 vehicles/day
1561	2035	**Cummins Hwy** S18224	Repave	1 Urgent	$116,367 Rate revenue	2.34	Failed arterial road (condition 5), paved 2012, 14,466 vehicles/day

1562	2035	**Franklin St** S3158	Repave	1 Urgent	$117,823 Rate revenue	2.25	Failed arterial road (condition 3), paved 2011, 13,234 vehicles/day
1563	2035	**Washington St** S16515	Repave shared dig B-2035-S16515	1 Urgent	$62,750 Rate revenue	1.43	Failed arterial road (condition 0), paved 2010, 13,031 vehicles/day
1564	2035	**Washington St** S8096	Repave	1 Urgent	$104,057 Rate revenue	1.34	Failed arterial road (condition 0), paved 2011, 14,722 vehicles/day
1565	2035	**Dorchester Ave** S9665.1	Repave engineering review	3 Plan	$192,854 Rate revenue	1.01	Fair arterial road (condition 70), paved 2024, 10,868 vehicles/day
1566	2035	**Washington St** S16515	Replace water main shared dig B-2035-S16515	4 Monitor	$87,934 Rate revenue	1.43	Moderate risk (index 31): cast iron main from 1857, 2 prior breaks, PoF 95
1567	2035	**Westland Ave** S15710	Repave engineering review	4 Monitor	$196,009 Rate revenue	1.15	Fair arterial road (condition 75), paved 2026, 14,206 vehicles/day
1568	2035	**Commonwealth Ave** S13434	Repave engineering review	4 Monitor	$216,063 Rate revenue	1.12	Fair arterial road (condition 75), paved 2026, 13,474 vehicles/day
1569	2035	**Newbury St** S5660	Repave engineering review	4 Monitor	$227,491 Rate revenue	1.12	Fair arterial road (condition 76), paved 2026, 13,216 vehicles/day
1570	2035	**E First St** S11658	Repave engineering review	4 Monitor	$186,192 Rate revenue	1.04	Fair arterial road (condition 75), paved 2026, 13,803 vehicles/day

NEEDS ENGINEERING REVIEW

Return could fall below the hurdle or reach it, depending on the pipe failure bounds (low return under 1.0, high return at or above). Showing 40 of 97.

YEAR	STREET	WORK	STATUS	COST	RETURN RANGE
2026	Boston St	Repave	Funded	$27,064	0.87 to 1.26
2026	Boston St	Replace water main	Funded	$30,160	0.87 to 1.26
2026	Huntington Ave	Replace water main	Funded	$92,590	0.85 to 1.17
2026	Huntington Ave	Repave	Funded	$52,036	0.85 to 1.17
2026	Perkins St	Replace water main	Funded	$51,460	0.82 to 1.16
2026	Perkins St	Repave	Funded	$35,584	0.82 to 1.16
2027	River St	Repave	Funded	$29,921	0.94 to 1.32
2027	River St	Replace water main	Funded	$34,679	0.94 to 1.32
2027	Massachusetts Ave	Repave	Funded	$122,361	0.88 to 1.19
2027	N Harvard St	Replace water main	Funded	$85,429	0.83 to 1.14
2027	N Harvard St	Repave	Funded	$50,222	0.83 to 1.14
2027	Seaport Blvd	Repave	Not funded	$0	0.75 to 1.01
2028	Seaport Blvd	Repave	Funded	$106,526	0.91 to 1.24
2028	E First St	Repave	Funded	$134,375	0.88 to 1.18
2028	River St	Replace water main	Funded	$98,965	0.83 to 1.21
2028	River St	Repave	Funded	$56,760	0.83 to 1.21
2028	W Second St	Repave	Not funded	$0	0.81 to 1.10
2028	Perkins St	Repave	Funded	$60,268	0.75 to 1.01
2029	W Second St	Repave	Funded	$101,179	0.93 to 1.26
2029	Hyde Park Ave	Repave	Funded	$65,780	0.93 to 1.26
2029	Tremont St	Replace water main	Funded	$99,792	0.84 to 1.16
2029	Tremont St	Repave	Funded	$58,292	0.84 to 1.16
2030	Old Colony Ave	Repave	Funded	$38,197	0.91 to 1.29
2030	Old Colony Ave	Replace water main	Funded	$46,337	0.91 to 1.29
2030	Savin Hill Ave	Repave	Not funded	$0	0.76 to 1.03
2031	Tremont St	Repave	Not funded	$0	0.92 to 1.24
2031	Melnea Cass Blvd	Repave	Funded	$190,870	0.89 to 1.20
2031	Norfolk St	Repave	Funded	$40,837	0.84 to 1.19
2031	Norfolk St	Replace water main	Funded	$49,496	0.84 to 1.19
2031	Stoughton St	Repave	Funded	$120,199	0.85 to 1.15

2031	Saratoga St	Repave	Not funded	$0	0.84 to 1.14
2031	Savin Hill Ave	Repave	Not funded	$0	0.81 to 1.09
2031	Heath St	Repave	Not funded	$0	0.80 to 1.09
2032	River St	Repave	Not funded	$0	0.98 to 1.32
2032	Saratoga St	Repave	Funded	$178,173	0.96 to 1.30
2032	Savin Hill Ave	Repave	Funded	$69,268	0.82 to 1.18
2032	Savin Hill Ave	Reline water main	Funded	$77,205	0.82 to 1.18
2032	Tremont St	Repave	Not funded	$0	0.86 to 1.16
2032	Bremen St	Repave	Not funded	$0	0.80 to 1.08
2032	Geneva Ave	Repave	Not funded	$0	0.77 to 1.04

NOT FUNDED, AND WHAT WOULD CHANGE THE ANSWER

Highest-return assets with no funded option. Showing 40 of 4035.

YEAR	STREET	WORK	ASK	REASON
2026	Park St	Replace water main	$0	Return 0.79 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.98 on the work alone).
2026	Bartlett St	Replace water main	$0	Return 0.79 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.35 on the work alone).
2026	Juniper St	Replace water main	$0	Return 0.77 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.43 on the work alone).
2026	Linley Ter	Replace water main	$0	Return 0.77 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.40 on the work alone).
2026	Elm Hill Ave	Replace water main	$0	Return 0.76 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.41 on the work alone).
2026	Marlborough St	Replace water main	$0	Return 0.74 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.56 on the work alone).
2026	Travis St	Replace water main	$0	Return 0.74 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.33 on the work alone).
2026	Glenway St	Replace water main	$0	Return 0.74 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.30 on the work alone).
2026	H St	Replace water main	$0	Return 0.74 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.57 on the work alone).
2026	Tremont St	Replace water main	$0	Return 0.74 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.46 on the work alone).
2026	Wordsworth St	Replace water main	$0	Return 0.73 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.21 on the work alone).
2026	South St	Replace water main	$0	Return 0.73 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.28 on the work alone).
2026	Devonshire St	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.59 on the work alone).
2026	Stillman St	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.43 on the work alone).
2026	Moore St	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.23 on the work alone).
2026	N Harvard St	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.43 on the work alone).
2026	River St	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.35 on the work alone).
2026	Eastland Rd	Replace water main	$0	Return 0.72 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.32 on the work alone).
2026	Commonwealth Ave	Replace water main	$0	Return 0.71 is below the 1.0 hurdle.
2026	Medfield St	Replace water main	$0	Return 0.71 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.34 on the work alone).
2026	New Cypher St	Replace water main	$0	Return 0.71 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.15 on the work alone).
2026	John F. Fitzgerald Surface Rd	Replace water main	$0	Return 0.70 is below the 1.0 hurdle.
2026	Ruskindale Rd	Replace water main	$0	Return 0.70 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.18 on the work alone).
2026	Allston St	Replace water main	$0	Return 0.70 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.24 on the work alone).
2026	Gerard St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.09 on the work alone).
2026	Converse St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.03 on the work alone).
2026	Margaret St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.34 on the work alone).
2026	Colbert St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.20 on the work alone).
2026	Cushing Ave	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.28 on the work alone).
2026	Forest Hills St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.14 on the work alone).
2026	O St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.09 on the work alone).
2026	W Second St	Repave	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.74 on the work alone).
2026	E Eighth St	Replace water main	$0	Return 0.69 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.00 on the work alone).
2026	Barclay Rd	Replace water main	$0	Return 0.68 is below the 1.0 hurdle.

2026	Erie St	Replace water main	$0	Return 0.68 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.26 on the work alone).
2026	Maryknoll St	Replace water main	$0	Return 0.68 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.16 on the work alone).
2026	Hano St	Replace water main	$0	Return 0.68 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.08 on the work alone).
2026	Seaport Blvd	Replace water main	$0	Return 0.68 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.05 on the work alone).
2026	Lawn St	Replace water main	$0	Return 0.68 is below the 1.0 hurdle. Would qualify as part of a shared dig (return 1.19 on the work alone).
2026	Commonwealth Ave	Replace water main	$0	Return 0.68 is below the 1.0 hurdle.

METHODOLOGY: FORMULAS

Return	present value of expected dollar loss removed / gross cost. Options on one asset are chosen by NPV = benefit - gross cost; candidates are ranked by return only when the budget binds.
Failure probability	p(t) = min(1, C x PoF(t) / 100), with C chosen so expected city-wide breaks equal N_target (breaks per mile x network miles).
Dollars per failure	F = emergency multiplier x planned pipe cost + (consequence index / 100) x worst-case social cost. Consequence excludes traffic and direct cost (no double counting).
Pipe benefit	sum over the treatment life of discount(t) x [expected loss before - expected loss after] x F. Reline removes a share of age; replace resets it. Waiting a year raises cost by the inflation rate and loses one year of benefit.
Road benefit	sum of discount(t) x vehicle-miles x [user cost per mile before - after]; user cost per mile = u0 x ((100 - PCR) / 100)^2.
Gross cost	pipe alone = dig + pipe work + repaving penalty; road alone = dig + road work; bundle = one dig + both works (no penalty). Penalty = repave cost x lost years / cycle, lost years = lambda x (cycle - street age).
Shared dig	A bundle wins on NPV when NPV(bundle) > NPV(pipe alone) + NPV(road alone). Each add-on must also clear the hurdle on its own work cost (marginal return).
Uncertainty	Returns are recomputed with the lower and upper pipe failure bounds. A project whose low return is under the hurdle while its high return reaches it is flagged for engineering review.
Priority tiers	Urgency 0.9+ is Tier 1 Urgent (funded first, up to a cap), 0.6 to 0.9 Soon, 0.3 to 0.6 Plan, below 0.3 Monitor.
Financing	Each project is paid from the cheapest source with room within its share and eligibility. Net cost = gross cost x present value of repayments per dollar (interest-free loan 0.811, state revolving loan 0.800, bonds 1.0, rate revenue 1.0). Ranking uses gross cost.
Reserve	Emergency repairs are covered by a reserve sized from the 95th percentile of simulated yearly emergency repair cost, capped as a share of the budget.

METHODOLOGY: INPUTS, STATUS AND RANGE TESTED

Sourced = a document we can cite. Calibrated = fit to real data we can name (none yet). Simulated assumption = a placeholder chosen by the team; the range column says what has been tested.

INPUT	VALUE	STATUS	SOURCE	RANGE TESTED	MEANING
`annual_budget_per_mile`	48000	Simulated assumption	ASSUMPTION	not yet tested	Capital budget per mile of street per year.
`breaks_per_mile_year`	0.3	Simulated assumption	ASSUMPTION	not yet tested	Expected water-main breaks per mile per year (N_target = this x miles). BWSC reports just over 35 failures a year (docs/budget_agent_reference.md); not yet divided by BWSC miles of main.
`proposal_fraction`	0.03	Simulated assumption	ASSUMPTION	not yet tested	Share of segments each agent may propose on.
`central_proposal_fraction`	0.2	Simulated assumption	ASSUMPTION	not yet tested	Share of segments the central planner scans.
`reserve_max_fraction`	0.25	Simulated assumption	ASSUMPTION	0.10 to 0.25 per docs/interfaces.md	Cap on the simulated reserve as a share of the budget.
`reserve_fraction`	0.15	Simulated assumption	ASSUMPTION	0.10 to 0.25 per docs/interfaces.md	Fixed reserve; used only when reserve_mode is fixed.
`urgency_full_prob`	0.3	Simulated assumption	ASSUMPTION	not yet tested	Yearly failure probability that scores urgency 1.0.
`critical_facility_multiplier`	1.25	Simulated assumption	ASSUMPTION	not yet tested	Urgency boost for a critical facility.
`urgent_cap_fraction`	0.5	Simulated assumption	ASSUMPTION	not yet tested	Tier 1 work may use at most this share of the spendable amount.
`urgent_override`	0.9	Simulated assumption	ASSUMPTION	not yet tested	Urgency at or above this is Tier 1 and can be funded below the hurdle.
`min_return`	1.0	Simulated assumption	ASSUMPTION	not yet tested	Return hurdle per dollar.
`dig_fixed`	50000	Simulated assumption	ASSUMPTION	not yet tested	Cost to open one street segment, paid once per opening (evidence_plan.md priority 1).

pipe_per_ft	300	Simulated assumption	ASSUMPTION	not yet tested	Pipe work cost per foot.
repave_per_ft	120	Simulated assumption	ASSUMPTION	not yet tested	Repaving cost per foot.
reline_frac	0.5	Simulated assumption	ASSUMPTION	not yet tested	Relining cost as a share of replacement.
emergency_multiplier	3.0	Simulated assumption	ASSUMPTION	not yet tested	A failure repair costs this multiple of planned replacement.
discount_rate	0.04	Simulated assumption	ASSUMPTION	0.03 to 0.07 per docs/evidence_plan.md	Discount rate.
cost_inflation	0.07	Sourced	MassDOT FY27-31 CIP p.58 (asphalt +40% over five years, about 7% a year)	not yet tested	Cost inflation per year.
department_split	{'pipe': 0.6, 'road': 0.4}	Simulated assumption	ASSUMPTION	not yet tested	Fixed pipe/road shares, isolated baseline only.
c_social_max	500000	Simulated assumption	ASSUMPTION	not yet tested	Dollar cost of a worst-case failure (social cost).
u0	0.3	Simulated assumption	ASSUMPTION	not yet tested	Road user cost, dollars per vehicle-mile at worst condition.
lam	0.3	Simulated assumption	Range 0.06 to 0.6 stated by the team from the literature; value is ASSUMPTION	0.06 to 0.6	Share of pavement life lost per cut.
L	15	Simulated assumption	ASSUMPTION	not yet tested	Resurfacing cycle in years.
H_replace	10	Simulated assumption	ASSUMPTION	not yet tested	Benefit horizon of a replacement, years.
H_reline	7	Simulated assumption	ASSUMPTION	not yet tested	Benefit horizon of a reline, years.
rho	0.6	Simulated assumption	ASSUMPTION	not yet tested	Share of pipe age removed by relining.
H_preserve	5	Simulated assumption	ASSUMPTION	not yet tested	Benefit horizon of pavement preservation.
rho_preserve	0.4	Simulated assumption	ASSUMPTION	not yet tested	Share of pavement age removed by preservation.
preserve_frac	0.25	Simulated assumption	ASSUMPTION	not yet tested	Preservation cost as a share of a repave.
reconstruct_mult	2.0	Simulated assumption	ASSUMPTION	not yet tested	Reconstruction cost as a multiple of a repave.
reconstruct_bonus_years	5	Simulated assumption	ASSUMPTION	not yet tested	Extra years of like-new condition after reconstruction.
pof_band	(0.85, 1.15, 5.0)	Simulated assumption	ASSUMPTION	not yet tested	PoF bounds: x0.85 and x1.15 + 5 (the rubric has no error bar).
road_benefit_band	0.15	Simulated assumption	ASSUMPTION	not yet tested	Road benefit bounds, plus or minus this share.
P_min	40	Simulated assumption	ASSUMPTION	not yet tested	PCR at or below which a road is Failed.
funding_mix	{'bonds': 0.293, 'rate_revenue': 0.303, 'interest_free_loan': 0.211, 'srf_loan': 0.193}	Sourced	BWSC 2024-2026 CIP water program, Table 11 (p.19)	fixed	Share of each year's spendable amount by source.
loan_terms.interest_free_loan	{'rate': 0.0, 'years': 10}	Sourced	BWSC CIP p.18 (MWRA LWSAP, interest-free, 10 years)	fixed	Interest-free loan terms.
loan_terms.srf_loan	{'rate': 0.02, 'years': 25}	Simulated assumption	Term from BWSC CIP p.18 (20 to 30 years, below market); rate 2% and 25 years chosen by the team	not yet tested	State revolving loan terms.
loan_terms.bonds	{'rate': 0.04, 'years': 20}	Simulated assumption	ASSUMPTION	not yet tested	Bond rate and term.
rate_revenue_eligible_work	('replace_pipe', 'reline_pipe', 'repave')	Sourced	BWSC CIP p.17: renewal and replacement, including main relining (docs/budget_agent_reference.md). Relining added by decision; interfaces.md listed replace_pipe and repave only	fixed	Work that rate revenue may pay for.

`era_old`	(1850, 1975, 1905)	Simulated assumption	ASSUMPTION	not yet tested	When pipes were mostly laid, older neighborhoods.
`adt_range`	{'arterial': (10000, 16000), 'collector': (4000, 8000), 'local': (300, 1500)}	Simulated assumption	ASSUMPTION	not yet tested	Traffic range by road class.
`street_network`	real Boston street segments	Sourced	Analyze Boston Street Segments (SAM) + MassDOT Road Inventory (data/SOURCES.md)	fixed	Street geometry, names, lengths, classes (REAL). Everything on and under the streets is simulated.
`reserve_share`	0.25 of budget (cap applied)	Simulated assumption	Derived: 95th percentile of simulated yearly emergency cost ($177,719,292) over 5 pilot seeds = 4.41 of the budget, capped by reserve_max_fraction	cap 0.10 to 0.25 per docs/interfaces.md	Share of the annual capital budget set aside for emergency repairs.